



FLUOR DANIEL GTI

10095639



**ENGINEERING REPORT
GEOTECHNICAL EXPLORATION PROGRAM
SOUTH CAROLINA AQUARIUM PARKING GARAGE
CALHOUN PARK AREA SITE
CHARLESTON, SOUTH CAROLINA**


Prepared for:
The Keenan Company, Inc.
1301 Gervais Street, Suite 600
Columbia, South Carolina 29211-1610

Prepared by:
Fluor Daniel GTI, Inc.
637 Braddock Avenue
East Pittsburgh, Pennsylvania 15112

October 1997


Fluor Daniel GTI Project 01003-0790

Fluor Daniel GTI, Inc.
Prepared by:



Richard A. Yocius
Project Task Manager

Fluor Daniel GTI, Inc.
Reviewed by:



Gregory J. Gromicko, P.E.
Project Manager

CONTENTS

1.0	INTRODUCTION	1
1.1	Site Background and Setting	1
1.2	Objectives	2
2.0	FIELD WORK	3
2.1	Health and Safety	3
2.2	Field Drilling and Sampling Activities	3
2.3	Decontamination Procedures	4
2.4	Material Handling Procedures	4
2.5	Site Restoration	4
3.0	GEOTECHNICAL FINDINGS	
3.1	Summary of Recommendations and Conclusions	5

LIST OF FIGURES

Figure 1 Boring Location Plan

APPENDICES

Appendix A	Daily Tailgate Meeting Logs
Appendix B	Drilling Logs
Appendix C	Field Notes
Appendix D	Report of Geotechnical Exploration



1.0 INTRODUCTION

This Engineering Report has been prepared by Fluor Daniel GTI, Inc. (Fluor Daniel GTI) to present the findings of the Geotechnical Exploration Program (GEP). The GEP was implemented to gain necessary information for construction of the City of Charleston parking garage on a portion of the Calhoun Park Area Site (CPA Site) in the City of Charleston, South Carolina. Fluor Daniel GTI provided an on-site geologist to manage drilling activities conducted by R. Simmons Drilling, Inc. and performed oversight of the geotechnical evaluation performed by SM&E, Inc. The on-site field work was conducted between August 12 through August 23, 1997.

The purpose of this engineering report is to document the performance of the GEP, to demonstrate that the GEP was conducted in accordance with the approved Work Plan prepared by Fluor Daniel GTI, dated June 1997, and present the findings of the geotechnical exploration.

The following sections of this report summarize the background information and the GEP objectives, document the field work which was performed, and present the geotechnical findings.

1.1 Site Background and Setting

The CPA Site encompasses approximately 18 acres on the eastern side of the Charleston Peninsula and is bordered to the north by Charlotte Street, to the west by Washington Street, to the south by Laurens Street, and to the east by Concord Street. The CPA Site is comprised of three main sections: SCE&G's Charlotte Street electrical substation; Calhoun Park; and the former Ansonborough Homes public housing complex. The CPA site is bisected by Calhoun Street which separates the northern portion of the site, comprised of the SCE&G substation and Calhoun Park, from the southern portion of the site, comprised of the former Ansonborough housing complex. The Cooper River is located approximately 500 feet east of the CPA Site.

This GEP focused on the Calhoun Park portion of the CPA Site, which is currently owned by the City of Charleston. Calhoun Park was formerly a public recreational park before it was closed and fenced off in June 1989. Calhoun Park currently includes a former ballfield and concrete surfaced basketball court and an abandoned picnic shelter. Prior to use as a park, the Calhoun Park portion of the CPA Site was used for industrial purposes. In the late 1800's, this area was occupied by the Fernoline Chemical Company and is located adjacent to a former manufactured gas plant (MGP) which operated from the 1850's to the 1950's (RI Report, Fluor Daniel GTI, 1996).

Current plans for the Calhoun Park portion of the CPA Site include the construction of a parking garage to support the parking requirements of the South Carolina Aquarium being constructed on the NPS property and other urban redevelopment projects in the immediate vicinity (FS Report, Fluor Daniel GTI, 1997). The proposed parking garage will consist of a six-level reinforced concrete structure with a

footprint of 180 feet by 365 feet, and is expected to have capacity of approximately 1,100 automobiles. The construction of this structure will require adequate subsurface support. Based on preliminary design information, the column loads for the structure are expected to be in the range of 500 to 1,200 kips. It is anticipated that the elevation of the first garage level will be near present grade.

1.2 Objectives

The purpose of implementing the GEP was to conduct a subsurface investigation to obtain specific geotechnical information from the Calhoun Park property necessary for the design of the parking garage. This geotechnical information was collected during the installation of six (6) borings to a total depth of approximately 77 to 97 feet which were terminated within the Cooper Marl. The specific objectives of this exploration program included:

- The determination of site subsurface conditions and their relationship to load bearing capacity requirements;
- Evaluation of site conditions relative to site preparation; and
- The evaluation of potential foundation design constraints which could potentially effect the construction of the parking garage.

In addition to these geotechnical concerns, the on-site field work was conducted at the CPA Site to satisfy the following environmental concerns:

- The handling of waste material generated from the field activities as investigation derived waste (IDW) and its proper management in accordance with the EPA approved Sampling and Analysis Plan (SAP) (RI/FS Work Plan, Chester, 1993); and
- Completion of intrusive drilling activities during penetration of the upper clay layer and intermediate clay layer in a manner that would not permit groundwater in the upper water-bearing units to contact groundwater in the lower water-bearing units.

The remainder of this Engineering Report discusses how the project objectives were fulfilled while addressing the above environmental concerns.

2.0 FIELD WORK

Fluor Daniel GTI provided an on-site geologist to manage drilling activities conducted by R. Simmons Drilling, Inc. and performed oversight of the geotechnical evaluation performed by SM&E, Inc. The on-site field work was conducted between August 12 through August 23, 1997. Additionally, Mr. Charles Till, US EPA Region IV, performed oversight during implementation of the project from August 12 through August 15, 1997.

2.1 Health and Safety

All field work was conducted in accordance with the site-specific Health and Safety Plan (HASP) submitted as part of the RI/FS Work Plan for the CPA Site (RI/FS Work Plan, Chester, 1993). This plan addressed drilling activities, sampling activities, and waste handling activities. All work was performed by personnel having OSHA 1910 training. A Fluor Daniel GTI representative was present on-site during all drilling activities to ensure that the HASP was followed and that appropriate Fluor Daniel GTI health and safety protocols were implemented. Copies of the Daily Tailgate Meeting Logs are presented in Appendix A.

2.2 Field Drilling and Sampling Activities

Sub-surface conditions, examined during implementation of the GEP, were explored by drilling seven (7) geotechnical exploration test borings (GT-1 through GT-6, and GT-1A) within the footprint of the proposed parking garage structure. Approximate locations of the borings completed at the site are shown on Figure 1 (Boring Location Plan). Boring GT-1 was terminated at 12 feet below ground surface (bgs) due to obstructions. However, the other six (6) borings were drilled to depths ranging from 77 to 97 feet, assuring adequate penetration into the Cooper Formation (locally known as "the marl"). Drilling logs for the borings are presented in Appendix B.

Due to suspected constituent impacts in the shallow water-bearing unit, an outer 8-inch surface casing was installed at each of the six (6) boring locations in the upper clay unit to eliminate the potential for migration of the shallow groundwater to lower water-bearing zones. The casing depth varied from 15 feet (5 borings) to 19 feet (1 boring). The casings were then grouted and allowed to cure for at least 24 hours. The borings were then advanced further and a 4-inch inner surface casing was telescoped through the 8-inch casing. These casings were also installed to isolate groundwater and varied between 57 and 63 feet in depth. The casings were also grouted and allowed to cure for at least 24 hours before the borings were advanced to their termination depth within the Cooper Formation.

Standard Penetration Tests (ASTM DD-1856) and split spoon samples were obtained continuously in the upper 8 to 10-feet of the borings (except GT-2 which was continuously sampled to 16-feet) and at 5-foot intervals thereafter. Field logs of the daily drilling procedures are provided in Appendix C.

2.3 Decontamination Procedures

Appropriate decontamination procedures were followed during drilling activities, as specified in the Sampling and Analysis Plan (SAP) (RI/FS Work Plan, Chester, 1993). Since no samples were collected for analyses of chemical constituents, an abbreviated decontamination procedure was utilized. The following procedures were used for field decontamination of non-dedicated equipment that came into direct contact with the geotechnical samples.

Gross material was removed from the sampling equipment by brushing and rinsing with tap water. Sampling equipment was then washed with non-phosphate detergent (Alconox) and potable water and rinsed with distilled water. The drill rig was decontaminated prior to and after drilling activities.

2.4 Material Handling Procedures

The IDW from the drilling activities was containerized in D.O.T. approved drums. The material generated was visually inspected and screened for volatile organic compounds (VOCs) using a photoionization detection (PID) and classified as it was generated. Additionally, the settled mud slurry, generated during the rotary mud drilling of the deep borings, was inspected and screened in the same manner. The drums containing IDW were labeled, staged on-site, and covered. Final disposition of these drums will be finalized upon determination of guidelines related to the currently pending on-site removal action.

2.5 Site Restoration

After each boring was completed to its total depth, the boring was grouted using a Portland cement/bentonite slurry mixture. The slurry was pumped to the bottom of the boring via a tremmie pipe placed to discharge at the base of the boring. The grout was pumped until all drilling fluid were displaced into the in-place mud pan and the grout returns were observed at the surface. Following placement of the grout, drilling mud was pumped to D.O.T. drums and the mud pan removed. The boring casings were cut off below-grade and the locations were marked with stakes for subsequent surveying.

3.0 GEOTECHNICAL FINDINGS

The subsurface exploration and geotechnical analyses was performed under the direction of Fluor Daniel GTI by SM&E, Inc. in accordance with the preliminary design criteria for the parking garage and appropriate ASTM requirements. The geotechnical findings presented in this report are based on the completion of the soil test borings to depths ranging from 12 to 97-feet bgs.

The analyses and recommendations presented in this report are based, in part, upon the data obtained from the subsurface investigation. The nature and extent of variations between the borings will not become evident until actual construction activities begin. If variations appear evident, the recommendations set forth in this report may require re-evaluation.

Since the Charleston area is within a known seismically active region, earthquake loads are an important part of the design process. Seismic considerations, including the evaluation of a seismic site coefficient, liquefaction analysis, and liquefaction potential, have been performed for the CPA Site during the geotechnical exploration. Based on these considerations, the construction of a deep foundation system bearing in the Cooper Marl is recommended. Additional recommendations and conclusions are presented in the following section.

3.1 Summary of Recommendations and Conclusions

A brief summary of conclusions and recommendations resulting from the completion of the geotechnical exploration is presented below.


- The borings encountered a variety of sand and clay soil strata that varied in consistency and thickness. Four (4) strata are of particular importance were identified and confirmed. These are:
 - 1) From ground surface, a 6 to 10 feet layer of uncontrolled fill (sand with bricks, concrete, wood, etc.) was encountered. The fill characteristics are consistent with previous investigations conducted in the area of Calhoun Park. At boring location GT-1, there was also subsurface debris present, which prevented drilling;
 - 2) Beneath the fill, a thick (typically 35 feet) very soft, highly plasticity clay was encountered. This layer was present at all boring locations and was used to set the upper casings, since this layer is of lower permeability and retards vertical migration of groundwater;
 - 3) Below the upper clay, a sand unit was encountered, generally at a depth of 40 to 45 feet bgs. The unit was present at all deep boring locations; and
 - 4) The final stratum encountered was the Cooper Marl, a soft to hard sandy silt, which was encountered at approximately 80 feet below grade. Borings were advanced into this material at depths ranging from 77 to 97 feet bgs.
- Based on the soil type S_3 encountered during the exploration, a seismic site coefficient (S) of 1.5 is recommended for seismic design. Sand deposits within the fill (upper 6 to 10-feet) and between 45 and 55 feet at the site may liquefy during a seismic event.
- A deep foundation system will be required to support the proposed structure. A foundation system consisting of driven piles (12-inch and 14-inch square prestressed concrete piles and H-piles) was the only option considered.

- The first floor slab, if earth supported without ground modification, may settle 6-inches or more due to the placement of 2-feet of new conventional fill at the site. Options that may be considered to eliminate this settlement include:
 - 1) Structural tie-in of the slab to the piling;
 - 2) Filling of the site with a lightweight fill (or a combination of lightweight and conventional fill) to reduce the load induced by the fill; and
 - 3) Surcharging of the site using flexible asphalt paving in the first floor area with anticipation of future repairs to the asphalt surface due to settlement. Alternatively, a ground modification program could be used to reduce post construction settlement.

A detailed presentation of this summary, which is inclusive of seismic considerations, foundation requirements, soil data, laboratory testing procedures, and consolidation reports, is presented in the *Report of Geotechnical Exploration*, prepared by SM&E, Inc. and is located in Appendix D of this document.



FIGURES





LEGEND

- ⊕ - SHALLOW PIEZOMETER LOCATION
- ⊕ - SHALLOW MONITORING WELL LOCATION
- ⊕ - INTERMEDIATE MONITORING WELL LOCATION
- ⊕ - DEEP MONITORING WELL LOCATION
- - BORING LOCATION
- - FORMER STRUCTURES



FLUOR DANIEL GTI

637 BRADDOCK AVENUE
EAST PITTSBURGH, PA 15112
PHONE: (412) 823-5300
FAX: (412) 824-7215

REV. NO.: DRAWING DATE: 6/09/97 ACAD FILE: 97079024.DWG

BORING LOCATIONS PLANS

CLIENT:

THE KEENAN COMPANY

PM:

G.G.

APPENDIX A
DAILY TAILGATE MEETING LOGS

TAILGATE MEETING FORM

Project Name: SEXY

Date: 8/12/97

Project Number: 010030790

Presented by: EDWIN FOX

Check the Topics/Information Reviewed:

- ☒ safety glasses, hard hat, safety boots
- ☒ site safety plan review and location
- ☐ equipment and machinery familiarization
- ☒ employee Right-To-Know/MSDS location
- ☐ open pits, excavations, and site hazards
- ☐ vehicle safety and driving/road conditions
- ☐ portable tool safety and awareness
- ☒ overhead utility locations and clearance
- ☒ first aid, safety, and PPE location
- ☐ sharp object, rebar, and scrap metal hazards
- ☒ safety is everyone's responsibility
- ☒ latex gloves inner/nitrile gloves outer
- ☐ excavation/trenching inspections/documentation
- ☐ full face respirators with proper cartridges
- ☐ upgrade to level c at FID/PID (___ eV) > ___ ppm
- ☐ work stoppage at FID/PID (___ eV) > ___ ppm, % LEL > 10%

- ☐ slips, trips, and falls
- ☒ directions to hospital
- ☒ anticipated visitors
- ☐ electrical ground fault
- ☐ public safety and fences
- ☐ excavator swing and loading
- ☐ orderly site and housekeeping
- ☒ smoking in designated areas
- ☒ leather gloves for protection
- ☐ effects of the night before
- ☒ vibration related injuries
- ☒ fire extinguisher locations
- ☐ eye wash station locations
- ☒ decontamination procedures

- ☒ daily work scope
- ☐ emergency protocol
- ☐ parking and laydown
- ☐ hot work permits
- ☐ strains and sprains
- ☐ noise hazards
- ☐ no horseplay
- ☒ heat and cold stress
- ☐ backing up hazards
- ☐ accidents are costly
- ☐ dust and vapor control
- ☐ refueling procedures
- ☐ confined space entry
- ☐ flying debris hazards

Discussion/Comments/Follow-up Actions: _____

NAME

SIGNATURE

COMPANY

Mike Armstrong
John Stacker
Charles Cacko
Charles J. Tell
EDWIN FOX

Mike Armstrong
John Stacker
Charles Cacko
Charles J. Tell
Edwin T. Fox

R.S.D
R.S.D
R.S.D
F.P.A.
FLUOR DANIEL GTE

Instructions:

- Conduct a daily safety meeting prior to beginning each day's site activities.
- Complete form by checking off specific topics and/or hazards.
- Obtain signatures from all GTI staff and GTI subcontractors.
- Follow-up on any noted items and document resolution of any action items.

TAILGATE MEETING FORM

Project Name: SCE+G GEOTECH

Date: 8/13/97

Project Number: 016030290

Presented by: EDWIN FOX

Check the Topics/Information Reviewed:

- | | | |
|--|--|--|
| <input checked="" type="checkbox"/> safety glasses, hard hat, safety boots | <input type="checkbox"/> slips, trips, and falls | <input type="checkbox"/> daily work scope |
| <input type="checkbox"/> site safety plan review and location | <input type="checkbox"/> directions to hospital | <input type="checkbox"/> emergency protocol |
| <input type="checkbox"/> equipment and machinery familiarization | <input type="checkbox"/> anticipated visitors | <input type="checkbox"/> parking and laydown |
| <input type="checkbox"/> employee Right-To-Know/MSDS location | <input type="checkbox"/> electrical ground fault | <input type="checkbox"/> hot work permits |
| <input type="checkbox"/> open pits, excavations, and site hazards | <input type="checkbox"/> public safety and fences | <input type="checkbox"/> strains and sprains |
| <input type="checkbox"/> vehicle safety and driving/road conditions | <input type="checkbox"/> excavator swing and loading | <input type="checkbox"/> noise hazards |
| <input type="checkbox"/> portable tool safety and awareness | <input type="checkbox"/> orderly site and housekeeping | <input checked="" type="checkbox"/> no horseplay |
| <input type="checkbox"/> overhead utility locations and clearance | <input type="checkbox"/> smoking in designated areas | <input checked="" type="checkbox"/> heat and cold stress |
| <input type="checkbox"/> first aid, safety, and PPE location | <input type="checkbox"/> leather gloves for protection | <input type="checkbox"/> backing up hazards |
| <input type="checkbox"/> sharp object, rebar, and scrap metal hazards | <input type="checkbox"/> effects of the night before | <input type="checkbox"/> accidents are costly |
| <input checked="" type="checkbox"/> safety is everyone's responsibility | <input type="checkbox"/> vibration related injuries | <input type="checkbox"/> dust and vapor control |
| <input type="checkbox"/> latex gloves inner/nitrile gloves outer | <input type="checkbox"/> fire extinguisher locations | <input type="checkbox"/> refueling procedures |
| <input type="checkbox"/> excavation/trenching inspections/documentation | <input type="checkbox"/> eye wash station locations | <input type="checkbox"/> confined space entry |
| <input type="checkbox"/> full face respirators with proper cartridges | <input type="checkbox"/> decontamination procedures | <input type="checkbox"/> flying debris hazards |
| <input type="checkbox"/> upgrade to level c at: FID/PID (___ eV) > ___ ppm | | |
| <input type="checkbox"/> work stoppage at: FID/PID (___ eV) > ___ ppm, % LEL > 10% | | |

Discussion/Comments/Follow-up Actions:

NAME

SIGNATURE

COMPANY

EDWIN FOX
Chris Lacko
Mike Armstrong
Charles Till
John Spicillick

Edwin T. Fox
Chris Lacko
Mike Armstrong
Charles Till
John Spicillick

FLUOR DANIEL GEOTECH
R.S.D.
R.S.D.
FLUOR
R.S.D.

Instructions:

- Conduct a daily safety meeting prior to beginning each day's site activities.
- Complete form by checking off specific topics and/or hazards.
- Obtain signatures from all GTI staff and GTI subcontractors.
- Follow-up on any noted items and document resolution of any action items.

TAILGATE MEETING FORM

Project Name: SCET G. GEOTECH

Date: 8/14/87

Project Number: 00030790

Presented by: EDWIN FOX

Check the Topics/Information Reviewed:

- | | | |
|---|--|--|
| <input checked="" type="checkbox"/> safety glasses, hard hat, safety boots | <input type="checkbox"/> slips, trips, and falls | <input type="checkbox"/> daily work scope |
| <input type="checkbox"/> site safety plan review and location | <input type="checkbox"/> directions to hospital | <input type="checkbox"/> emergency protocol |
| <input type="checkbox"/> equipment and machinery familiarization | <input type="checkbox"/> anticipated visitors | <input type="checkbox"/> parking and laydown |
| <input type="checkbox"/> employee Right-To-Know/MSDS location | <input type="checkbox"/> electrical ground fault | <input type="checkbox"/> hot work permits |
| <input type="checkbox"/> open pits, excavations, and site hazards | <input type="checkbox"/> public safety and fences | <input type="checkbox"/> strains and sprains |
| <input type="checkbox"/> vehicle safety and driving/road conditions | <input type="checkbox"/> excavator swing and loading | <input type="checkbox"/> noise hazards |
| <input type="checkbox"/> portable tool safety and awareness | <input type="checkbox"/> orderly site and housekeeping | <input type="checkbox"/> no horseplay |
| <input type="checkbox"/> overhead utility locations and clearance | <input type="checkbox"/> smoking in designated areas | <input checked="" type="checkbox"/> heat and cold stress |
| <input type="checkbox"/> first aid, safety, and PPE location | <input type="checkbox"/> leather gloves for protection | <input type="checkbox"/> backing up hazards |
| <input type="checkbox"/> sharp object, rebar, and scrap metal hazards | <input type="checkbox"/> effects of the night before | <input type="checkbox"/> accidents are costly |
| <input checked="" type="checkbox"/> safety is everyone's responsibility | <input type="checkbox"/> vibration related injuries | <input type="checkbox"/> dust and vapor control |
| <input checked="" type="checkbox"/> latex gloves inner/nitrile gloves outer | <input type="checkbox"/> fire extinguisher locations | <input type="checkbox"/> refueling procedures |
| <input type="checkbox"/> excavation/trenching inspections/documentation | <input type="checkbox"/> eye wash station locations | <input type="checkbox"/> confined space entry |
| <input type="checkbox"/> full face respirators with proper cartridges | <input type="checkbox"/> decontamination procedures | <input type="checkbox"/> flying debris hazards |
| <input type="checkbox"/> upgrade to level c at FID/PID (___ eV) > ___ ppm | | |
| <input type="checkbox"/> work stoppage at FID/PID (___ eV) > ___ ppm, % LEL > 10% | | |

Discussion/Comments/Follow-up Actions: POSITIVE NATURE OF COAL TAR

NAME

SIGNATURE

COMPANY

EDWIN FOX
Mike Armstrong
John Skubicki
Chris Larko
Charles Till

Edwin Fox
Mike Armstrong
John Skubicki
Chris Larko
Charles Till

FLUOR DANIEL G&T
R.S.D
R.S.D
R.S.D
EPA

Instructions:

- Conduct a daily safety meeting prior to beginning each day's site activities.
- Complete form by checking off specific topics and/or hazards.
- Obtain signatures from all GTI staff and GTI subcontractors.
- Follow-up on any noted items and document resolution of any action items.

TAILGATE MEETING FORM

Project Name: SEAG EEO-TECH

Date: 8/15/97

Project Number: 010030790

Presented by: EDWIN FOX

Check the Topics/Information Reviewed:

- | | | |
|---|---|--|
| <input checked="" type="checkbox"/> safety glasses, hard hat, safety boots | <input type="checkbox"/> slips, trips, and falls | <input type="checkbox"/> daily work scope |
| <input type="checkbox"/> site safety plan review and location | <input type="checkbox"/> directions to hospital | <input type="checkbox"/> emergency protocol |
| <input type="checkbox"/> equipment and machinery familiarization | <input type="checkbox"/> anticipated visitors | <input type="checkbox"/> parking and laydown |
| <input type="checkbox"/> employee Right-To-Know/MSDS location | <input type="checkbox"/> electrical ground fault | <input type="checkbox"/> hot work permits |
| <input type="checkbox"/> open pits, excavations, and site hazards | <input type="checkbox"/> public safety and fences | <input type="checkbox"/> strains and sprains |
| <input type="checkbox"/> vehicle safety and driving/road conditions | <input type="checkbox"/> excavator swing and loading | <input type="checkbox"/> noise hazards |
| <input type="checkbox"/> portable tool safety and awareness | <input type="checkbox"/> ordinary site and housekeeping | <input type="checkbox"/> no horseplay |
| <input type="checkbox"/> overhead utility locations and clearance | <input type="checkbox"/> smoking in designated areas | <input checked="" type="checkbox"/> heat and cold stress |
| <input type="checkbox"/> first aid, safety, and PPE location | <input type="checkbox"/> leather gloves for protection | <input type="checkbox"/> backing up hazards |
| <input type="checkbox"/> sharp object, rebar, and scrap metal hazards | <input type="checkbox"/> effects of the night before | <input type="checkbox"/> accidents are costly |
| <input checked="" type="checkbox"/> safety is everyone's responsibility | <input type="checkbox"/> vibration related injuries | <input type="checkbox"/> dust and vapor control |
| <input checked="" type="checkbox"/> latex gloves inner/nitrile gloves outer | <input type="checkbox"/> fire extinguisher locations | <input type="checkbox"/> refueling procedures |
| <input type="checkbox"/> excavation/trenching inspections/documentation | <input type="checkbox"/> eye wash station locations | <input type="checkbox"/> confined space entry |
| <input type="checkbox"/> full face respirators with proper cartridges | <input type="checkbox"/> decontamination procedures | <input type="checkbox"/> flying debris hazards |
| <input type="checkbox"/> upgrade to level c at FID/PID (___ eV) > ___ ppm | | |
| <input type="checkbox"/> work stoppage at FID/PID (___ eV) > ___ ppm, % LEL > 10% | | |

Discussion/Comments/Follow-up Actions:

NAME

SIGNATURE

COMPANY

EDWIN FOX
Mike Armstrong
Chris Lacko
John Schickel
Charles Till

Edwin T. Fox
Mike Armstrong
Chris Lacko
John Schickel
Charles Till

FLUOR DANIEL GTI
R.S.D.
R.S.D.
R.S.D.
ETA

Instructions:

- Conduct a daily safety meeting prior to beginning each day's site activities.
- Complete form by checking off specific topics and/or hazards.
- Obtain signatures from all GTI staff and GTI subcontractors.
- Follow-up on any noted items and document resolution of any action items.

TAILGATE MEETING FORM

Project Name: SEFAC

Date: 8/16/97

Project Number: 010030790

Presented by: EDWIN FOX

Check the Topics/Information Reviewed:

- | | | |
|---|---|--|
| <input checked="" type="checkbox"/> safety glasses, hard hat, safety boots | <input type="checkbox"/> slips, trips, and falls | <input type="checkbox"/> daily work scope |
| <input checked="" type="checkbox"/> site safety plan review and location | <input checked="" type="checkbox"/> directions to hospital | <input type="checkbox"/> emergency protocol |
| <input type="checkbox"/> equipment and machinery familiarization | <input type="checkbox"/> anticipated visitors | <input type="checkbox"/> parking and laydown |
| <input type="checkbox"/> employee Right-To-Know/MSDS location | <input type="checkbox"/> electrical ground fault | <input type="checkbox"/> hot work permits |
| <input type="checkbox"/> open pits, excavations, and site hazards | <input type="checkbox"/> public safety and fences | <input type="checkbox"/> strains and sprains |
| <input type="checkbox"/> vehicle safety and driving/road conditions | <input type="checkbox"/> excavator swing and loading | <input type="checkbox"/> noise hazards |
| <input type="checkbox"/> portable tool safety and awareness | <input type="checkbox"/> orderly site and housekeeping | <input type="checkbox"/> no horseplay |
| <input type="checkbox"/> overhead utility locations and clearance | <input type="checkbox"/> smoking in designated areas | <input checked="" type="checkbox"/> heat and cold stress |
| <input checked="" type="checkbox"/> first aid, safety, and PPE location | <input checked="" type="checkbox"/> leather gloves for protection | <input type="checkbox"/> backing up hazards |
| <input type="checkbox"/> sharp object, rebar, and scrap metal hazards | <input type="checkbox"/> effects of the night before | <input type="checkbox"/> accidents are costly |
| <input checked="" type="checkbox"/> safety is everyone's responsibility | <input type="checkbox"/> vibration related injuries | <input type="checkbox"/> dust and vapor control |
| <input type="checkbox"/> latex gloves inner/nitrile gloves outer | <input checked="" type="checkbox"/> fire extinguisher locations | <input type="checkbox"/> refueling procedures |
| <input type="checkbox"/> excavation/trenching inspections/documentation | <input type="checkbox"/> eye wash station locations | <input type="checkbox"/> confined space entry |
| <input type="checkbox"/> full face respirators with proper cartridges | <input checked="" type="checkbox"/> decontamination procedures | <input type="checkbox"/> flying debris hazards |
| <input type="checkbox"/> upgrade to level c at FID/PID (___ eV) > ___ ppm | | |
| <input type="checkbox"/> work stoppage at FID/PID (___ eV) > ___ ppm, % LEL > 10% | | |

Discussion/Comments/Follow-up Actions: _____

NAME	SIGNATURE	COMPANY
EDWIN FOX	<i>Edwin T. Fox</i>	FLUOR DANIEL GTI
Mike Armstrong	<i>Mike Armstrong</i>	R.S.D.
Chris Lacko	<i>Chris Lacko</i>	R.S.D.
GAIL DAUS	<i>Gail Daus</i>	R.S.D.

Instructions:

- Conduct a daily safety meeting prior to beginning each day's site activities.
- Complete form by checking off specific topics and/or hazards.
- Obtain signatures from all GTI staff and GTI subcontractors.
- Follow-up on any noted items and document resolution of any action items.

TAILGATE MEETING FORM

Project Name: SC+G

Date: 8/17/97

Project Number: 016030790

Presented by: EDWIN FOX

Check the Topics/Information Reviewed:

- | | | |
|---|--|--|
| <input checked="" type="checkbox"/> safety glasses, hard hat, safety boots | <input type="checkbox"/> slips, trips, and falls | <input type="checkbox"/> daily work scope |
| <input type="checkbox"/> site safety plan review and location | <input type="checkbox"/> directions to hospital | <input type="checkbox"/> emergency protocol |
| <input type="checkbox"/> equipment and machinery familiarization | <input type="checkbox"/> anticipated visitors | <input type="checkbox"/> parking and laydown |
| <input type="checkbox"/> employee Right-To-Know/MSDS location | <input type="checkbox"/> electrical ground fault | <input type="checkbox"/> hot work permits |
| <input type="checkbox"/> open pits, excavations, and site hazards | <input type="checkbox"/> public safety and fences | <input type="checkbox"/> strains and sprains |
| <input type="checkbox"/> vehicle safety and driving/road conditions | <input type="checkbox"/> excavator swing and loading | <input type="checkbox"/> noise hazards |
| <input type="checkbox"/> portable tool safety and awareness | <input type="checkbox"/> orderly site and housekeeping | <input type="checkbox"/> no horseplay |
| <input type="checkbox"/> overhead utility locations and clearance | <input type="checkbox"/> smoking in designated areas | <input checked="" type="checkbox"/> heat and cold stress |
| <input type="checkbox"/> first aid, safety, and PPE location | <input type="checkbox"/> leather gloves for protection | <input type="checkbox"/> backing up hazards |
| <input type="checkbox"/> sharp object, rebar, and scrap metal hazards | <input type="checkbox"/> effects of the night before | <input type="checkbox"/> accidents are costly |
| <input checked="" type="checkbox"/> safety is everyone's responsibility | <input type="checkbox"/> vibration related injuries | <input type="checkbox"/> dust and vapor control |
| <input type="checkbox"/> latex gloves inner/nitrile gloves outer | <input type="checkbox"/> fire extinguisher locations | <input type="checkbox"/> refueling procedures |
| <input type="checkbox"/> excavation/trenching inspections/documentation | <input type="checkbox"/> eye wash station locations | <input type="checkbox"/> confined space entry |
| <input type="checkbox"/> full face respirators with proper cartridges | <input type="checkbox"/> decontamination procedures | <input type="checkbox"/> flying debris hazards |
| <input type="checkbox"/> upgrade to level c at FID/PID (___ eV) > ___ ppm | | |
| <input type="checkbox"/> work stoppage at FID/PID (___ eV) > ___ ppm, % LEL > 10% | | |

Discussion/Comments/Follow-up Actions: _____

NAME	SIGNATURE	COMPANY
<u>EDWIN FOX</u>	<u>Edwin Fox</u>	<u>FLUOR DANIEL GTI</u>
<u>Mike Armstrong</u>	<u>Mike Armstrong</u>	<u>R.S.D</u>
<u>Chris Laska</u>	<u>Chris Laska</u>	<u>R.S.D</u>
<u>Chad Davis</u>	<u>Chad Davis</u>	<u>R.S.P</u>
_____	_____	_____
_____	_____	_____
_____	_____	_____
_____	_____	_____
_____	_____	_____
_____	_____	_____

Instructions:

- Conduct a daily safety meeting prior to beginning each day's site activities.
- Complete form by checking off specific topics and/or hazards.
- Obtain signatures from all GTI staff and GTI subcontractors.
- Follow-up on any noted items and document resolution of any action items.

TAILGATE MEETING FORM

Project Name: CALHOUN PARK GEO-TECH

Date: 8/18/97

Project Number: 010030790

Presented by: EDWIN FOX

Check the Topics/Information Reviewed:

- | | | |
|---|---|---|
| <input checked="" type="checkbox"/> safety glasses, hard hat, safety boots | <input type="checkbox"/> slips, trips, and falls | <input type="checkbox"/> daily work scope |
| <input type="checkbox"/> site safety plan review and location | <input type="checkbox"/> directions to hospital | <input type="checkbox"/> emergency protocol |
| <input type="checkbox"/> equipment and machinery familiarization | <input type="checkbox"/> anticipated visitors | <input type="checkbox"/> parking and laydown |
| <input type="checkbox"/> employee Right-To-Know/MSDS location | <input type="checkbox"/> electrical ground fault | <input type="checkbox"/> hot work permits |
| <input type="checkbox"/> open pits, excavations, and site hazards | <input type="checkbox"/> public safety and fences | <input type="checkbox"/> strains and sprains |
| <input type="checkbox"/> vehicle safety and driving/road conditions | <input type="checkbox"/> excavator swing and loading | <input type="checkbox"/> noise hazards |
| <input type="checkbox"/> portable tool safety and awareness | <input type="checkbox"/> orderly site and housekeeping | <input type="checkbox"/> no horseplay |
| <input type="checkbox"/> overhead utility locations and clearance | <input checked="" type="checkbox"/> smoking in designated areas | <input type="checkbox"/> heat and cold stress |
| <input type="checkbox"/> first aid, safety, and PPE location | <input type="checkbox"/> leather gloves for protection | <input type="checkbox"/> backing up hazards |
| <input type="checkbox"/> sharp object, rebar, and scrap metal hazards | <input type="checkbox"/> effects of the night before | <input type="checkbox"/> accidents are costly |
| <input checked="" type="checkbox"/> safety is everyone's responsibility | <input type="checkbox"/> vibration related injuries | <input type="checkbox"/> dust and vapor control |
| <input type="checkbox"/> latex gloves inner/nitrile gloves outer | <input type="checkbox"/> fire extinguisher locations | <input type="checkbox"/> refueling procedures |
| <input type="checkbox"/> excavation/trenching inspections/documentation | <input type="checkbox"/> eye wash station locations | <input type="checkbox"/> confined space entry |
| <input type="checkbox"/> full face respirators with proper cartridges | <input type="checkbox"/> decontamination procedures | <input type="checkbox"/> flying debris hazards |
| <input type="checkbox"/> upgrade to level c at FID/PID (___ eV) > ___ ppm | | |
| <input type="checkbox"/> work stoppage at FID/PID (___ eV) > ___ ppm, % LEL > 10% | | |

Discussion/Comments/Follow-up Actions:

NAME

SIGNATURE

COMPANY

EDWIN FOX

Edwin T. Fox

FLUOR DANIEL GTI

Chris Lacko

Chris Lacko

R.S.D.

Mike Armstrong

Mike Armstrong

R.S.D.

GALE DAVIS

Gale Davis

R.S.D.

Instructions:

- Conduct a daily safety meeting prior to beginning each day's site activities.
- Complete form by checking off specific topics and/or hazards.
- Obtain signatures from all GTI staff and GTI subcontractors.
- Follow-up on any noted items and document resolution of any action items.

TAILGATE MEETING FORM

Project Name: SETH GEOTECH

Date: 8/19/97

Project Number: 01003-0790

Presented by: EDWIN FOY

Check the Topics/Information Reviewed:

- | | | |
|---|--|---|
| <input type="checkbox"/> safety glasses, hard hat, safety boots | <input type="checkbox"/> slips, trips, and falls | <input type="checkbox"/> daily work scope |
| <input type="checkbox"/> site safety plan review and location | <input type="checkbox"/> directions to hospital | <input type="checkbox"/> emergency protocol |
| <input type="checkbox"/> equipment and machinery familiarization | <input type="checkbox"/> anticipated visitors | <input type="checkbox"/> parking and laydown |
| <input type="checkbox"/> employee Right-To-Know/MSDS location | <input type="checkbox"/> electrical ground fault | <input type="checkbox"/> hot work permits |
| <input type="checkbox"/> open pits, excavations, and site hazards | <input type="checkbox"/> public safety and fences | <input type="checkbox"/> strains and sprains |
| <input type="checkbox"/> vehicle safety and driving/road conditions | <input type="checkbox"/> excavator swing and loading | <input type="checkbox"/> noise hazards |
| <input type="checkbox"/> portable tool safety and awareness | <input type="checkbox"/> orderly site and housekeeping | <input type="checkbox"/> no horseplay |
| <input type="checkbox"/> overhead utility locations and clearance | <input type="checkbox"/> smoking in designated areas | <input type="checkbox"/> heat and cold stress |
| <input type="checkbox"/> first aid, safety, and PPE location | <input type="checkbox"/> leather gloves for protection | <input type="checkbox"/> backing up hazards |
| <input type="checkbox"/> sharp object, rebar, and scrap metal hazards | <input type="checkbox"/> effects of the night before | <input type="checkbox"/> accidents are costly |
| <input type="checkbox"/> safety is everyone's responsibility | <input type="checkbox"/> vibration related injuries | <input type="checkbox"/> dust and vapor control |
| <input checked="" type="checkbox"/> latex gloves inner/nitrile gloves outer | <input type="checkbox"/> fire extinguisher locations | <input type="checkbox"/> refueling procedures |
| <input type="checkbox"/> excavation/trenching inspections/documentation | <input type="checkbox"/> eye wash station locations | <input type="checkbox"/> confined space entry |
| <input type="checkbox"/> full face respirators with proper cartridges | <input type="checkbox"/> decontamination procedures | <input type="checkbox"/> flying debris hazards |
| <input type="checkbox"/> upgrade to level c at FID/PID (___ eV) > ___ ppm | | |
| <input type="checkbox"/> work stoppage at FID/PID (___ eV) > ___ ppm, % LEL > 10% | | |

Discussion/Comments/Follow-up Actions: _____

NAME

EDWIN FOX
Mike Armstrong
Chris Lacko
GALE DAVIS

SIGNATURE

Edwin Fox
Mike Armstrong
Chris Lacko
Gale Davis

COMPANY

FLUOR DANIEL GTI
R.S.D.C.T.
R.S.D.
R.S.D.

Instructions:

- Conduct a daily safety meeting prior to beginning each day's site activities.
- Complete form by checking off specific topics and/or hazards.
- Obtain signatures from all GTI staff and GTI subcontractors.
- Follow-up on any noted items and document resolution of any action items.

TAILGATE MEETING FORM

Project Name: SCETG

Date: 8/20/97

Project Number: 01003 8790

Presented by: E. Fox

Check the Topics/Information Reviewed:

- | | | |
|---|--|--|
| <input checked="" type="checkbox"/> safety glasses, hard hat, safety boots | <input type="checkbox"/> slips, trips, and falls | <input type="checkbox"/> daily work scope |
| <input type="checkbox"/> site safety plan review and location | <input type="checkbox"/> directions to hospital | <input type="checkbox"/> emergency protocol |
| <input type="checkbox"/> equipment and machinery familiarization | <input type="checkbox"/> anticipated visitors | <input type="checkbox"/> parking and laydown |
| <input type="checkbox"/> employee Right-To-Know/MSDS location | <input type="checkbox"/> electrical ground fault | <input type="checkbox"/> hot work permits |
| <input type="checkbox"/> open pits, excavations, and site hazards | <input type="checkbox"/> public safety and fences | <input type="checkbox"/> strains and sprains |
| <input type="checkbox"/> vehicle safety and driving/road conditions | <input type="checkbox"/> excavator swing and loading | <input type="checkbox"/> noise hazards |
| <input type="checkbox"/> portable tool safety and awareness | <input type="checkbox"/> orderly site and housekeeping | <input type="checkbox"/> no horseplay |
| <input type="checkbox"/> overhead utility locations and clearance | <input type="checkbox"/> smoking in designated areas | <input checked="" type="checkbox"/> heat and cold stress |
| <input type="checkbox"/> first aid, safety, and PPE location | <input type="checkbox"/> leather gloves for protection | <input type="checkbox"/> backing up hazards |
| <input type="checkbox"/> sharp object, rebar, and scrap metal hazards | <input type="checkbox"/> effects of the night before | <input type="checkbox"/> accidents are costly |
| <input checked="" type="checkbox"/> safety is everyone's responsibility | <input type="checkbox"/> vibration related injuries | <input type="checkbox"/> dust and vapor control |
| <input type="checkbox"/> latex gloves inner/nitrile gloves outer | <input type="checkbox"/> fire extinguisher locations | <input type="checkbox"/> refueling procedures |
| <input type="checkbox"/> excavation/trenching inspections/documentation | <input type="checkbox"/> eye wash station locations | <input type="checkbox"/> confined space entry |
| <input type="checkbox"/> full face respirators with proper cartridges | <input type="checkbox"/> decontamination procedures | <input type="checkbox"/> flying debris hazards |
| <input type="checkbox"/> upgrade to level c at FID/PID (___ eV) > ___ ppm | | |
| <input type="checkbox"/> work stoppage at FID/PID (___ eV) > ___ ppm, % LEL > 10% | | |

Discussion/Comments/Follow-up Actions: _____

NAME

SIGNATURE

COMPANY

EDWIN FOX
Mike Armstrong
Chris Lacked
BAILEY DAVIS

Edwin T. Fox
Mike Armstrong
Chris Lacked
Bailey Davis

FLUOR DANIEL GTI
R.S.D.
R.S.D.
R.S.D.

Instructions:

- Conduct a daily safety meeting prior to beginning each day's site activities.
- Complete form by checking off specific topics and/or hazards.
- Obtain signatures from all GTI staff and GTI subcontractors.
- Follow-up on any noted items and document resolution of any action items.

TAILGATE MEETING FORM

Project Name: SETH

Date: 8/21/97

Project Number: 010030790

Presented by: EDWIN FOX

Check the Topics/Information Reviewed:

- | | | |
|--|--|--|
| <input checked="" type="checkbox"/> safety glasses, hard hat, safety boots | <input type="checkbox"/> slips, trips, and falls | <input checked="" type="checkbox"/> daily work scope |
| <input type="checkbox"/> site safety plan review and location | <input type="checkbox"/> directions to hospital | <input type="checkbox"/> emergency protocol |
| <input type="checkbox"/> equipment and machinery familiarization | <input type="checkbox"/> anticipated visitors | <input type="checkbox"/> parking and laydown |
| <input type="checkbox"/> employee Right-To-Know/MSDS location | <input type="checkbox"/> electrical ground fault | <input type="checkbox"/> hot work permits |
| <input type="checkbox"/> open pits, excavations, and site hazards | <input type="checkbox"/> public safety and fences | <input type="checkbox"/> strains and sprains |
| <input type="checkbox"/> vehicle safety and driving/road conditions | <input type="checkbox"/> excavator swing and loading | <input type="checkbox"/> noise hazards |
| <input type="checkbox"/> portable tool safety and awareness | <input type="checkbox"/> orderly site and housekeeping | <input type="checkbox"/> no horseplay |
| <input type="checkbox"/> overhead utility locations and clearance | <input type="checkbox"/> smoking in designated areas | <input checked="" type="checkbox"/> heat and cold stress |
| <input type="checkbox"/> first aid, safety, and PPE location | <input type="checkbox"/> leather gloves for protection | <input type="checkbox"/> backing up hazards |
| <input type="checkbox"/> sharp object, rebar, and scrap metal hazards | <input type="checkbox"/> effects of the night before | <input type="checkbox"/> accidents are costly |
| <input checked="" type="checkbox"/> safety is everyone's responsibility | <input type="checkbox"/> vibration related injuries | <input type="checkbox"/> dust and vapor control |
| <input type="checkbox"/> latex gloves inner/nitrile gloves outer | <input type="checkbox"/> fire extinguisher locations | <input type="checkbox"/> refueling procedures |
| <input type="checkbox"/> excavation/trenching inspections/documentation | <input type="checkbox"/> eye wash station locations | <input type="checkbox"/> confined space entry |
| <input type="checkbox"/> full face respirators with proper cartridges | <input type="checkbox"/> decontamination procedures | <input type="checkbox"/> flying debris hazards |
| <input type="checkbox"/> upgrade to level c at FID/PID (___ eV) > ___ ppm | | |
| <input type="checkbox"/> work stoppage at: FID/PID (___ eV) > ___ ppm, % LEL > 10% | | |

Discussion/Comments/Follow-up Actions:

NAME

SIGNATURE

COMPANY

EDWIN FOX

Edwin T. Fox

FLUOR DANIEL GTI

Mike Armstrong

Mike Armstrong

R.S.D.

Chris Lacko

Chris Lacko

R.S.D.

DALE MALIS

Dale Malis

R.S.D.

Instructions:

- Conduct a daily safety meeting prior to beginning each day's site activities.
- Complete form by checking off specific topics and/or hazards.
- Obtain signatures from all GTI staff and GTI subcontractors.
- Follow-up on any noted items and document resolution of any action items.

TAILGATE MEETING FORM

Project Name: SCETG GBO TECH

Date: 8/22/97

Project Number: 010030790

Presented by: E. FOX

Check the Topics/Information Reviewed:

- | | | |
|---|--|--|
| <input type="checkbox"/> safety glasses, hard hat, safety boots | <input type="checkbox"/> slips, trips, and falls | <input type="checkbox"/> daily work scope |
| <input type="checkbox"/> site safety plan review and location | <input type="checkbox"/> directions to hospital | <input type="checkbox"/> emergency protocol |
| <input type="checkbox"/> equipment and machinery familiarization | <input type="checkbox"/> anticipated visitors | <input type="checkbox"/> parking and laydown |
| <input type="checkbox"/> employee Right-To-Know/MSDS location | <input type="checkbox"/> electrical ground fault | <input type="checkbox"/> hot work permits |
| <input type="checkbox"/> open pits, excavations, and site hazards | <input type="checkbox"/> public safety and fences | <input type="checkbox"/> strains and sprains |
| <input type="checkbox"/> vehicle safety and driving/road conditions | <input type="checkbox"/> excavator swing and loading | <input type="checkbox"/> noise hazards |
| <input type="checkbox"/> portable tool safety and awareness | <input type="checkbox"/> orderly site and housekeeping | <input type="checkbox"/> no horseplay |
| <input type="checkbox"/> overhead utility locations and clearance | <input type="checkbox"/> smoking in designated areas | <input checked="" type="checkbox"/> heat and cold stress |
| <input type="checkbox"/> first aid, safety, and PPE location | <input type="checkbox"/> leather gloves for protection | <input type="checkbox"/> backing up hazards |
| <input type="checkbox"/> sharp object, rebar, and scrap metal hazards | <input type="checkbox"/> effects of the night before | <input type="checkbox"/> accidents are costly |
| <input checked="" type="checkbox"/> safety is everyone's responsibility | <input type="checkbox"/> vibration related injuries | <input type="checkbox"/> dust and vapor control |
| <input checked="" type="checkbox"/> latex gloves inner/nitrile gloves outer | <input type="checkbox"/> fire extinguisher locations | <input type="checkbox"/> refueling procedures |
| <input type="checkbox"/> excavation/trenching inspections/documentation | <input type="checkbox"/> eye wash station locations | <input type="checkbox"/> confined space entry |
| <input type="checkbox"/> full face respirators with proper cartridges | <input type="checkbox"/> decontamination procedures | <input type="checkbox"/> flying debris hazards |
| <input type="checkbox"/> upgrade to level c at FID/PID (___ eV) > ___ ppm | | |
| <input type="checkbox"/> work stoppage at FID/PID (___ eV) > ___ ppm, % LEL > 10% | | |

Discussion/Comments/Follow-up Actions:

NAME

SIGNATURE

COMPANY

EDWIN FOX
MIKE ARMSTRONG
GALE DAVIS

Edwin T. Fox
Mike Armstrong
Gale Davis

FLUOR DANIEL GTI
A.S.D.
A.S.D.

Instructions:

- Conduct a daily safety meeting prior to beginning each day's site activities.
- Complete form by checking off specific topics and/or hazards.
- Obtain signatures from all GTI staff and GTI subcontractors.
- Follow-up on any noted items and document resolution of any action items.

APPENDIX B
DRILLING LOGS

FLUOR DANIEL GTI





Project Geotechnical Borings Owner City of Charleston, SC
 Location Calhoun Park Proj. No. 010030790-02
 Surface Elev. _____ Total Hole Depth 12 ft. Diameter 12 in.
 Top of Casing _____ Water Level Initial 4 ft. Static _____
 Screen: Dia _____ Length _____ Type/Size _____
 Casing: Dia _____ Length _____ Type Sched. 40 PVC
 Fill Material _____ Rig/Core GP-1000
 Drill Co. R. Simmons Drilling Method Mud Rotary
 Driller M. Armstrong Log By E. Fox Date 08/13/97 Permit # _____
 Checked By C. Wingerd License No. _____

See Site Map
For Boring Location

COMMENTS:

Depth (ft.)	Well Completion	PID (ppm)	Sample ID Blow Count/ % Recovery	Graphic Log	USCS Class.	Description (Color, Texture, Structure) Trace < 10%, Little 10% to 20%, Some 20% to 35%, And 35% to 50%
-2						
0						
2						Moderate yellowish brown, medium dense, fine to medium SAND, some silt, moist.
4						Very dark gray, medium dense, silty, fine SAND some organic debris, moist.
6						Olive brown, medium dense, silty, fine SAND, saturated.
8						BRICK and WOOD fragments (FILL).
10						Wood fragments.
12						BRICK and CONCRETE fragments (FILL), pinesol like odor.
14						WOOD fragments (FILL).
16						WOOD fragments and CLAY (FILL).
18						
20						
22						
24						Boring terminated and abandoned at 12 feet.

Drilling Log

FLUOR DANIEL GTI



GT-01A












Project Geotechnical Borings Owner City of Charleston, South Carolina
 Location Calhoun Park Proj. No. 010030790-02
 Surface Elev. _____ Total Hole Depth 82 ft. Diameter 12 in. to 4 in.
 Top of Casing _____ Water Level Initial 4 ft. Static _____
 Screen: Dia _____ Length _____ Type/Size _____
 Casing: Dia 8 in. and 4 in. Length 15 ft. and 58 ft. Type Schedule 40 PVC
 Fill Material _____ Rig/Core GP-1000
 Drill Co. R. Simmons Drilling Method Mud Rotary
 Driller M. Armstrong Log By E. Fox Date 08/20/97 Permit # _____
 Checked By C. Wingerd License No. _____

See Site Map
For Boring Location

COMMENTS:

Depth (ft.)	Well Completion	PID (ppm)	Sample ID Blow Count/ % Recovery	Graphic Log	USCS Class.	Description (Color, Texture, Structure) Trace < 10%, Little 10% to 20%, Some 20% to 35%, And 35% to 50%
-2						
0						
2						Moderate yellowish brown, loose, fine to medium SAND, some silt, trace gravel, moist.
4						Brownish black, wood fragments, moist.
6						Light olive gray, loose, fine SAND, damp. Brownish black, sandy peat, damp to moist.
8						Gray, very loose, clayey, fine to coarse SAND and GRAVEL, saturated, slight pinesol-like odor. Gray, very soft CLAY, wet.
10						
12						
14						
16						Dark greenish gray (5GY4/1), very soft CLAY, trace shell fragments, wet, H ₂ S (rotton egg-like) odor.
18						
20						
22						
24						

Project Geotechnical Borings Owner City of Charleston, South Carolina
 Location Calhoun Park Proj. No. 010030790-02

Depth (ft.)	Well Completion	PID (ppm)	Sample ID Blow Count/ % Recovery	Graphic Log	USCS Class.	Description (Color, Texture, Structure) Trace < 10%, Little 10% to 20%, Some 20% to 35%, And 35% to 50%
24			8 WR			No shell fragments, some organic debris at 25 feet.
26						
28						
30						
32						
34						
36						
38						
40						
42						
44			11 2 3 2 4			Dark greenish gray (5GY4/1), very loose, fine SAND, some clay, saturated.
46						
48						
50						
52						
54						
56						
46			12 7 10 14 17			Medium gray, medium dense, fine to medium SAND, some fine gravel, trace coarse sand.
48						
50						
52						
54						
56						
50			13 3 4 6 7			Dark greenish gray (5GY4/1), medium stiff, fine SAND and CLAY.
52						
54						
56						
52			14 2 2			Dark greenish gray (5GY4/1), loose, clayey, fine SAND.
54						
56						
54			14 2 2			Dark greenish gray (5GY4/1), medium stiff, CLAY and fine SAND, some shell fragments.
56						
56			14 2 2			Dark greenish gray (5GY4/1), soft, silty CLAY, some sand and shell fragments, slightly plastic, wet.





Project Geotechnical Borings

Owner City of Charleston, South Carolina

Location Calhoun Park

Proj. No. 010030790-02

Depth (ft.)	Well Completion	PID (ppm)	Sample ID	Blow Count/ % Recovery	Graphic Log	USCS Class.	Description (Color, Texture, Structure) Trace < 10%, Little 10% to 20%, Some 20% to 35%, And 35% to 50%
56			14	3 5			
58							
60				2 1			Dark greenish gray (5G4/1), very soft, silty CLAY, trace plant fragments.
62			15	2 3			
64							
66			16	3 3 4 6			No recovery
68							
70				3 3 5 7			Dark greenish gray (5G4/1), loose, silty, fine SAND, trace shell fragments, saturated.
72			17				
74							
76			18	2 2 3 6			
78							
80				3 4 5 9			Moderate olive brown, medium stiff, SILT and fine SAND, slightly plastic.
82			19				Boring terminated at 82 feet.
84							
86							
88							



Project GeotTechnical Borings Owner City of Charleston, South Carolina
 Location Calhoun Park Proj. No. 010030790-02
 Surface Elev. _____ Total Hole Depth 97 ft. Diameter 12 in. to 4 in.
 Top of Casing _____ Water Level Initial 2 ft. Static _____
 Screen: Dia _____ Length _____ Type/Size _____
 Casing: Dia 8 in. and 4 in. Length 19 ft. and 62 ft. Type Schedule 40 PVC
 Fill Material _____ Rig/Core GP-1000
 Drill Co. R. Simmons Drilling Method Mud Rotary
 Driller M. Armstrong Log By E. Fox Date 08/12/97 Permit # _____
 Checked By C. Wingerd License No. _____

See Site Map
For Boring Location

COMMENTS:

Depth (ft.)	Well Completion	PID (ppm)	Sample ID Blow Count/ % Recovery	Graphic Log	USCS Class.	Description (Color, Texture, Structure) Trace < 10%, Little 10% to 20%, Some 20% to 35%, And 35% to 50%
-2						
0						Moderate yellowish brown and dark olive gray, loose, fine to medium SAND, some silt and fine gravel, brick fragments, moist.
2			5 50/8"			Brownish black to dark grayish brown, loose, fine to medium SAND, some silt, saturated.
4			2 4			Wood in shoe.
6			7 9			No Recovery, still getting wood in return water.
8			3 2			Dark yellowish brown, very loose, fine SAND, some silt.
10			1			Olive black, sandy PEAT.
12			1/12"			Dark gray, very soft CLAY, some silt.
14			1/12"			
16			1/12"			
18			1/12"			
20			1/12"			
22			1/12"			
24			1/24"			
			9			Shell fragments at 13.5 feet.
			10	WH		Dark greenish gray (5GY4/1), very soft, fine SAND and CLAY, some shell fragments, saturated, H ₂ S (rotten egg-like) odor.



Project GeotTechnical Borings

Owner City of Charleston, South Carolina

Location Calhoun Park

Proj. No. 010030790-02

Depth (ft.)	Well Completion	PID (ppm)	Sample ID Blow Count/ % Recovery	Graphic Log	USCS Class.	Description (Color, Texture, Structure) Trace < 10%, Little 10% to 20%, Some 20% to 35%, And 35% to 50%
24						
26			WH/12" 2 1			Dark greenish gray (5GY4/1), very soft CLAY, some large shell fragments, wet, odor.
28						
30						
32			12 1			
34						
36			WH/8" 1 1/12"			
38						
40						Dark greenish gray (5GY4/1), very soft, CLAY, some fine sand, trace shell fragments.
42			14 3 3 7			Dark greenish gray (5G4/1), soft, fine SAND and CLAY, saturated.
44						
46			15 1 2 3			Dark greenish gray (5G4/1), very loose, clayey, fine SAND.
48						
50						
52			16 5 6 7			Dark greenish gray (5G4/1), medium dense, clayey, fine SAND, little clay.
54						
56			17 3 2			Dark greenish gray (5GY4/1), soft, fine SAND and CLAY. Dark greenish gray (5GY4/1), soft, SILTY and CLAY, trace fine sand, slight plasticity, moist, no odor.



Project GeotTechnical Borings

Owner City of Charleston, South Carolina

Location Calhoun Park

Proj. No. 010030790-02

Depth (ft.)	Well Completion	PID (ppm)	Sample ID Blow Count/ % Recovery	Graphic Log	USCS Class.	Description (Color, Texture, Structure) Trace < 10%, Little 10% to 20%, Some 20% to 35%, And 35% to 50%
56			17	2 4		
58						
60						
62			18	2 2 3 4		
64						
66			19	2 7 8 9		Dark greenish gray (5G4/1), stiff, sandy CLAY, wet.
68						Dark greenish gray (5G4/1), medium dense, clayey, fine to coarse SAND and SHELL FRAGMENTS, saturated.
70						Dark greenish gray (5G4/1), stiff, silty CLAY, trace sand, wet.
72			20	1 2 2 7		Dark greenish gray (5G4/1), soft, CLAY and fine SAND, trace shell fragments, saturated.
74						
76			21	1 3 3 13		Dark greenish gray (5G4/1), loose, fine SAND, some clay.
78						Moderate olive brown (5Y4/4), fine SAND, some silt, wet.
80			22	8 5 8 13		Moderate olive brown (5Y4/4), medium dense, fine SAND and SILT, wet.
82						
84						
86			23	3 3 3 5		
88						



Project Geot Technical Borings

Owner City of Charleston, South Carolina

Location Calhoun Park

Proj. No. 010030790-02

Depth (ft.)	Well Completion	PID (ppm)	Sample ID Blow Count/ % Recovery	Graphic Log	USCS Class.	Description (Color, Texture, Structure) Trace < 10%, Little 10% to 20%, Some 20% to 35%, And 35% to 50%
88			24			Moderate olive brown (5Y4/4), medium dense, fine SAND and SILT, wet.
90						
92						
94						
96						
98			25			Boring terminated at 97 feet.
100						
102						
104						
106						
108						
110						
112						
114						
116						
118						
120						



Project Geotechnical Borings Owner City of Charleston, South Carolina
 Location Calhoun Park Proj. No. 010030790-02
 Surface Elev. _____ Total Hole Depth 77 ft. Diameter 12 in. to 4 in.
 Top of Casing _____ Water Level Initial 4 ft. Static _____
 Screen: Dia _____ Length _____ Type/Size _____
 Casing: Dia 8 in. and 4 in. Length 15 ft. and 62 ft. Type Schedule 40 PVC
 Fill Material _____ Rig/Core GP-1000
 Drill Co. R. Simmons Drilling Method Mud Rotary
 Driller M. Armstrong Log By E. Fox Date 08/20/97 Permit # _____
 Checked By C. Wingerd License No. _____

See Site Map
For Boring Location

COMMENTS:

Depth (ft.)	Well Completion	PID (ppm)	Sample ID Blow Count/ % Recovery	Graphic Log	USCS Class.	Description (Color, Texture, Structure) Trace < 10%, Little 10% to 20%, Some 20% to 35%, And 35% to 50%
-2						
0			5			Dark yellowish orange to moderate yellowish brown, loose, fine SAND, some medium sand and silt, moist.
2			7			
4			10			Light gray CONCRETE, severely weathered.
6			13			Dark olive gray, very soft, gravelly CLAY, some sand and wood fragments, saturated, sheen, odor.
8			4			Dark olive gray, very soft, sandy CLAY, some organic plant matter, saturated, sheen, odor.
10						
12						
14						
16			5	WH		Dark greenish gray (5GY4/1), very soft CLAY, trace fine sand, wet, no sheen or odor.
18						
20			8	WH		Dark greenish gray (5GY4/1), very soft, fine SAND and CLAY, wet.
22						
24						

Project Geotechnical BoringsOwner City of Charleston, South CarolinaLocation Calhoun ParkProj. No. 010030790-02

Depth (ft.)	Well Completion	PID (ppm)	Sample ID Blow Count/ % Recovery	Graphic Log	USCS Class.	Description (Color, Texture, Structure) Trace < 10%, Little 10% to 20%, Some 20% to 35%, And 35% to 50%
24			7			Dark greenish gray (5GY4/1), very soft CLAY, some large shell fragments, trace sand.
26						
28			8			Dark greenish gray (5GY4/1), very soft CLAY, wet.
30						
32			9			
34						
36			10			Dark greenish gray (5GY4/1), very soft, CLAY, trace organic debris.
38						
40			11			Dark greenish gray (5GY4/1), very loose, clayey, fine SAND, saturated.
42						
44			12			Greenish gray (5G6/1), medium dense, clayey, fine SAND.
46						
48			13			Greenish gray (5G6/1), loose, fine to coarse SAND, some gravel.
50						Dark greenish gray (5GY4/1), medium stiff, fine SAND and CLAY, wet.
52						
54						
56						



Project Geotechnical Borings Owner City of Charleston, South Carolina
 Location Calhoun Park Proj. No. 010030790-02
 Surface Elev. _____ Total Hole Depth 97 ft. Diameter 12 in. to 4 in.
 Top of Casing _____ Water Level Initial 1.5 ft. Static _____
 Screen: Dia _____ Length _____ Type/Size _____
 Casing: Dia 8 in. and 4 in. Length 15 ft. and 62 ft. Type Sched. 40 PVC
 Fill Material _____ Rig/Core GP-1000
 Drill Co. R. Simmons Drilling Method Mud Rotary
 Driller M. Armstrong Log By E. Fox Date 08/21/97 Permit # _____
 Checked By C. Wingerd License No. _____

See Site Map
For Boring Location

COMMENTS:

Depth (ft.)	Well Completion	PID (ppm)	Sample ID Blow Count/ % Recovery	Graphic Log	USCS Class.	Description (Color, Texture, Structure) Trace < 10%, Little 10% to 20%, Some 20% to 35%, And 35% to 50%
-2						
0						Dark yellowish brown, loose, fine SAND and SILT, moist to saturated, sheen, odor.
2						Dark olive brown, loose, fine to coarse GRAVEL, some coarse sand, fatty, sheen, odor.
4						Dark olive brown, loose, fine to coarse GRAVEL, some coarse sand and wood chips, some tar, sheen, odor.
6						Olive gray, loose, fine to coarse SAND, some fine to medium gravel, sheen, odor.
8						Olive gray, medium stiff CLAY, wet, odor.
10						
12						
14						
16						Grayish olive, very soft CLAY, H ₂ S (rotten egg-like) odor.
18						
20						Grayish olive, very soft CLAY, some fine sand, odor.
22						
24						



Drilling Log

GT-04

Project Geotechnical Borings

Owner City of Charleston, South Carolina

Location Calhoun Park

Proj. No. 010030790-02

Depth (ft.)	Well Completion	PTD (ppm)	Sample ID Blow Count/ % Recovery	Graphic Log	USCS Class.	Description (Color, Texture, Structure) Trace < 10%, Little 10% to 20%, Some 20% to 35%, And 35% to 50%
24			8	WH		Dark greenish gray (5GY4/1), very soft CLAY, trace roots and shell fragments, faint hydrocarbon odor.
26						
28			9	WH		
30						
32			10	WH		
34						
36			11	WH/12'		
38						
40			12	1		Greenish gray (5GY6/1), very loose, fine SAND, some clay, saturated.
42						
44			13	3		Greenish gray (5G6/1), stiff, sandy CLAY.
46						
48			14	8		Greenish gray (5G6/1), medium dense, fine SAND, some clay.
50						
52			15	13		Dark greenish gray (5GY4/1), medium dense, fine SAND, trace clay, odor.
54						
56			16	9		Olive gray, medium dense, fine to coarse SAND, some fine gravel.

Project Geotechnical BoringsOwner City of Charleston, South CarolinaLocation Calhoun ParkProj. No. 010030790-02

Depth (ft.)	Well Completion	PID (ppm)	Sample ID Blow Count/ % Recovery	Graphic Log	USCS Class.	Description (Color, Texture, Structure) Trace < 10%, Little 10% to 20%, Some 20% to 35%, And 35% to 50%
56			14	4		
58				9		
60				2		
62			15	2		Dark greenish gray (5G4/1), soft, silty CLAY, trace sand and shell fragments, slight plasticity, moist, no odor.
64				2		
66			16	3		Dark greenish gray (5G4/1), soft, silty CLAY, some shell fragments.
68				2		Dark greenish gray (5G4/1), very soft, silty, fine SAND, saturated.
70				4		
72			17	2		Dark greenish gray (5G4/1), medium dense, clayey SILT, some fine sand stringers, slight plasticity, moist.
74				4		
76			18	2		
78				2		
80				4		
82			19	1		Dark greenish gray (5G4/1), loose, silty, fine SAND, some shell fragments, trace medium sand, saturated.
84				2		
86			20	5		Moderate olive brown (5Y4/4), medium stiff, SILT, some sand, slight plasticity, wet.
88				5		



Project Geotechnical Borings Owner City of Charleston, South Carolina
 Location Calhoun Park Proj. No. 010030790-02

Depth (ft.)	Well Completion	PTD (ppm)	Sample ID Blow Count/ % Recovery	Graphic Log	USCS Class.	Description (Color, Texture, Structure) Trace < 10%, Little 10% to 20%, Some 20% to 35%, And 35% to 50%
88			21			Moderate olive brown (5Y4/4), medium stiff, SILT, some sand, slight plasticity, wet.
90						
92						
94						
96						
98						Boring terminated at 97 feet.
100						
102						
104						
106						
108						
110						
112						
114						
116						
118						
120						



Project Geotechnical Borings Owner City of Charleston, South Carolina
 Location Calhoun Park Proj. No. 010030790-02
 Surface Elev. _____ Total Hole Depth 82 ft. Diameter 12 in to 4 in.
 Top of Casing _____ Water Level Initial 2 ft. Static _____
 Screen: Dia _____ Length _____ Type/Size _____
 Casing: Dia 8 in. and 4 in. Length 15 ft. and 63 ft. Type Schedule 40 PVC
 Fill Material _____ Rig/Core GP-1000
 Drill Co. R. Simmons Drilling Method Mud Rotary
 Driller M. Armstrong Log By E. Fox Date 08/21/97 Permit # _____
 Checked By C. Wingerd License No. _____

See Site Map
For Boring Location

COMMENTS:

Depth (ft.)	Well Completion	PID (ppm)	Sample ID Blow Count/ % Recovery	Graphic Log	USCS Class.	Description (Color, Texture, Structure) Trace < 10%, Little 10% to 20%, Some 20% to 35%, And 35% to 50%
-2						
0						
2			1			Moderate yellowish brown, loose, silty, fine SAND, some clay, moist.
4			2			Olive black, loose, silty, fine to coarse SAND and fine GRAVEL, saturated, tarry, sheen, odor.
6			3			Dark olive gray, loose, fine SAND, trace silt, odor, sheen.
8			4			Olive gray, medium dense, silty CLAY, trace fine sand, moist, odor.
10			5			Dark olive gray, loose, clayey, fine to medium SAND, some brick fragments, saturated, slight sheen, odor.
12						Dark olive gray, medium stiff, sandy CLAY, wet, odor.
14						Dark olive gray, very soft CLAY, wet, odor.
16			6	WH		Olive gray (5Y3/2), very soft CLAY, trace sand and shell fragments, wet, H ₂ S (rotten egg-like) odor.
18						
20			7	WH		
22						
24						



Drilling Log

GT-05

Project Geotechnical BoringsOwner City of Charleston, South CarolinaLocation Calhoun ParkProj. No. 010030790-02

Depth (ft.)	Well Completion	PID (ppm)	Sample ID Blow Count/ % Recovery	Graphic Log	USCS Class.	Description (Color, Texture, Structure) Trace < 10%, Little 10% to 20%, Some 20% to 35%, And 35% to 50%
24						
26			8	WH		Dark greenish gray (5GY4/1), very soft CLAY, trace shell fragments, odor.
28						
30						No shell fragments at 30 feet.
32			9	WH		
34						
36			10	1/12" 1/12"		Dark greenish gray (5GY4/1), very soft CLAY, trace fine sand and organic material.
38						
40			11	2 3 WH/12"		Brownish gray, very soft, sandy CLAY, some organic material.
42						Dark greenish gray (5G4/1), very soft, fine SAND and CLAY, trace roots.
44						
46			12	5 4 2 2		
48						
50						Dark greenish gray (5G4/1), medium dense CLAY.
52			13	2 3 4 18		Dark greenish gray (5G4/1), medium stiff, fine SAND and CLAY.
54						Olive gray (5Y4/1), loose, fine SAND, some clay, saturated.
56			14	8 13		Dark greenish gray (5G4/1), dense, fine to coarse SAND, some fine gravel, slight oily sheen, oily coating on bottom 0.2 feet of sample, odor.



Project Geotechnical Borings

Owner City of Charleston, South Carolina

Location Cathoun Park

Proj. No. 010030790-02

Depth (ft.)	Well Completion	PID (ppm)	Sample ID Blow Count/ % Recovery	Graphic Log	USCS Class.	Description (Color, Texture, Structure) Trace < 10%, Little 10% to 20%, Some 20% to 35%, And 35% to 50%
56		14	32 27			
58						
60		15	3 3 8 8			Dark greenish gray (5G4/1), medium stiff, silty CLAY, some shell fragments, slight plasticity, wet, trace staining and odor from 60 to 61 feet.
62						
64		16	2 3 6 8			Dark greenish gray (5G4/1), medium stiff, sandy CLAY, grading to clayey, fine SAND, wet, no odor or staining.
66						
68		17	2 4 5 7			Dark greenish gray (5G4/1), medium stiff CLAY, some fine sand.
70						Dark greenish gray (5G4/1), loose, fine SAND, some clay, trace shell fragments, saturated.
72		18	3 3 4 5			Dark greenish gray (5G4/1), medium dense CLAY and fine SAND, wet.
74						
76		19	2 7 7 8			Moderate olive brown (5Y4/4), stiff, sandy SILT, slight plasticity, wet.
78						
80						Boring terminated at 82 feet.
82						
84						
86						
88						



Drilling Log

GT-06

Project Geotechnical Borings Owner City of Charleston, South Carolina
 Location Cathoun Park Proj. No. 010030790-02
 Surface Elev. _____ Total Hole Depth 92 ft. Diameter 12 in. to 4 in.
 Top of Casing _____ Water Level Initial 2 ft. Static _____
 Screen: Dia _____ Length _____ Type/Size _____
 Casing: Dia 12 in and 4 in. Length 15 ft. and 57 ft. Type Schedule 40 PVC
 Fill Material _____ Rig/Core GP-1000
 Drill Co. R. Simmons Drilling Method Mud Rotary
 Driller M. Armstrong Log By E. Fox Date 08/20/97 Permit # _____
 Checked By C. Wingerd License No. _____



See Site Map
For Boring Location

COMMENTS:

Depth (ft.)	Well Completion	PID (ppm)	Sample ID Blow Count/ % Recovery	Graphic Log	USCS Class.	Description (Color, Texture, Structure) Trace < 10%, Little 10% to 20%, Some 20% to 35%, And 35% to 50%
-2						
0						Moderate brown to dark yellowish orange, loose, SAND and SILT, moist.
2						Olive black, loose, fine SAND, some silt, moist, coal tar-like odor, oily coating. Saturated.
4						Olive gray, medium dense, silty, fine SAND, some brick fragments, odor.
6						Olive gray, loose, fine to coarse SAND and GRAVEL, sheen, odor.
8						Gray, medium stiff, CLAY, wet.
10						No Recovery.
12						Gray, very soft CLAY, wet, no odor.
14						
16						Olive gray, very soft. CLAY, trace sand and organic material, wet, H ₂ S (rotten egg-like) odor.
18						Shelby tube pushed from 18 to 20 feet.
20						
22						
24						







Project Geotechnical Borings Owner City of Charleston, South Carolina
 Location Calhoun Park Proj. No. 010030790-02

Depth (ft.)	Well Completion	PTD (ppm)	Sample ID Blow Count/ % Recovery	Graphic Log	USCS Class.	Description (Color, Texture, Structure) Trace < 10%, Little 10% to 20%, Some 20% to 35%, And 35% to 50%
24						Dark greenish gray (5GY4/1), very soft CLAY, trace sand and organic material, wet, odor.
26						
28						
30						
32						
34						
36						
38						
40						
42						
44						Greenish gray (5GY6/1), medium dense, clayey, fine SAND, saturated.
46						
48						Dark greenish gray (5GY4/1), dense, fine to coarse SAND, some gravel.
50						
52						Dark greenish gray (5GY4/1), very loose, clayey, fine SAND, some shell fragments, wet.
54						
56						Dark greenish gray (5GY4/1), soft CLAY, trace fine sand, slight plasticity, wet.



Project Geotechnical Borings Owner City of Charleston, South Carolina
 Location Calhoun Park Proj. No. 010030790-02

Depth (ft.)	Well Completion	PID (ppm)	Sample ID Blow Count/ % Recovery	Graphic Log	USCS Class.	Description (Color, Texture, Structure) Trace < 10%, Little 10% to 20%, Some 20% to 35%, And 35% to 50%
56			15			
58			3			
60			3			
62			4			Dark greenish gray (5G4/1), loose, clayey, fine SAND, trace shell fragments, little rooted, saturated.
64			5			
66			1			Dark greenish gray (5G4/1), medium stiff, sandy CLAY.
68			4			Dark greenish gray (5G4/1), loose, fine SAND, some clay.
70			5			
72			2			
74			7			Moderate olive brown (5Y4/4), medium dense, silty, fine SAND, wet.
76			10			
78			11			
80			2			Dark greenish gray (5G4/1), loose, fine SAND, some clay, trace shell fragments.
82			3			Dark greenish gray (5G4/1), medium stiff, silty CLAY, trace fine sand.
84			4			
86			4			
88			4			
			5			
			7			Moderate olive brown (5Y4/4), stiff, sandy SILT, slight plasticity.
			17			
			4			
			4			
			4			
			8			



Project Geotechnical Borings

Owner City of Charleston, South Carolina

Location Calhoun Park

Proj. No. 010030790-02

Depth (ft.)	Well Completion	PTD (ppm)	Sample ID Blow Count/ % Recovery	Graphic Log	USCS Class.	Description (Color, Texture, Structure) Trace < 10%, Little 10% to 20%, Some 20% to 35%, And 35% to 50%
88			22			Boring terminated at 92 feet.
90						
92						
94						
96						
98						
100						
102						
104						
106						
108						
110						
112						
114						
116						
118						
120						

APPENDIX C
FIELD NOTES

8/12/77

SUNNY & CLEAR

0700 - 12 HOUR DINNER GET REP EDWIN FOR

ON SITE - UNLOCK GATE BUT GET

IMPEDED OFF BY SKIFFERS

0740 - LEAVE SITE INVESTIGATION OF MURDER

RE PERMANENT

0745 - RETURN TO SITE

CHECK & DOWNS FROM STAIR BUILDING

DIEGO, RAO

0810 - CALL JAMES & W. MURPHY WANT

NOT IN, BUT INFORMED THE PERSON

WHO ANSWERED THE PHONE WE WILL

BEGIN DRILLING ON CATHOLIC PARK

TWO LBS. GROUND. W/ THE SUBSTANCE

FOR EQUIPMENT -

0830 - RETURN TO SITE

CHARLIE TILL (USEFUL) ON SITE

- DRILLERS ARRIVE AS MEET CHARLIE

- DRILLERS DON'T HAVE ANY 8" CASING

SO CALL OFFICE 8" CASING IN SUBSTANCE

0920 - 0940 TAILGATE SAFETY MEETING

0945 - DRILLERS UNLOAD EQUIP

RUN OVER TO SUBSTATION TO GET

8" CASING

1030 - ATTEMPT TO TURN ON MOUNT SIDE OF SITE UNSUCCESSFUL

8/12/77

- CALL M. VACARIO - TALK TO MURRY BREAHA

OR FLECKER (ACQUAINTANCE)

- CALL WATKINS DEPT. LEAVE MESSAGE W/

RICK BIGGERSTADT ABOUT ACCESS TO HYDRO

R.I.L. PUT W/RE NOTIFICATION W/

AT

MURRY

SAID NO INFORMATION AVAILABLE

OFFERED TO GET A LINE SET UP

1130 - SEND DRILLERS TO FIRE STATION WHILE

PTF GOES TO SCENE - LEADS W/RE TO SEE

IF SOMEONE THERE CAN HELP LOCATE

WATER SOURCE - THEY WERE NO HELP

W. MURPHY IS OUT TODAY

1230 - RETURN & DO LUNCH

1330 - BEGIN SAM PLING GT-02

DRILL RIG - GUSPECH GP-1000

DRILL BIT = 12" DIAMETER

1550 - SET CASING @

8/12/77
C-2 1.6
13.5-14.5
12-14 1/12" 1.1 12-13.5 SMA
1514 2.0
13.5-14.5 SHELL FRAGS
13.5-14.5

8-10 1/12" 1/12" SMA
1148 0.3
10-12 1/12" 1/12" SMA
1450 0.3

4-6 2.4-7.9 100 RECOVERY
1408 0.3
6-8 3.2-1.1 6-6.5 IN YEL BRD F SAND, SOME SHT
1433 1.25 6.5-6.6 OL BLK SANDY PEYNT
6.6-8 DK GRAY VERY SOFT (LN)
SOME SILT

2-4 2.2-2.3 BRICK BLK TO DK GRAY (LN)
1336 1.6
14-16 1/12" 1/12" SMA
1530 1.8
17-19 1/24" SMA
1510

(7-10)

9/13/71

SUNDAY + CLAY

0700 - JAMES LAMBERT AND REID - 20' FOR OUSTER

0720 - DEPTER'S OUSTER

0730 - 617 11:20 - THE LARGEST SPERMYMELE

0740 - 617 10' (M. J. J. J.)

0800 - REID IN SHALLOW 617-03

ENCOUNTERED WOOD PILES 2, 1, 5

THOSE ARE 5' ALMOST

0830 - 617

0845 - CREEK (SAND) AND ONE W/ SHAPES

FROM PREVIOUS CORES OF THE

WATER FOR REPTRENE

WATER IS 17' SHAPES SO

LAST PUSH CASING FIRST IS

0850 - 617 10' SAMPLE 617-01 BECAUSE

WIDE TO DECON TUBS + TOOLS

AFTER WORDS

0910 - BEGON SHAPES 617-01

ENCOUNTERED 11' OF WOOD 617-01

ALL 11:15

OF 2.1 SPARKS ODORE - MORE OF THE

11:15 - INFO FOR ME. WE WILL TAKE LUNCH +

THAT HE SHOULD LOOK INTO THE STATUS

OF THE DRUMS

- MIKE SAID HOLE IS CROOKED BECAUSE OF

WOOD

1130 - ALL CINDERELLA + 6. GRAMMA (ADULT)

WORTH THEM OF THE SITUATION W/

617-01 + THAT

W/ MORE DEPTER'S TO

W/ KNOW THE PAGING

- CHIEF THINKS THE ODORE IS FROM THE

WOOD. PETER DISTURB W/EN WAS

HERE

1230 - RETURN TO SITE CHECK EVO

SEE IF M. SHAPES IS 10' W/

617 BRINGS DRUMS +

DECK SHAPES

1245 - DECKERS GO FOR WATER

SP. BEGON CROOKING

1400 - BEGON 617-01A SAMPLING

- 617 617.5'

1430 - DECK 70' 10' AREA TO SET CASING

1447 - SET CASING. PUSHED CASING FROM

10' - 15'

1517 - FINISH GRADING CASING

W/ENUP SITE

MORE TO 617-06

617 H2O

8/13/97

0.2 5.734 BK YEL OR - NO MOD YEL BEN
0.1 1.25
6.7 - 0.3
MOIST
2.4 1.13-4.1 2-2.5 SPA
2 0.7 2.3-2.7 K.T.G.R.Y. LUMBERED
CONCRETE MOIST
4-6 1.1/1.2 BK OR GRAY GRAVELLY CLAY
3 0.125 SOME SHAD + WOOD FRAGS
AFTER HEED, SHEEN, ODOE
6-8 1.3 1/2" DL OR GRAY, VERY SOFT SANDY
CLAY, SOME PILOT MATERIAL
SHT, SHEEN, ODOE

CT. 01

0.2 4.5-8.6 MOD YEL BEN F IN SAND
1.5
2-4 5.10-7.6 2-2.2 2.1/1.1 2.25-4 1.1-1.5 GRAY, SHTY, F.S.M.
MOIST
4-6 8.7-10.15 0.75 4-4.75 GRTOL, BEN, SHTY
F-C SAND, SATURATED
4.75-6 BRCK FRAGS + WOOD
1-2.46 5, SAT
6-6.5 WOOD FRIL MEND
0.75-8 WOOD FRIL MEND BRICK
4. CONCRETE FRAGS, SAT
MOD BENT FRABLE ODOE (LICKS)
ALO SHEEN
8-10 15.7-9.14 1.0
10-12 13-10.12-15 1.5
SHT, SOME CLAY

8/13/57

GT-01A

- 0-2 4.5-6.10
1 1.6 MOD V. BRN F. IN SAND
SOME SILET,
TR. GRAVEL, S. MOIST
- 2-4 10.4-12.2 2-2.8 SAA
2 1.0 2.8-4.1 BRN. BLACK. WOOD FRAGS
MOIST
- 4-6 2.3-4.4 4-4.25 LT OL GRAY, F SAND, DRY
3 1.5 4.25-6 S. BRN BLACK, SILTY
PEAT, DRY TO MOIST
- 6-8 7.1-11.1 6-6.5 SAA
4 2.0 6.5-7.5 GRAY, CLAYEY, F. C
GRAVEL, SAT, S. W. PINE S. ODR
7.5-8 GRAY CLAY, SATY
- 8-10 WH
1 0.5

GT-06

- 0-2 4.3-4.3 8-0.75 MOD BRN TO DK GR
1 1.75 SAWDUST SILET, MOIST
6.75 OL BLACK F. SAND, SOME
SILET, COACT. LK ODR
OLY 2A COACT.
- 2-4 6.7-6.6 SAA, SAT. GR. FRAGS
2 2.0
- 4-6 7.13-8.6 OL GRAY, SILTY, F SAND, BRN
3 1.5 FRAGMENTS SAT, ODR
F. C SAND & GRAVEL
6-8 5.3-6.4 6-7.25 SAA, SILEN
4 2.0 7.25 GRAY CLAY SOME WITE
SILTY W. PINE S, WET,
- 8-10 1.1-1.1 FIF 8/13/57
5 0.0 SAA NO RELOVER
- 10-12 1.1 GRAY CLAY, WET, NO ODR
6 2.0

8/13/77


1640 - FINISH DRILLING TO 10' @ GT-06

1730 - FINISH GRADING & CASING

- 12" BORING TO 10'

- PULLED 8" CASING FROM
10' TO 85'

- GROUT (TREMIED) FROM
10' TO 0'



8/14/71

MOISTLY SUNNY

0100 - 1000 WINDY AT THE RAMP FOR OXIDE

0113 - RECOVERED CASING

0115-0120 - WINDY AT THE RAMP

0125 - RAMP FOR H₂O

0130 - SET UP TO DRILL OUT AT 11:00

CALIBRATION H₂O

FROM 5000 OMS

INITIAL 48 0.80 Y

FINAL 100 7.50 N

CALIBRATION CAS: 10000 (SUBSTANTIAL)

LOT 11: 3-130

0150 - DRY TRENCH, ORGANIC IMPROVEMENTS

0200 - RECOVERED CASING TO 10' TO GET CASING

0205 - 010 FROM

0215 - RECOVERED CASING

0215-0220 - SET UP TO GET DRILLING

0245 - FIRST DRILLING, USE 2 BATCHES

OF CASING - CASING TO 15' AT 02:45

0250 - FIRST CASING W/

0255 - SET UP ON 02:05

0305 - BEGIN DRILLING, SET 05

1000 - FIRST SAMPLING, RAMP OUT HOLE

1030 - FIRST DRILLING TO 11' + SETTING CASING @ 15', PER TO CORRECT

8/14/71

1040 - CLEANUP SITE, SET CASING ALONG RAMP

1100-1130 - SAMPLE SETTING

SET UP TO DRILL

DRILLERS RUN FOR H₂O

1130 - CASING SET UP TO GET TUBES

1240 - SET REVISIONS

SET REVISIONS W/ CASING ON SITE

TO FIGURE OUT WHERE WE W/

GET H₂O

THE LINE SIMPLY 106-THE RHOES

WHILE TRIVOLE WAS DISCONTINUED

BECAUSE OF A WATER LINE BREAK

SERIEY SAID HE WILL HAVE A BACKFLOW

PREVENTION MADE UP TO USE AND

GET H₂O FROM A HOLE

1310-1325 DRILL SET-04 TO 11' DRILL W/ MUD

FROM 8 TO 11' TO PREVENT RAY

CASING TO 15' H₂O

1401 - FINISH DRILLING IN CASING 1305 0.0

1405 - SETUP @ DECON 1310 1.5

1500-1510 DECON - CASING RECOMMENDS 1330 0.8

SOAP W/ STEAM

1610 - DRILLERS RUN TO GET FITTINGS

8/14/77

GTT-05

D-2 2.2.4.1
1.15MOD VEL BRN SIFTY F
SAND, SOME CLAY, HARD2-4 3.5.4.2
0.75DUNE BOILER, SIFTY F-C SAND
+ F-M GRAYEL, SAT, HARDY,
ODOR, SIFTY4-6 5.4.3.3
1.254-4.6 SAA
4.6-6 DK OL GRAY, FINE SAND,
TRACE SILT, SAT, ODR
5-6 OL GRAY, SIFTY CLAY,
TRACE F SAND, MOIST, ODR6-8 5.4.2.2
1.16-6.7 SAA, CLAYEY, F-M SAND,
BRICK FRAGMENTS, SAT, SLIGHT
ODOR6.1-8 SAA, SANDY CLAY, SIFT,
ODOR8-10 1.1.1
0.3

DK OL GRAY CLAY, SAT, ODR

GTT-04


8/14/77

D-2 2.3.7.6
1.7DK YEL BRN, F SAND-SILT
MOIST TO SAT W/ ODR
+ SHEEN2-4 6.4.3.2
0.7DK OL BRN F-C GRAYEL, SOME
COARSE SAND, SAT, HARDY,
ODOR, SHEEN4-6 1.1.2.1
1.254-4.75 SAA
4.75-6 SAA WOOD CHIPS, ODR,
SAT, SOME TAR + SHEEN6-8 4.7.2.1
1.96-7.1 SAA
7.1-7.75 OL GRAY F-C SAND + GRAYEL
SOME F-M GRAYEL, SAT, SHEEN, ODR
7.75-8 OL GRAY CLAY, SAT, ODR8-10 1.1.1
0.75

SAA

2/14/77

1840 - continue in road
1845 - Finish Bridge set up for mud
1848 - small sign up from road
1905 - old bridge built



01/27

SUNNY, HAZY, 100°

0125 - FIRST TEST FOR OIL SPILL

0130 - DEPTH & CAPACITY MEASUREMENTS

0140 - HAD CALCULATION

TIME	DEPTH	CAPACITY	REMARKS
0140	88	750	Y
0150	100	132	NO

0130 - BEGIN REAMING BORING GT-02020

TIME TO PTD

0130 0.0

0140 0.6

0150 0.0

0100 0.4

0130 0.2

0140 0.2

0940 - FINISH SAMPLING TO 62' W/ "RUB"

0945 - BEGIN REAMING BORING TO 62' W/ 8" BIT

GET 1120

1035 - FINISH GETTING WATER

1100 - FINISH REAMING BORING TO 62'

- PULL TOOLS

- PLACE 12" CASING TO 62'

- PREP TO GRIND

1150 - SET & DOWN RIG TO GET DRUMS

THINER

- MIX & CANS GET WATER - 1 TARE CANS

1330 - BEGIN MIXING GROUT - MAKE 1 TARE
BATCH OF GROUT

1400 - FINISH GRINDING & CLEANING OUT
BORING

- USED TOTAL OF 7 DRUMS TO
CONTAIN WASTE GENERATED FROM
2ND CASING INSTALLATION

1412 - BREAK DOWN RIG & MOVE
TO GT-01

1435 - BEGIN SAMPLING GT-01

1640 - FINISH SAMPLING GT-014 TO 57'
PREPARE TO REAM

1720 - FINISH REAMING TO 58' PULL TOOLS

1734 - FINISH PILING CASING (4") TO 58'
CLEANOUT MUD TUB & PREP TO GRIND

1800 - FINISH PILING GROUT
BEGIN CLEAN UP

1830 - DEPART

8/15/47

6-0-62

2-2-34

2.0

2.0

2.0

2.0

2.0

8/15/47 GT 02
 20-22 1014 DARK GRAY, DRY SOFT, FINE SAND
 2.0 A CLAY, SOME ^{WHITE} SHELL FRAGS, SILENT
 20-23 1014 1/2" 2.1 SNA, VERY SOFT CLAY, SOME
 1.9 LARGE LIM OF ^{WHITE} SHELL FRAGS, SILENT
 20-32 1.1 SNA, 0.50 FT CLAY, TRACIE SHELL
 2.0 FRAGS, WET, ODDER
 20-33 1014 1.1 SNA, TRACE DK YEL OR GREEN
 2.0 FRAGS, WET, ODDER
 40-47 1.3-3.7 40-40.3 SNA, SOME ^{TIME} SANDS ^{FR} SHELLS
 1.5 40.5-42 DK GRAY, FINE SAND + CLAY
 547
 45 47 1.1-2.3 SNA CLAY, FINE SAND
 2.0
 50-52 3.0-6.1 DK GRAY SNA TO DK GRAY SNA 56 4/1
 0.75 FINE SAND, LITTLE CLAY, SILENT
 55-57 7.2-2.4 55 SNA, SILENT CLAY, FINE SAND + CLAY
 2.0 55.5-57 SNA, SILENT CLAY, FINE SAND, SILENT
 56.5-57 SNA, SILENT CLAY, NO ODDER

8/15/47

6-0-62

2-2-34

2.0

2.0

2.0

2.0

2.0

8/15/47 GT 02
 20-22 1014 DARK GRAY, DRY SOFT, FINE SAND
 2.0 A CLAY, SOME ^{WHITE} SHELL FRAGS, SILENT
 20-23 1014 1/2" 2.1 SNA, VERY SOFT CLAY, SOME
 1.9 LARGE LIM OF ^{WHITE} SHELL FRAGS, SILENT
 20-32 1.1 SNA, 0.50 FT CLAY, TRACIE SHELL
 2.0 FRAGS, WET, ODDER
 20-33 1014 1.1 SNA, TRACE DK YEL OR GREEN
 2.0 FRAGS, WET, ODDER
 40-47 1.3-3.7 40-40.3 SNA, SOME ^{TIME} SANDS ^{FR} SHELLS
 1.5 40.5-42 DK GRAY, FINE SAND + CLAY
 547
 45 47 1.1-2.3 SNA CLAY, FINE SAND
 2.0
 50-52 3.0-6.1 DK GRAY SNA TO DK GRAY SNA 56 4/1
 0.75 FINE SAND, LITTLE CLAY, SILENT
 55-57 7.2-2.4 55 SNA, SILENT CLAY, FINE SAND + CLAY
 2.0 55.5-57 SNA, SILENT CLAY, FINE SAND, SILENT
 56.5-57 SNA, SILENT CLAY, NO ODDER

8/15/47

GT-01A

15-17

CH. GARDENARY 56Y 4/1 " DEFEY GOTT
CLAY, WET, STICK PEARLS

REMOVED TO C. 0000

20-22

1.1
2.0
SMA

25-27

WRE. SHT. "DO SHOCK FIKAS, SCALE
LEAKERS

30-32

WRE. SMA
2.0

35-37

WRE. SMA
2.0

40-42

2.3 2.11 WRE. GARDENARY (56Y 4/1) FINE SAND
1.4 SOME CLAY

45-47

WRE. 4/1 WRE. GARDENARY 12-14 SAND, SOME
F. 0.75 F. 0.75 GARDENARY 12-14 SAND

50-52

3.4 0.7 50-50.25 WRE. GARDENARY 56Y 4/1
1.5 F. 0.75 4 CLAY

50.25-51.3 SAND CLAYEY, F. SAND
51.3-52 SAND, CLAYEY F. SAND, 5 WRE.
FRANKS

35-37

2.2, 3.5
1.4 2.0

GT-01A

SMA, GARDENARY CLAY, SHT. 1/1
SCALE SAND (SHT. 1/1)

WRE.

2/16/77

SUNNY

- E-BOX CASSETTE
- BRICCEP'S CASSSETTE
- BRICCEP'S SAFETY VIDEOTAPING
- RECORDING MEASUREMENT SAFETY PROGRAM

- LUGGAGE HANDLING WILL ADVANCE BORING
 W/0 USING CORE BIRRELS
 DRILLERS DO NOT HAVE ANY OTHER
 TIPS - THE 2" FISH TAIL
 BIT DRILLERS OUT THE BOTTOM
 THE CHANGE AS OURS

- BACKSE TO CUT-03

- CORRECTION 1100

FROM 5PM CANT

100 71.32 Y

- 1000

0800 BEGINNING SAMPLING CUT-03

TIME 10PM
 0800 0.0
 0800 0.0
 0800 0.0
 0800 0.0
 0800 0.0

2/16/77

1000 FINISH SAMPLING TO 02' SEA LEVEL

MEAN THE BORING

- GET 1120 TUBE BREAK

1047 BEGINNING REINFORCING BORING

- BEGIN 1005 WITH REINFORCING BORING

35 FT

- PLACE 3.3 GAL BARRIERS OF MUD

INTO BORING, REFORCING BORING

RETURN

1130 FINISH REINFORCING BORING, CORRECT

MUD TUB, TUB TO CORRECT

1311 FINISH GROUTING & CORRECTING MUD TUB

USE 8 1/2 DUMPS TO CORRECT MUD TUB

WASTE

1315 1/45 CORRECT

- SET UP ON CUT-06

1500 - BEGIN SAMPLING OF CUT-06

1507 - BEGINNING TUBE FROM 18'-20'

- SET SAMPLE SET FOR 10 MIN BEFORE

FINISHING

TIME	PID	TIME	PID
1515	0.0	1645	0.0
1545	0.0		
1615	0.0		

1705 - FINISH SAMPLING TO 570

8/16/13

5. 10. 11

95-17 10541

DATE RECD COPY (5 day 4/11) VERIFY
SECRET COPY, - (WFO) 15 JAN 68
10571.

2.0	2.0
10/1	2.0
10/1	2.0

ALLI SENESE, 10 F. 1

25.07	1.1.1.
7	0.75

WIKTOROWSKI (S. & J.) USTAY
5017 66th N, BURNING TREE
CHICAGO, ILLINOIS, PRAIRIE SWOOD

2000 2001 2002 2003 2004 2005 2006 2007 2008 2009 2010 2011 2012 2013 2014 2015 2016 2017 2018 2019 2020 2021 2022 2023 2024 2025 2026 2027 2028 2029 2030 2031 2032 2033 2034 2035 2036 2037 2038 2039 2040 2041 2042 2043 2044 2045 2046 2047 2048 2049 2050 2051 2052 2053 2054 2055 2056 2057 2058 2059 2060 2061 2062 2063 2064 2065 2066 2067 2068 2069 2070 2071 2072 2073 2074 2075 2076 2077 2078 2079 2080 2081 2082 2083 2084 2085 2086 2087 2088 2089 2090 2091 2092 2093 2094 2095 2096 2097 2098 2099 2100 2101 2102 2103 2104 2105 2106 2107 2108 2109 2110 2111 2112 2113 2114 2115 2116 2117 2118 2119 2120 2121 2122 2123 2124 2125 2126 2127 2128 2129 2130 2131 2132 2133 2134 2135 2136 2137 2138 2139 2140 2141 2142 2143 2144 2145 2146 2147 2148 2149 2150 2151 2152 2153 2154 2155 2156 2157 2158 2159 2160 2161 2162 2163 2164 2165 2166 2167 2168 2169 2170 2171 2172 2173 2174 2175 2176 2177 2178 2179 2180 2181 2182 2183 2184 2185 2186 2187 2188 2189 2190 2191 2192 2193 2194 2195 2196 2197 2198 2199 2200 2201 2202 2203 2204 2205 2206 2207 2208 2209 2210 2211 2212 2213 2214 2215 2216 2217 2218 2219 2220 2221 2222 2223 2224 2225 2226 2227 2228 2229 2230 2231 2232 2233 2234 2235 2236 2237 2238 2239 2240 2241 2242 2243 2244 2245 2246 2247 2248 2249 2250 2251 2252 2253 2254 2255 2256 2257 2258 2259 2260 2261 2262 2263 2264 2265 2266 2267 2268 2269 2270 2271 2272 2273 2274 2275 2276 2277 2278 2279 2280 2281 2282 2283 2284 2285 2286 2287 2288 2289 2290 2291 2292 2293 2294 2295 2296 2297 2298 2299 2300 2301 2302 2303 2304 2305 2306 2307 2308 2309 2310 2311 2312 2313 2314 2315 2316 2317 2318 2319 2320 2321 2322 2323 2324 2325 2326 2327 2328 2329 2330 2331 2332 2333 2334 2335 2336 2337 2338 2339 2340 2341 2342 2343 2344 2345 2346 2347 2348 2349 2350 2351 2352 2353 2354 2355 2356 2357 2358 2359 2360 2361 2362 2363 2364 2365 2366 2367 2368 2369 2370 2371 2372 2373 2374 2375 2376 2377 2378 2379 2380 2381 2382 2383 2384 2385 2386 2387 2388 2389 2390 2391 2392 2393 2394 2395 2396 2397 2398 2399 2400 2401 2402 2403 2404 2405 2406 2407 2408 2409 2410 2411 2412 2413 2414 2415 2416 2417 2418 2419 2420 2421 2422 2423 2424 2425 2426 2427 2428 2429 2430 2431 2432 2433 2434 2435 2436 2437 2438 2439 2440 2441 2442 2443 2444 2445 2446 2447 2448 2449 2450 2451 2452 2453 2454 2455 2456 2457 2458 2459 2460 2461 2462 2463 2464 2465 2466 2467 2468 2469 2470 2471 2472 2473 2474 2475 2476 2477 2478 2479 2480 2481 2482 2483 2484 2485 2486 2487 2488 2489 2490 2491 2492 2493 2494 2495 2496 2497 2498 2499 2500 2501 2502 2503 2504 2505 2506 2507 2508 2509 2510 2511 2512 2513 2514 2515 2516 2517 2518 2519 2520 2521 2522 2523 2524 2525 2526 2527 2528 2529 2530 2531 2532 2533 2534 2535 2536 2537 2538 2539 2540 2541 2542 2543 2544 2545 2546 2547 2548 2549 2550 2551 2552 2553 2554 2555 2556 2557 2558 2559 2560 2561 2562 2563 2564 2565 2566 2567 2568 2569 2570 2571 2572 2573 2574 2575 2576 2577 2578 2579 2580 2581 2582 2583 2584 2585 2586 2587 2588 2589 2590 2591 2592 2593 2594 2595 2596 2597 2598 2599 2600 2601 2602 2603 2604 2605 2606 2607 2608 2609 2610 2611 2612 2613 2614 2615 2616 2617 2618 2619 2620 2621 2622 2623 2624 2625 2626 2627 2628 2629 2630 2631 2632 2633 2634 2635 2636 2637 2638 2639 2640 2641 2642 2643 2644 2645 2646 2647 2648 2649 2650 2651 2652 2653 2654 2655 2656 2657 2658 2659 2660 2661 2662 2663 2664 2665 2666 2667 2668 2669 2670 2671 2672 2673 2674 2675 2676 2677 2678 2679 2680 2681 2682 2683 2684 2685 2686 2687 2688 2689 2690 2691 2692 2693 2694 2695 2696 2697 2698 2699 2700 2701 2702 2703 2704 2705 2706 2707 2708 2709 2710 2711 2712 2713 2714 2715 2716 2717 2718 2719 2720 2721 2722 2723 2724 2725 2726 2727 2728 2729 2730 2731 2732 2733 2734 2735 2736 2737 2738 2739 2740 2741 2742 2743 2744 2745 2746 2747 2748 2749 2750 2751 2752 2753 2754 2755 2756 2757 2758 2759 2760 2761 2762 2763 2764 2765 2766 2767 2768 2769 2770 2771 2772 2773 2774 2775 2776 2777 2778 2779 2780 2781 2782 2783 2784 2785 2786 2787 2788 2789 2790 2791 2792 2793 2794 2795 2796 2797 2798 2799 2800 2801 2802 2803 2804 2805 2806 2807 2808 2809 2810 2811 2812 2813 2814 2815 2816 2817 2818

5.11.16, 10.1.17, 5.11.17, 10.1.17

35	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----

2011/1, 1000 1000 30 70 30.5'

140. 42 "Kathie"
101 210

5111, Ticker: OXYLXZ, DECEMBER 5

1.1 1.2 1.3 1.4 1.5 1.6 1.7 1.8 1.9 2.0 2.1 2.2 2.3 2.4 2.5 2.6 2.7 2.8 2.9 3.0 3.1 3.2 3.3 3.4 3.5 3.6 3.7 3.8 3.9 4.0 4.1 4.2 4.3 4.4 4.5 4.6 4.7 4.8 4.9 5.0 5.1 5.2 5.3 5.4 5.5 5.6 5.7 5.8 5.9 6.0 6.1 6.2 6.3 6.4 6.5 6.6 6.7 6.8 6.9 7.0 7.1 7.2 7.3 7.4 7.5 7.6 7.7 7.8 7.9 8.0 8.1 8.2 8.3 8.4 8.5 8.6 8.7 8.8 8.9 9.0 9.1 9.2 9.3 9.4 9.5 9.6 9.7 9.8 9.9 10.0 10.1 10.2 10.3 10.4 10.5 10.6 10.7 10.8 10.9 11.0 11.1 11.2 11.3 11.4 11.5 11.6 11.7 11.8 11.9 12.0 12.1 12.2 12.3 12.4 12.5 12.6 12.7 12.8 12.9 13.0 13.1 13.2 13.3 13.4 13.5 13.6 13.7 13.8 13.9 14.0 14.1 14.2 14.3 14.4 14.5 14.6 14.7 14.8 14.9 15.0 15.1 15.2 15.3 15.4 15.5 15.6 15.7 15.8 15.9 16.0 16.1 16.2 16.3 16.4 16.5 16.6 16.7 16.8 16.9 17.0 17.1 17.2 17.3 17.4 17.5 17.6 17.7 17.8 17.9 18.0 18.1 18.2 18.3 18.4 18.5 18.6 18.7 18.8 18.9 19.0 19.1 19.2 19.3 19.4 19.5 19.6 19.7 19.8 19.9 20.0 20.1 20.2 20.3 20.4 20.5 20.6 20.7 20.8 20.9 21.0 21.1 21.2 21.3 21.4 21.5 21.6 21.7 21.8 21.9 22.0 22.1 22.2 22.3 22.4 22.5 22.6 22.7 22.8 22.9 23.0 23.1 23.2 23.3 23.4 23.5 23.6 23.7 23.8 23.9 24.0 24.1 24.2 24.3 24.4 24.5 24.6 24.7 24.8 24.9 25.0 25.1 25.2 25.3 25.4 25.5 25.6 25.7 25.8 25.9 26.0 26.1 26.2 26.3 26.4 26.5 26.6 26.7 26.8 26.9 27.0 27.1 27.2 27.3 27.4 27.5 27.6 27.7 27.8 27.9 28.0 28.1 28.2 28.3 28.4 28.5 28.6 28.7 28.8 28.9 29.0 29.1 29.2 29.3 29.4 29.5 29.6 29.7 29.8 29.9 30.0 30.1 30.2 30.3 30.4 30.5 30.6 30.7 30.8 30.9 31.0 31.1 31.2 31.3 31.4 31.5 31.6 31.7 31.8 31.9 32.0 32.1 32.2 32.3 32.4 32.5 32.6 32.7 32.8 32.9 33.0 33.1 33.2 33.3 33.4 33.5 33.6 33.7 33.8 33.9 34.0 34.1 34.2 34.3 34.4 34.5 34.6 34.7 34.8 34.9 35.0 35.1 35.2 35.3 35.4 35.5 35.6 35.7 35.8 35.9 36.0 36.1 36.2 36.3 36.4 36.5 36.6 36.7 36.8 36.9 37.0 37.1 37.2 37.3 37.4 37.5 37.6 37.7 37.8 37.9 38.0 38.1 38.2 38.3 38.4 38.5 38.6 38.7 38.8 38.9 39.0 39.1 39.2 39.3 39.4 39.5 39.6 39.7 39.8 39.9 40.0 40.1 40.2 40.3 40.4 40.5 40.6 40.7 40.8 40.9 41.0 41.1 41.2 41.3 41.4 41.5 41.6 41.7 41.8 41.9 42.0 42.1 42.2 42.3 42.4 42.5 42.6 42.7 42.8 42.9 43.0 43.1 43.2 43.3 43.4 43.5 43.6 43.7 43.8 43.9 44.0 44.1 44.2 44.3 44.4 44.5 44.6 44.7 44.8 44.9 45.0 45.1 45.2 45.3 45.4 45.5 45.6 45.7 45.8 45.9 46.0 46.1 46.2 46.3 46.4 46.5 46.6 46.7 46.8 46.9 47.0 47.1 47.2 47.3 47.4 47.5 47.6 47.7 47.8 47.9 48.0 48.1 48.2 48.3 48.4 48.5 48.6 48.7 48.8 48.9 49.0 49.1 49.2 49.3 49.4 49.5 49.6 49.7 49.8 49.9 50.0 50.1 50.2 50.3 50.4 50.5 50.6 50.7 50.8 50.9 51.0 51.1 51.2 51.3 51.4 51.5 51.6 51.7 51.8 51.9 52.0 52.1 52.2 52.3 52.4 52.5 52.6 52.7 52.8 52.9 53.0 53.1 53.2 53.3 53.4 53.5 53.6 53.7 53.8 53.9 54.0 54.1 54.2 54.3 54.4 54.5 54.6 54.7 54.8 54.9 55.0 55.1 55.2 55.3 55.4 55.5 55.6 55.7 55.8 55.9 56.0 56.1 56.2 56.3 56.4 56.5 56.6 56.7 56.8 56.9 57.0 57.1 57.2 57.3 57.4 57.5 57.6 57.7 57.8 57.9 58.0 58.1 58.2 58.3 58.4 58.5 58.6 58.7 58.8 58.9 59.0 59.1 59.2 59.3 59.4 59.5 59.6 59.7 59.8 59.9 60.0 60.1 60.2 60.3 60.4 60.5 60.6 60.7 60.8 60.9 61.0 61.1 61.2 61.3 61.4 61.5 61.6 61.7 61.8 61.9 62.0 62.1 62.2 62.3 62.4 62.5 62.6 62.7 62.8 62.9 63.0 63.1 63.2 63.3 63.4 63.5 63.6 63.7 63.8 63.9 64.0 64.1 64.2 64.3 64.4 64.5 64.6 64.7 64.8 64.9 65.0 65.1 65.2 65.3 65.4 65.5 65.6 65.7 65.8 65.9 66.0 66.1 66.2 66.3 66.4 66.5 66.6 66.7 66.8 66.9 67.0 67.1 67.2 67.3 67.4 67.5 67.6 67.7 67.8 67.9 68.0 68.1 68.2 68.3 68.4 68.5 68.6 68.7 68.8 68.9 69.0 69.1 69.2 69.3 69.4 69.5 69.6 69.7 69.8 69.9 70.0 70.1 70.2 70.3 70.4 70.5 70.6 70.7 70.8 70.9 71.0 71.1 71.2 71.3 71.4 71.5 71.6 71.7 71.8 71.9 72.0 72.1 72.2 72.3 72.4 72.5 72.6 72.7 72.8 72.9 73.0 73.1 73.2 73.3 73.4 73.5 73.6 73.7 73.8 73.9 74.0 74.1 74.2 74.3 74.4 74.5 74.6 74.7 74.8 74.9 75.0 75.1 75.2 75.3 75.4 75.5 75.6 75.7 75.8 75.9 76.0 76.1 76.2 76.3 76.4 76.5 76.6 76.7 76.8 76.9 77.0 77.1 77.2 77.3 77.4 77.5 77.6 77.7 77.8 77.9 78.0 78.1 78.2 78.3 78.4 78.5 78.6 78.7 78.8 78.9 79.0 79.1 79.2 79.3 79.4 79.5 79.6 79.7 79.8 79.9 80.0 80.1 80.2 80.3 80.4 80.5 80.6 80.7 80.8 80.9 81.0 81.1 81.2 81.3 81.4 81.5 81.6 81.7 81.8 81.9 82.0 82.1 82.2 82.3 82.4 82.5 82.6 82.7 82.8 82.9 83.0 83.1 83.2 83.3 83.4 83.5 83.6 83.7 83.8 83.9 84.0 84.1 84.2 84.3 84.4 84.5 84.6 84.

4400 604 (561 9/1) 25 58100, 500E
 4400 604 100 58100E 12 500000, 511T
 74001 00000,

30-52	5'9.11.19
12	1.9

50-51 4811 4812 (36 47) 4813 4814
— 4815 4816 4817 4818
51-52 4819 4820 4821 4822 4823 4824 4825 4826 4827 4828 4829 4830 4831 4832 4833 4834 4835 4836 4837 4838 4839 4840 4841 4842 4843 4844 4845 4846 4847 4848 4849 4850 4851 4852 4853 4854 4855 4856 4857 4858 4859 4860 4861 4862 4863 4864 4865 4866 4867 4868 4869 4870 4871 4872 4873 4874 4875 4876 4877 4878 4879 4880 4881 4882 4883 4884 4885 4886 4887 4888 4889 4890 4891 4892 4893 4894 4895 4896 4897 4898 4899 4900 4901 4902 4903 4904 4905 4906 4907 4908 4909 4910 4911 4912 4913 4914 4915 4916 4917 4918 4919 4920 4921 4922 4923 4924 4925 4926 4927 4928 4929 4930 4931 4932 4933 4934 4935 4936 4937 4938 4939 4940 4941 4942 4943 4944 4945 4946 4947 4948 4949 4950 4951 4952 4953 4954 4955 4956 4957 4958 4959 4960 4961 4962 4963 4964 4965 4966 4967 4968 4969 4970 4971 4972 4973 4974 4975 4976 4977 4978 4979 4980 4981 4982 4983 4984 4985 4986 4987 4988 4989 4990 4991 4992 4993 4994 4995 4996 4997 4998 4999 5000

55	57	6.4	4.4
13		1.25	

33-554 SAM F-C SYMB SAMPLE
FGRADUEL SAT.

11/	2.0
20/2	3.3.6.7

SMT₁: SICTY cch₁ SUGALLY PMSI₁
SMT₂: SMT₁ - 451 + EEL2 17.40s

53.4-57 DECEMBER 1944
F. S. A. 1-6 C. 1. 1/1, 100-1

8/16/97

CUT-86

15-17.5 NH OL GRAY (5 1/2) CLAY, TR SAND
 7 2.0 TRACE PLANT & ROOT MATERIAL 1/2
 SAT, BOLDING 0.002

18-20 SHALLOOY TINE

2.0' F.E.C.

20-22 10H SHA

2.0'

25-27 10H DK GRN GRAY (5 1/2 1/1), SHA

9 2.0

30-32 10H SHA

10 2.0

35-37 2.5 7.5 35.35.2 SHA

1 1.7 35.2-37 GRN GRAY (5 1/2 1/1) CLAYEY
 F SAND, SAT

40-42 4.13.14.18 40-40.2 SHA

1.7 1.3 40.2-42 SHA, F SAND GRADING TO
 A FINE TO COARSE SAND, SAT

45-47 18.21.24.27 DK GRN GRAY (5 1/2 1/1) F-C SAND
 1.3 1.0 SOME F GRAVEL

8/16/97

50-52 3.2.3.5 SHA, CLAYEY F SAND, ^{F.C.} ~~F.C.~~ SOME
 14 1.5 SHELL FRAGS. WET

53-57 3.3.3.6 SHA, SHALLOOY FINEST, SILENT
 15 2.0 CLAY, TR F SAND

1.5/21/3

1547-1548

$\text{ANSOXO} \left(\frac{1}{167} \right) X_{(12)} I$ 0.9.9.11

[illegible]

2012-2013 11/11/13 11/11/13

187-06 80 57

„S. 241. 242. 243. 244. 245. 246. 247. 248. 249. 250. 251. 252. 253. 254. 255. 256. 257. 258. 259. 260. 261. 262. 263. 264. 265. 266. 267. 268. 269. 270. 271. 272. 273. 274. 275. 276. 277. 278. 279. 280. 281. 282. 283. 284. 285. 286. 287. 288. 289. 290. 291. 292. 293. 294. 295. 296. 297. 298. 299. 300. 301. 302. 303. 304. 305. 306. 307. 308. 309. 310. 311. 312. 313. 314. 315. 316. 317. 318. 319. 320. 321. 322. 323. 324. 325. 326. 327. 328. 329. 330. 331. 332. 333. 334. 335. 336. 337. 338. 339. 340. 341. 342. 343. 344. 345. 346. 347. 348. 349. 350. 351. 352. 353. 354. 355. 356. 357. 358. 359. 360. 361. 362. 363. 364. 365. 366. 367. 368. 369. 370. 371. 372. 373. 374. 375. 376. 377. 378. 379. 380. 381. 382. 383. 384. 385. 386. 387. 388. 389. 390. 391. 392. 393. 394. 395. 396. 397. 398. 399. 400. 401. 402. 403. 404. 405. 406. 407. 408. 409. 410. 411. 412. 413. 414. 415. 416. 417. 418. 419. 420. 421. 422. 423. 424. 425. 426. 427. 428. 429. 430. 431. 432. 433. 434. 435. 436. 437. 438. 439. 440. 441. 442. 443. 444. 445. 446. 447. 448. 449. 450. 451. 452. 453. 454. 455. 456. 457. 458. 459. 460. 461. 462. 463. 464. 465. 466. 467. 468. 469. 470. 471. 472. 473. 474. 475. 476. 477. 478. 479. 480. 481. 482. 483. 484. 485. 486. 487. 488. 489. 490. 491. 492. 493. 494. 495. 496. 497. 498. 499. 500. 501. 502. 503. 504. 505. 506. 507. 508. 509. 510. 511. 512. 513. 514. 515. 516. 517. 518. 519. 520. 521. 522. 523. 524. 525. 526. 527. 528. 529. 530. 531. 532. 533. 534. 535. 536. 537. 538. 539. 540. 541. 542. 543. 544. 545. 546. 547. 548. 549. 550. 551. 552. 553. 554. 555. 556. 557. 558. 559. 560. 561. 562. 563. 564. 565. 566. 567. 568. 569. 570. 571. 572. 573. 574. 575. 576. 577. 578. 579. 580. 581. 582. 583. 584. 585. 586. 587. 588. 589. 590. 591. 592. 593. 594. 595. 596. 597. 598. 599. 600. 601. 602. 603. 604. 605. 606. 607. 608. 609. 610. 611. 612. 613. 614. 615. 616. 617. 618. 619. 620. 621. 622. 623. 624. 625. 626. 627. 628. 629. 630. 631. 632. 633. 634. 635. 636. 637. 638. 639. 640. 641. 642. 643. 644. 645. 646. 647. 648. 649. 650. 651. 652. 653. 654. 655. 656. 657. 658. 659. 660. 661. 662. 663. 664. 665. 666. 667. 668. 669. 670. 671. 672. 673. 674. 675. 676. 677. 678. 679. 680. 681. 682. 683. 684. 685. 686. 687. 688. 689. 690. 691. 692. 693. 694. 695. 696. 697. 698. 699. 700. 701. 702. 703. 704. 705. 706. 707. 708. 709. 710. 711. 712. 713. 714. 715. 716. 717. 718. 719. 720. 721. 722. 723. 724. 725. 726. 727. 728. 729. 730. 731. 732. 733. 734. 735. 736. 737. 738. 739. 740. 741. 742. 743. 744. 745. 746. 747. 748. 749. 750. 751. 752. 753. 754. 755. 756. 757. 758. 759. 760. 761. 762. 763. 764. 765. 766. 767. 768. 769. 770. 771. 772. 773. 774. 775. 776. 777. 778. 779. 780. 781. 782. 783. 784. 785. 786. 787. 788. 789. 790. 791. 792. 793. 794. 795. 796. 797. 798. 799. 800. 801. 802. 803. 804. 805. 806. 807. 808. 809. 810. 811. 812. 813. 814. 815. 816. 817. 818. 819. 820. 821. 822. 823. 824. 825. 826. 827. 828. 829. 830. 831. 832. 833. 834. 835. 836. 837. 838. 839. 840. 841. 842. 843. 844. 845. 846. 847. 848. 849. 850. 851. 852. 853. 854. 855. 856. 857. 858. 859. 860. 861. 862. 863. 864. 865. 866. 867. 868. 869. 870. 871. 872. 873. 874. 875. 876. 877. 878. 879. 880. 881. 882. 883. 884. 885. 886. 887. 888. 889. 890. 891. 892. 893. 894. 895. 896. 897. 898. 899. 900. 901. 902. 903. 904. 905. 906. 907. 908. 909. 910. 911. 912. 913. 914. 915. 916. 917. 918. 919. 920. 921. 922. 923. 924. 925. 926. 927. 928. 929. 930. 931. 932. 933. 934. 935. 936. 937. 938. 939. 940. 941. 942. 943. 944. 945. 946. 947. 948. 949. 950. 951. 952. 953. 954. 955. 956. 957. 958. 959. 960. 961. 962. 963. 964. 965. 966. 967. 968. 969. 970. 971. 972. 973. 974. 975. 976. 977. 978. 979. 980. 981. 982. 983. 984. 985. 986. 987. 988. 989. 990. 991. 992. 993. 994. 995. 996. 997. 998. 999. 1000. 1001. 1002. 1003. 1004. 1005. 1006. 1007. 1008. 1009. 1010. 1011. 1012. 1013. 1014. 1015. 1016. 1017. 1018. 1019. 1020. 1021. 1022. 1023. 1024. 1025. 1026. 1027. 1028. 1029. 1030. 1031. 1032. 1033. 1034. 1035. 1036. 1037. 1038. 1039. 1040. 1041. 1042. 1043. 1044. 1045. 1046. 1047. 1048. 1

... 2000-01-01

11/10/11
M/1/11
L9142

Y	1955/56	1956/57
732		

0030 - REPAIR WORK
C-706 W/8 "L.B."

7/1/15 9:15 7/1/15 9:15

0.0 0.0 0.0 0.0

0.035

0900 0.0

04.8. 0900 0.0 57" PLATE 1504
TODAY BELIEVING 57" PLATE 1504
TO 57" + PREP TO 57"

UIC - 5000 GPOCIN, 12 1/2" ASIN, 70 SUP. FLO

[illegible]

of 1071 Cl SWIN 7715
- 4' : (1965) T3 10AT 70

most important part of the course

6. DRUMS 1-2011 SUBSISTENCE

03/1 50 50111 V 1.371,

0501 55-11 62 677-05

11/5 . 1916.12.25

28/11/53

71.47
27 May 11.

2.2

1430 0.5

1500

115

1536/2016

1607

1/200 Lutz.it

1305 10271024E

1350 - REFERENCE 55-57' SAMPLE BOTTOM OF
WAS CONTAINED IN 20/25/30/35/40/45/50/55/60/65/70/75/80/85/90/95/100/105/110/115/120/125/130/135/140/145/150/155/160/165/170/175/180/185/190/195/200/205/210/215/220/225/230/235/240/245/250/255/260/265/270/275/280/285/290/295/300/305/310/315/320/325/330/335/340/345/350/355/360/365/370/375/380/385/390/395/400/405/410/415/420/425/430/435/440/445/450/455/460/465/470/475/480/485/490/495/500/505/510/515/520/525/530/535/540/545/550/555/560/565/570/575/580/585/590/595/600/605/610/615/620/625/630/635/640/645/650/655/660/665/670/675/680/685/690/695/700/705/710/715/720/725/730/735/740/745/750/755/760/765/770/775/780/785/790/795/800/805/810/815/820/825/830/835/840/845/850/855/860/865/870/875/880/885/890/895/900/905/910/915/920/925/930/935/940/945/950/955/960/965/970/975/980/985/990/995/1000/1005/1010/1015/1020/1025/1030/1035/1040/1045/1050/1055/1060/1065/1070/1075/1080/1085/1090/1095/1100/1105/1110/1115/1120/1125/1130/1135/1140/1145/1150/1155/1160/1165/1170/1175/1180/1185/1190/1195/1200/1205/1210/1215/1220/1225/1230/1235/1240/1245/1250/1255/1260/1265/1270/1275/1280/1285/1290/1295/1300/1305/1310/1315/1320/1325/1330/1335/1340/1345/1350/1355/1360/1365/1370/1375/1380/1385/1390/1395/1400/1405/1410/1415/1420/1425/1430/1435/1440/1445/1450/1455/1460/1465/1470/1475/1480/1485/1490/1495/1500/1505/1510/1515/1520/1525/1530/1535/1540/1545/1550/1555/1560/1565/1570/1575/1580/1585/1590/1595/1600/1605/1610/1615/1620/1625/1630/1635/1640/1645/1650/1655/1660/1665/1670/1675/1680/1685/1690/1695/1700/1705/1710/1715/1720/1725/1730/1735/1740/1745/1750/1755/1760/1765/1770/1775/1780/1785/1790/1795/1800/1805/1810/1815/1820/1825/1830/1835/1840/1845/1850/1855/1860/1865/1870/1875/1880/1885/1890/1895/1900/1905/1910/1915/1920/1925/1930/1935/1940/1945/1950/1955/1960/1965/1970/1975/1980/1985/1990/1995/2000/2005/2010/2015/2020/2025/2030/2035/2040/2045/2050/2055/2060/2065/2070/2075/2080/2085/2090/2095/2100/2105/2110/2115/2120/2125/2130/2135/2140/2145/2150/2155/2160/2165/2170/2175/2180/2185/2190/2195/2200/2205/2210/2215/2220/2225/2230/2235/2240/2245/2250/2255/2260/2265/2270/2275/2280/2285/2290/2295/2300/2305/2310/2315/2320/2325/2330/2335/2340/2345/2350/2355/2360/2365/2370/2375/2380/2385/2390/2395/2400/2405/2410/2415/2420/2425/2430/2435/2440/2445/2450/2455/2460/2465/2470/2475/2480/2485/2490/2495/2500/2505/2510/2515/2520/2525/2530/2535/2540/2545/2550/2555/2560/2565/2570/2575/2580/2585/2590/2595/2600/2605/2610/2615/2620/2625/2630/2635/2640/2645/2650/2655/2660/2665/2670/2675/2680/2685/2690/2695/2700/2705/2710/2715/2720/2725/2730/2735/2740/2745/2750/2755/2760/2765/2770/2775/2780/2785/2790/2795/2800/2805/2810/2815/2820/2825/2830/2835/2840/2845/2850/2855/2860/2865/2870/2875/2880/2885/2890/2895/2900/2905/2910/2915/2920/2925/2930/2935/2940/2945/2950/2955/2960/2965/2970/2975/2980/2985/2990/2995/3000/3005/3010/3015/3020/3025/3030/3035/3040/3045/3050/3055/3060/3065/3070/3075/3080/3085/3090/3095/3100/3105/3110/3115/3120/3125/3130/3135/3140/3145/3150/3155/3160/3165/3170/3175/3180/3185/3190/3195/3200/3205/3210/3215/3220/3225/3230/3235/3240/3245/3250/3255/3260/3265/3270/3275/3280/3285/3290/3295/3300/3305/3310/3315/3320/3325/3330/3335/3340/3345/3350/3355/3360/3365/3370/3375/3380/3385/3390/3395/3400/3405/3410/3415/3420/3425/3430/3435/3440/3445/3450/3455/3460/3465/3470/3475/3480/3485/3490/3495/3500/3505/3510/3515/3520/3525/3530/3535/3540/3545/3550/3555/3560/3565/3570/3575/3580/3585/3590/3595/3600/3605/3610/3615/3620/3625/3630/3635/3640/3645/3650/3655/3660/3665/3670/3675/3680/3685/3690/3695/3700/3705/3710/3715/3720/3725/3730/3735/3740/3745/3750/3755/3760/3765/3770/3775/3780/3785/3790/3795/3800/3805/3810/3815/3820/3825/3830/3835/3840/3845/3850/3855/3860/3865/3870/3875/3880/3885/3890/3895/3900/3905/3910/3915/3920/3925/3930/3935/3940/3945/3950/3955/3960/3965/3970/3975/3980/3985/3990/3995/4000/4005/4010/4015/4020/4025/4030/4035/4040/4045/4050/4055/4060/4065/4070/4075/4080/4085/4090/4095/4100/4105/4110/4115/4120/4125/4130/4135/4140/4145/4150/4155/4160/4165/4170/4175/4180/4185/4190/4195/4200/4205/4210/4215/4220/4225/4230/4235/4240/4245/4250/4255/4260/4265/4270/4275/4280/4285/4290/4295/4

1400 - Finish shipping to GE, HP, RRP, TO

THE NEW YORK PUBLIC LIBRARY

1600 - 1605 115TH ST NW - 115TH ST NW

五

14.30 - DEPART SMT

8/17/77

CLAYS

13-17 WH 0.6 GRAY (5 Y 3/2) VERY SOFT
20 2.0 CLAY, TENDS SANDS & SHELLS
REMARKS: FINE-GR. SAND

20-22 WH 0.4 CLAY, WHITE
27 2.0

23-27 WH 1.4 GRAY / 5.0 GRAY / 1.0 VERY SOFT
28 0.6 CLAY, WHITE, ROTTEN EGG ODOR

30-32 WH 0.4 SAND, NO SHELLS
31 2.0

35-37 1.1 SHA, TR SAND & ORGANIC MATTER
1.0

40-42 2.3 WH 10-402 GRAY, SANDY CLAY
2.0 SOME ORG. DEBRIS
41 2.0 DARK GRAY (5.0 GRAY) SAND
1.4 CLAY, WET ODOR

45 47 0.4 2.4 SHA
12 1.5

8/27/77

50-52 0.3 4.1 6.0 2.0 CLAY
50-51 0.4 SAND, F. SANDY CLAY
51-52 0.4 GRAY (5.0 GRAY) (F. SAND)
SOME CLAY

53-57 0.13 32.27 1.0
TR. SAND W/ (5.0 GRAY)
SHA, F. C SANDS SOME F.
GRAVEL, SLIGHT OILY SHEEN
BOTTOM 0.2' OF SAND, OILY
CONTAINS W/ NATURAL LEAD
0.05

60-62 3.2 6.8 2.0
SHA, SILTY CLAY, SOME
SHELL FRAGMENTS, SLIGHTLY
TIME STAINING A-ODOR F. FROM 60-61

8/19/77

SUNDAY-1/ET

- 0713 - FDSIT FEE E. FOX ON SITE
HPTP FOR DAY
- 0730 - CALL MOORE DRUMS TO FIND OUT
AVAILABILITY OF DRUMS
THEY WONT HAVE UNTIL 1100
- CALL G. GROMICKO FOR SCHEDULE
- FINISH CENTERLINE THURS. INSTALL
WELCS FRIDAY
- 0745 - DRILLERS ON SITE
- TAILGATE SAFETY MEETING
- WILL SAMPLE GT-04 - IF EXHIBITOR
DATA PLOT WILL STOP UNTIL GET
RESULTS
- 0830 - BEGIN SAMPLING GT-04
1100 CALIBRATION
- | | 7PM | SP/IN | Ø/IN |
|---------|-----|-------|------|
| INITIAL | 94 | 7.32 | N |
| FINAL | 100 | 7.24 | N |
-
- | | TIME | 7PM | TIME | 4PM |
|------|------|------|------|-----|
| 0840 | 0.0 | 1130 | 0.2 | |
| 0900 | 0.2 | 1200 | 0.2 | |
| 0930 | 0.0 | | | |
| 1000 | 0.0 | | | |
- SOME SAMPLES TO BE TAKEN ON RETURN LATER AFTER
EXPLORING THROUGH 25'-27' INTERVAL

- 1020 - FINISH SAMPLING TO 62'
- 1027 - MIKE & CHRIS LEAVE TO WORK ON DENNY HILL
ABOUT STATUS OF THE 4" ROVARS
ETP CALLS ABOUT STATUS OF DRUMS
10-15 DRUMS AVAILABLE OR MORE
DRUMS
- 1055 - GAVE LEAVE TO GET DRUMS
- 1115 - PREP TO REAM AT GT-00 TO 62'
- 1225 - REAM
- 1150 - FINISH REAMING CASING TO 62'
- 1205 - GAVE RETURNED 10-14 MORE DRUMS TO
- PREP TO GROUT
- 1245 - FINISH GROUTING IN CASING
- 1255-1405 LUNCH
- CONTINUE CLEANING UP SITE
- 1430 - FINISH DRUM MARK CUTTINGS
- 1436 - GAVE RETURNED 10/14 MORE DRUMS
- 1440 - ETP CALLS SITE TO GET THE ^{CONTRACT} NAME AND
PHONE # OF FRANK EATON TO SEE IF HE
WOULD HAVE 11 SH. DISCHARGE BITWE COULD
BORROW
- 1500 - DRILLERS BEGIN DIE COU OF ROCKS & RIG
- 1510 - FRANK EATON & BRIMMONSON (SOIL CONSULTANT)
ON SITE TO SEE IF THEY HAVE ANYTHING
WHICH WILL WORK WITH TYPE - NO

8/18/47

GJ-04

15-17 WH GRY OL (56 1/2) VERY SOFT
6 1.0 CLAY, BOTTOM EGG COR.

20-22 WH SHA, SOME F SAND
2 2.0

23-27 WH MEDIUM GR (56 1/2) VERY
8 2.0 SOFT CLAY TRACE ^{FOOTS} ~~2-3 GRAINS~~
FINEST HYDROCARBON DEEP
FACILITRAGE, ~~WATER-REPEL~~

30-32 WH SHA
9 2.0

35-37 WH SHA
10 2.0

40-42 WH 1.2 40-41.8 SHA

11 2.0 41.8-42 SHA, F SAND, SOME CLAY
SHT, FINEST HYDROCARBON COR

45-47 1.5-8.0 45-46.1 (56 1/2) SANDY CLAY, OILY
12 1.65 46.1-47 SHA, FINE SAND, SOME CLAY
SHT, COR.

50-52 18-17-17-23 DK GRAY (56 1/2) F SAND,
13 1.2 TR LIME, COR

55-57 9-12-14-9 OL GR (56 1/2) F SAND,
14 1.0 SOME F GRAVEL, SHA, COR

60-62 2-2-3-5 DK GRAY (56 1/2) SILTY CLAY,
15 2.0 TRACE SAND + SHELL FRAGS, ^{LOFT} ~~THIN~~
MOST, NO COR

8/15/77

1525-1535 BREAK

1540 - GIVE RETURN OF DRUMS

1600 - A MOUTH PERSON

1600 - LONG BREAK

1615 - SET UP TO CONTINUE MOUNDING G-02

1700 - G-02 TO G-01

1752 - END WORK

- G-01 (SAMP) WAS ON SITE
TO PICKUP CHECKY TUBE + CHECK OUT
THE STATUS OF THE PROJECT

DISCUSSED THE DESIRED ^{FINAL} DEPTH OF
THE BORINGS

G-01 - IDENTIFY + SAMPLE TOP OF MARL

G-02 - SAMPLE 20' INTO MARL

G-03 - TOP OF MARL

G-04 - 15' INTO MARL

G-05 - TOP OF MARL

G-06 - 15' INTO MARL

07/10

SURF & HOT

0730 - SURF ONT. WIND

0740 - SURF ONT. WIND

0750 - SURF ONT. WIND

0800 - SURF ONT. WIND

0810 - SURF ONT. WIND

0820 - SURF ONT. WIND

0830 - SURF ONT. WIND

0840 - SURF ONT. WIND

0850 - SURF ONT. WIND

0900 - SURF ONT. WIND

0910 - SURF ONT. WIND

0920 - SURF ONT. WIND

0930 - SURF ONT. WIND

0940 - SURF ONT. WIND

0950 - SURF ONT. WIND

1000 - SURF ONT. WIND

0945 - SURF ONT. WIND

0955 - SURF ONT. WIND

1005 - SURF ONT. WIND

1015 - SURF ONT. WIND

1025 - SURF ONT. WIND

1035 - SURF ONT. WIND

11:50 - FREQUENT 80-82' SHALLOW TIDE, 80-82'

12:00 - SURF ONT. WIND

13:10 - SURF ONT. WIND

13:20 - SURF ONT. WIND

14:00 - SURF ONT. WIND

14:10 - SURF ONT. WIND

14:20 - SURF ONT. WIND

14:30 - SURF ONT. WIND

15:30 - SURF ONT. WIND

16:00 - SURF ONT. WIND

16:10 - SURF ONT. WIND

16:20 - SURF ONT. WIND

16:30 - SURF ONT. WIND

16:40 - SURF ONT. WIND

16:50 - SURF ONT. WIND

17:00 - SURF ONT. WIND

17:10 - SURF ONT. WIND

17:20 - SURF ONT. WIND

17:30 - SURF ONT. WIND

17:40 - SURF ONT. WIND

17:50 - SURF ONT. WIND

18:00 - SURF ONT. WIND

18:10 - SURF ONT. WIND

18:20 - SURF ONT. WIND

18:30 - SURF ONT. WIND

18:40 - SURF ONT. WIND

18:50 - SURF ONT. WIND

19:00 - SURF ONT. WIND

19:10 - SURF ONT. WIND

19:20 - SURF ONT. WIND

19:30 - SURF ONT. WIND

19:40 - SURF ONT. WIND

19:50 - SURF ONT. WIND

20:00 - SURF ONT. WIND

20:10 - SURF ONT. WIND

20:20 - SURF ONT. WIND

20:30 - SURF ONT. WIND

6/19/50

67-01

65-62 2.2.5.7 BR BRNDRY (6.4/11) SANDY CLAY, WET
 16 2.0 63.7.16.83 SH, FINE SAND +
 SHITLE FINE SANDS SHIT
 66.83 41 SH, SUTTY CLAY, BR SAND, WET
 70-72 1.2.3.6 SH, FINE SHAD, YR. SMEL
 20 2.0 1.2.3.6, SHIT
 75-77 1.3.5.13 75 W.3 SH, F. SHAD, SOME CLAY
 21 2.0 74.5.77. MOD. OR BRN. (5.4/14)
 F. SHAD SOME SHIT (MARL)
 80-82 6.5.8.13 SH, F. SHAD + SHIT
 21 1.0
 85-87 3.3.3.3 SH, F. SHAD,
 23 2.0
 90-92 2.3.5.6 SH, F. SHAD + SHIT
 24 2.0
 95-97 2.2.2.1 SH
 25 2.0

67-01A

60-62 2.1.2.3 BR BRNDRY (6.4/11) SUTTY CLAY
 15 2.0 FINE PLAIN MARL
 65-67 3.3.4.6 N/A FINE CLAY
 16 0.0
 70-72 3.3.5.7 SHIT (6.4/11) SUTTY, F. SHAD
 17 0.7 SHIT (6.4/11) SHIT (6.4/11) SHIT (6.4/11)
 75-77 2.2.3.6 SH
 18 2.0
 80-82 3.4.5.14 MOD. OR BRN. SUTTY PLAIN
 19 1.4 SHIT + F. SHAD TO SHIT SHIT
 (MARL)

8/11/72

SUNNY + WINDY

0700 - ABOUT 1000 YDS. FOX GROUND

0715 - ABOUT 1000 YDS. FOX GROUND

0730 - ABOUT 1000 YDS. FOX GROUND

0745 - ABOUT 1000 YDS. FOX GROUND

0800 - ROAD ROUNDS INTO HOLE + ALONGSIDE
TO 80'

0805 - TRAIL CONNECTING 80-82 SAMPLE FROM AREA
805

0810 - ABOUT 1000 YDS
0815 - ABOUT 1000 YDS

0820 - ABOUT 1000 YDS. FOX GROUND

0830 - ABOUT 1000 YDS. FOX GROUND

0840 - ABOUT 1000 YDS. FOX GROUND

0850 - ABOUT 1000 YDS. FOX GROUND

0900 - ABOUT 1000 YDS. FOX GROUND

0910 - ABOUT 1000 YDS. FOX GROUND

0920 - ABOUT 1000 YDS. FOX GROUND

1300 SET UP ON CAT 06 + 1300 SAMPLE

1515 - SET UP STEPS HOLE + 1515

1530 - SET UP STEPS HOLE + 1530

1635 - COLLECT 16-9215 FROM CAT-06

1640 - COLLECT 16-9215 FROM CAT-06

1645 - COLLECT 16-9215 FROM CAT-06

1650 - COLLECT 16-9215 FROM CAT-06

1700 - ABOUT 1000 YDS. FOX GROUND

1710 - ABOUT 1000 YDS. FOX GROUND

1720 - ABOUT 1000 YDS. FOX GROUND

1730 - ABOUT 1000 YDS. FOX GROUND

1740 - ABOUT 1000 YDS. FOX GROUND

8/20/47

LT-03

65-67 4.0-5.5 dk GRN GRAY (SG 4/1) SLIGHTLY
15 0.25 PLASTIC SILTY CLAY

70-72 3.4-2.4 70-71.35 Silt, CLAYEN, F-C SAND
16 2.0 SOME SHELL FRAGS, Silt

71.35-72 Silt, CLAYEN, F SAND, Silt
BOTTOM EGG ODD FOR LIXIE SAMPLE

75-77 8.1-2.10 15 76.25 Silt

17 2.0 76.25-77 MOD. OL. BRN, SLIGHTLY PLASTIC
SANDY SILT (MIX)

LT-06

60-62 3.5-4.5 dk GRN GRAY (SG 4/1), CLAYEN
16 1.4 F SAND, TR. SHELL FRAGS,
ROOTED, SAT

65-67 1.4-1.5 65-66.35 Silt, SANDY CLAY

17 1.6 66.35-67 Silt F SAND, SOME CLAY
70-72 2.7-10.11 70-71.35 Silt

18 1.5 71.35 MOD OL BRN SILTY F SAND

75-77 2.3 4.5 75-76 dk GRN GRAY (SG 4/1) F SAND
19 2.0 SOME CLAY TR. SHELL FRAGS

76-77 Silt SILTY CLAY, TR. F SAND

80-82 4.5-7.17 MOD OL BRN, SANDY SILT, SLIGHTLY
20 2.00 PLASTIC

85-87 4.4-1.6 Silt

21 2.0

90-92 3.1-6.8 Silt
22 2.10

8/21/77

WESTLY SADDY

- 0700 - 1st egg on nest
- 0720 - 2nd egg on nest
- 0740 - 3rd egg on nest
- 0750 - 4th egg on nest
- 0800 - 5th egg on nest
- 0810 - 6th egg on nest
- 0820 - 7th egg on nest
- 0830 - 8th egg on nest
- 0840 - 9th egg on nest
- 0850 - 10th egg on nest
- 0900 - 11th egg on nest
- 0910 - 12th egg on nest
- 0920 - 13th egg on nest
- 0930 - 14th egg on nest
- 0940 - 15th egg on nest
- 0950 - 16th egg on nest
- 1000 - 17th egg on nest
- 1010 - 18th egg on nest
- 1020 - 19th egg on nest
- 1030 - 20th egg on nest
- 1040 - 21st egg on nest
- 1050 - 22nd egg on nest
- 1100 - 23rd egg on nest
- 1110 - 24th egg on nest
- 1120 - 25th egg on nest
- 1130 - 26th egg on nest
- 1140 - 27th egg on nest
- 1150 - 28th egg on nest
- 1200 - 29th egg on nest
- 1210 - 30th egg on nest
- 1220 - 31st egg on nest
- 1230 - 32nd egg on nest
- 1240 - 33rd egg on nest
- 1250 - 34th egg on nest
- 1300 - 35th egg on nest
- 1310 - 36th egg on nest
- 1320 - 37th egg on nest
- 1330 - 38th egg on nest
- 1340 - 39th egg on nest
- 1350 - 40th egg on nest

8/21/77

- 1440 - 41st egg on nest
- 1450 - 42nd egg on nest
- 1500 - 43rd egg on nest
- 1510 - 44th egg on nest
- 1520 - 45th egg on nest
- 1530 - 46th egg on nest
- 1540 - 47th egg on nest
- 1550 - 48th egg on nest
- 1600 - 49th egg on nest
- 1610 - 50th egg on nest
- 1620 - 51st egg on nest
- 1630 - 52nd egg on nest
- 1640 - 53rd egg on nest
- 1650 - 54th egg on nest
- 1700 - 55th egg on nest
- 1710 - 56th egg on nest
- 1720 - 57th egg on nest
- 1730 - 58th egg on nest
- 1740 - 59th egg on nest
- 1750 - 60th egg on nest
- 1800 - 61st egg on nest
- 1810 - 62nd egg on nest
- 1820 - 63rd egg on nest
- 1830 - 64th egg on nest
- 1840 - 65th egg on nest
- 1850 - 66th egg on nest
- 1900 - 67th egg on nest
- 1910 - 68th egg on nest
- 1920 - 69th egg on nest
- 1930 - 70th egg on nest
- 1940 - 71st egg on nest
- 1950 - 72nd egg on nest
- 2000 - 73rd egg on nest
- 2010 - 74th egg on nest
- 2020 - 75th egg on nest
- 2030 - 76th egg on nest
- 2040 - 77th egg on nest
- 2050 - 78th egg on nest
- 2100 - 79th egg on nest
- 2110 - 80th egg on nest
- 2120 - 81st egg on nest
- 2130 - 82nd egg on nest
- 2140 - 83rd egg on nest
- 2150 - 84th egg on nest
- 2200 - 85th egg on nest
- 2210 - 86th egg on nest
- 2220 - 87th egg on nest
- 2230 - 88th egg on nest
- 2240 - 89th egg on nest
- 2250 - 90th egg on nest
- 2300 - 91st egg on nest
- 2310 - 92nd egg on nest
- 2320 - 93rd egg on nest
- 2330 - 94th egg on nest
- 2340 - 95th egg on nest
- 2350 - 96th egg on nest
- 2400 - 97th egg on nest
- 2410 - 98th egg on nest
- 2420 - 99th egg on nest
- 2430 - 100th egg on nest

8/21/97

CT-03

65-67 2.5-6.8 DK GRN GRAY (50% 4/1) SANDY
16 2.0 CLAY DEPENDS TO CALVEY F SAND

70-72 2.4-5.7 7-11 SAA 1 CLAY SOME F SAND
17 2.0 SAA, F SAND SOME CLAY
WHITE SHELL FRAGS

75-77 3.3-4.5 SAA CLAY + F SAND
18 2.0

80-82 2.7-7.8 MOD CL BRN, SANDY, SILTY
19 2.0 SLIGHTLY PLASTIC

CT-04

8/21/97

65-67 3.2-2.4 ^{65-66.35} DK GRN GRAY (50% 4/1) SILTY CLAY
16 1.6 SOME SHELL FRAGS

66.35-67 SAA, SILTY F SAND
70-72 2.4-5.7 SAA (SILT), SOME F SAND
17 2.0 SCRUB, FIB, SLIGHTLY PLASTIC

75-77 2.3-4.6 SAA
18 2.0

80-82 1.2-5.6 SAA SILTY F SAND SOME
19 2.0 SHELL FRAGS TRACE RED,
SAND

85-87 5.5-5.6 MOD CL BRN, SLIGHTLY PLASTIC
20 1.8 SILT, SOME SAND

90-92 11.15-20.21 SAA
21 2.0

95-97 3.4-6.7
22

APPENDIX D
REPORT OF GEOTECHNICAL EXPLORATION

REPORT OF GEOTECHNICAL
EXPLORATION

AQUARIUM PARKING GARAGE
CHARLESTON, SOUTH CAROLINA
S&ME JOB NO. 1131-97-290

Prepared For:

FLUOR DANIEL GTI
EAST PITTSBURGH, PENNSYLVANIA

Prepared By

S&ME, Inc.
840 Low Country Boulevard
Mt. Pleasant, South Carolina

September 24, 1997

TABLE OF CONTENTS

	Page
EXECUTIVE SUMMARY	1
1.0 PROJECT INFORMATION	2
2.0 EXPLORATION PROCEDURES	3
2.1 FIELD DRILLING AND TESTING	3
2.2 LABORATORY TESTING	3
3.0 SITE AND SUBSURFACE CONDITIONS	5
3.1 SITE CONDITIONS	5
3.2 SUBSURFACE CONDITIONS	5
4.0 CONCLUSIONS AND RECOMMENDATIONS	8
4.1 SEISMIC CONSIDERATIONS	8
4.1.1 Site Seismic Coefficient	8
4.1.2 Design Earthquake	9
4.1.3 Liquefaction Potential	9
4.2 FOUNDATION RECOMMENDATIONS	11
4.2.1 Deep Foundations	11
4.2.2 First Floor Slab	18
4.3 SITE PREPARATION	21
4.4 CONTROLLED FILL	21
4.5 CONSTRUCTION MONITORING AND TESTING	21
5.0 LIMITATIONS OF REPORT	24
APPENDIX	
Figure A-1: Boring Location Plan	
Figure A-2: Soil Profiles	
Boring Logs	
Field Testing Procedures	
Soil Data Summary	
Consolidation Report	
Laboratory Testing Procedures	
Figure A-3: Settlement Plate Detail	

EXECUTIVE SUMMARY

A subsurface exploration was performed in order to determine various geotechnical parameters for use in the design of the proposed Aquarium Parking Garage in Charleston, South Carolina. Our conclusions and recommendations can be summarized below:

1. Subsurface conditions at the site were explored by drilling seven soil test borings to depths of 10 to 97 ft below existing grade. Due to on-site contamination from previous industrial facilities on and around the site, extensive casing and soil containerization was required.
2. The borings encountered a variety of sand and clay soil strata that varied in consistency and thickness. Three strata are of particular importance; 1) 6 to 10 ft of uncontrolled fill (sand with bricks, concrete, wood, etc.) near the surface, 2) a thick (typically 35-ft) very soft, highly plastic clay beneath the fill, and 3) the Cooper Marl, a soft to hard sandy silt that was encountered at about 80 ft below grade.
3. We recommend a seismic site coefficient (S) of 1.5 for seismic design, based on soil type S_3 . Sand deposits within the fill (upper 6 to 10 ft) and between 45 and 55 ft at the site may liquefy during a seismic event.
4. A deep foundation system will be required to support the proposed structure. A foundation system consisting of driven piles (12-in. and 14-in. square prestressed concrete piles and steel H-piles) was the only option considered. We believe that auger cast piles and/or drilled caissons are probably prohibitive due to contaminants in the soil.
5. The first floor slab, if earth supported without ground modification, may settle 6 in or more due to the placement of 2 ft of new conventional fill at the site. One option to eliminate this settlement is to structurally tie the slab into the piles. Another option is to fill the site with lightweight fill or a combination of lightweight and conventional fill to reduce the load induced by the fill. A third option is to surcharge the site. Flexible asphalt paving could be used within the first floor area although periodic maintenance would eventually be required to repair settlement related problems. Alternatively, a ground modification program (surcharging with/without the use of lightweight fill) could be used to reduce post construction settlement.

1.0 PROJECT INFORMATION

We understand the proposed parking garage will be a six-level, reinforced concrete structure with a footprint of 180 ft x 365 ft. Based on Walker Parking Consultant's fax to Sandy Logan dated April 29, 1997, we anticipate column loads for the structure will be in the range of 500 to 1200 kips. We understand that the desired elevation of the first garage level will be near present grades, but as subsequently explained, we have assumed that up to 2 ft of controlled fill will be required underneath the first floor slab.

As a result of its industrial past, the site has been classified as contaminated. Specifically, the upper aquifer and soils contain hazardous and potentially hazardous levels of chemicals of concern. As explained subsequently, the contamination required special drilling procedures. Also, in consideration of the cost of disposing of any of the soils from the site, we have assumed that any construction activity involving excavation will be prohibitively expensive. Therefore, our subsequent geotechnical evaluation has not considered construction techniques such as undercutting, drilled shafts, auger cast piles, etc.

2.0 EXPLORATION PROCEDURES

2.1 FIELD DRILLING AND TESTING

Subsurface conditions at the site were explored by drilling seven soil test borings (designated GT-1 through GT-6, and GT-1A) within the footprint of the structure. The approximate boring locations are shown on the Boring Location Plan (Fig. A-1) enclosed in the Appendix. Boring GT-1 was terminated at 10 ft due to obstructions. The other six borings were drilled to depths of 77 to 97 ft. The boring locations were established in the field by pacing distances and estimating right angles from existing site features, and should therefore be considered approximate. Standard Penetration Tests (ASTM D-1586) and split-spoon samples were generally obtained continuously in the upper 8 to 10 ft of the borings (except GT-2 which was continuously sampled to 16 ft) and at 5-ft intervals thereafter.

Due to the on site contamination in the upper soils, extensive casing was required to reduce the chance of the contaminants migrating to deeper soil strata. In general, the borings were drilled to depth of 15 ft. An 8 in. casing was then set to a depth of approximately 20 ft and grouted. This grout had to cure for at least 24 hours before drilling within the boring could continue. The borings were then advanced to a depth of approximately 60 ft and a 4 in. casing was "telescoped" through the 8 in casing. Again, the 4-in. casing was grouted and allowed to cure for at least 24 hours before the borings were advanced to their termination depths. A more detailed description of our field testing procedures, as well as the Boring Logs, are included in the Appendix of this report.

2.2 LABORATORY TESTING

In order to evaluate the liquefaction potential of sands three grainsize analyses were performed on select samples. Consolidation properties of clay strates were evaluated

through one consolidation test, eleven moisture content tests, and three Atterberg Limits tests. These test results are provided in the Soil Data Summary, the consolidation test report, and on individual boring logs included in the Appendix of this report.

3.0 SITE AND SUBSURFACE CONDITIONS

3.1 SITE CONDITIONS

The site is located on the eastern side of peninsular Charleston within the southern half of the property bounded to the north by Charlotte Street, to the west by Washington Street, to the south by Calhoun Street, and to the east by Concord Street. Most of the relatively level site was previously occupied (in the late 1800's) by a wood treating plant which used creosote during its manufacturing process¹. A former manufactured gas plant was also located adjacent to the site between the 1850's and 1950's. The site is presently closed and fenced off (June 1989), but includes a former baseball field, basketball court, and picnic shelter. The site is located approximately 500 ft to the west of the Cooper River and contains numerous ground water monitoring wells.

3.2 SUBSURFACE CONDITIONS

Details of the subsurface conditions encountered by the soil test borings are shown on the Boring Logs in the Appendix. A subsurface profile of these conditions is illustrated on Figure A-2, which can be found in the Appendix. The logs and profile represent our interpretation of the subsurface conditions based upon visual examination of the split-spoon samples. Stratification lines on the Boring Logs and profiles represent approximate boundaries between soil types; however, the actual transition may be gradual.

¹ RI Report, Fluor Daniel GTI, 1995

The general subsurface conditions and their pertinent characteristics are discussed in the following paragraphs.

1. Fill (sand, gravel, brick, concrete, wood): Very loose to medium dense, or soft to firm fill material was encountered in all seven soil test borings to a depth of about 6 to 10 ft. The fines content throughout the fill varied greatly. The Standard Penetration Test (SPT) N-values ranged from 2/18" to 50/6" and were obviously effected by debris (brick fragments, etc.). A moderate to strong organic (and chemical) odor was detected within much of the fill.
2. Clay (CH): This very soft to stiff, highly plastic soil was encountered between depths of approximately 8 to 45 ft below existing grade. SPT N-values of these clays ranged from less than 1 (wor-weight of drilling rods) to 2. The water content within this zone ranged from 73% to 126 %, but was generally about 95%. The grain-size analysis run on one sample indicates a fines content of 94%.
3. Clayey Sand (SC) and/or Silty Sand (SM): This 5 to 15 ft thick, very loose to medium dense, clean to clayey and/or silty sand, was encountered at depths ranging from about 40 to 60 ft. In several borings, this sand strata contained zones which were very clayey. SPT N-values ranged from 3 to 20. Three moisture content determination tests were conducted on samples from this zone and indicated a water content of 29 to 33 percent. Fines contents of two samples were 18 and 19 percent.
4. Clay (CH/MH): Between approximately 55 and 70 ft, the borings generally encountered a soft to stiff, slightly sandy to sandy, highly plastic clay. SPT N-values ranged from 3 to 15. The moisture content ranged from 49 to 65 percent. Two Atterberg limits tests were run on samples from within this strata, which resulted in liquid limits of 86 and 104 and plasticity indices of 57 and 65, respectively.
5. Very Sandy Clay/Very Clayey Sand (SC/CH): Between approximately 70 ft and the top of the Cooper Group (Cooper Marl), the borings generally encountered soft to stiff (3 to 9), very sandy clay or very loose to medium dense (4 to 17), very clayey/silty sand. Laboratory testing was not performed on any samples taken from this zone.
6. Cooper Group (Cooper Marl) - Sandy Silt (MH)/Silty Sand (SM): This olive, calcareous, soft to hard sandy silt material and/or loose to medium dense silty sand, which is locally referred to as Cooper Marl, was encountered in the six borings at a depth of 76 to 84 ft below existing grade. All deep borings were terminated within the marl at depths of 77 to 97 ft. The SPT N-values ranged from 4 to 35. The total thickness of this soil stratum is generally in excess of 100

ft. The Cooper mari is the thick "basement" strata of the area in which most deep foundations bear.

Groundwater levels were measured at the time of drilling and varied from 1 1/2 ft to 4 ft below existing grade. However, groundwater levels will fluctuate with seasonal and climactic variations, tidal fluctuations, and construction activity in the area.

4.0 CONCLUSIONS AND RECOMMENDATIONS

The analyses and recommendations submitted herein are based, in part, upon data obtained from the subsurface exploration. The nature and extent of variations between the borings will not become evident until construction. If variations appear evident, then we will re-evaluate the recommendations of this report. In the event that any changes in the nature, design, or location of the building are planned, the conclusions and recommendations contained in this report shall not be considered valid unless the changes are reviewed and conclusions modified or verified in writing. We strongly recommend that S&ME be retained to review the final design plans and specifications to confirm that earthwork and foundation recommendations are properly interpreted and implemented.

4.1 SEISMIC CONSIDERATIONS

As stated in Section 1206 of the Standard Building Code, "Every building and structure, and portion thereof, shall be designed and constructed to resist the effects of earthquake motions....". The remainder of Section 1206 specifies how the seismic loading is to be estimated and analyzed for a given site. Since the Charleston area is within a known seismically active region, earthquake loads are an important part of the design process.

4.1.1 Seismic Site Coefficient

Based upon the Standard Building Code (1992/1993 Revisions), the site soil conditions can be classified as Soil-Profile Type S_3 :

"A soil profile containing 20 to 40 ft in thickness of soft to medium-stiff clays with or without intervening layers of cohesionless soils."

A Seismic Site Coefficient (S) of 1.5 is therefore appropriate for design.

4.1.2 Design Earthquake For Liquefaction Analysis

The Standard Building Code (1992, 1993 Revisions) requires that the design earthquake have a 90% probability of non-exceedance in 50 years. To satisfy this criteria, the design earthquake used in our analyses has a magnitude (M) of approximately 5.9, and produces a "base" acceleration of 0.12g. This is the seismic event being used in the design of the I-526 (Mark Clark Expressway) bridges over the Stono River, which was developed by a comprehensive study of Charleston seismicity. S&ME commissioned Martin C. Chapman² to perform this study in 1992, during the early design stages for the Mark Clark project. Depending on actual near surface stratigraphy, the base acceleration may be amplified within the overlying soils. Theoretical determination of the site amplification was beyond the scope of this study. However, based upon complete site seismic response analyses we have conducted on similar sites, and upon empirical relationships for the amplification of base acceleration due to site specific soil conditions, we have assumed that the Peak Ground Acceleration (PGA) will be 0.18g. This acceleration value has been used in our liquefaction analysis.

4.1.3 Liquefaction Potential

Liquefaction, which is the loss of a soil's shear strength due to the increase in porewater pressure resulting from seismic vibrations, is always a concern in the Charleston area. Liquefiable soils are found in the Charleston area and significant geological evidence suggests liquefaction has commonly occurred during past earthquakes. Soils most susceptible to liquefaction generally consist of saturated, loose, "clean" (i.e., plasticity index of less than 5), fine (10% size ranging from 0.07 to 0.25 mm) sands. Various zones within the sand fill (upper 10 ft) and several sand layers between 45 and 55 ft meet this criteria.

² Martin C. Chapman is a seismologist at the Seismological Observatory of the Virginia Polytechnical Institute.

Liquefaction potential was evaluated with the widely-used methods developed by Seed, Idriss and Arango³ which are based on field observations of the performance of sand deposits during previous earthquakes. This method compares some in-situ characteristics of the observed liquefiable deposits to the actual deposits at the subject site. This liquefaction analysis procedure is widely accepted by government agencies, and is described in NAVFAC Design Manual 7.3.

For each stratum which appeared to meet the previously outlined grainsize and plasticity criteria, a factor of safety against liquefaction was calculated using the procedures outlined by Seed, et al. This factor of safety is the ratio of the cyclic stress required to cause liquefaction to the cyclic stress generated by the design earthquake. Subsurface strata with a factor of safety against liquefaction of less than 1.2 are generally considered to be "liquefiable". Our results indicate that a few isolated sand zones within the upper 10 ft (fill zone) and the sands at a depth of approximately 50 ft are liquefiable.

With regard to foundations and building construction, liquefaction creates two major problems; ground-surface disruption and/or volumetric compression. Ground surface disruption may be in the form of fissures, sand boils, surface oscillations or lateral displacements. Such ground surface disturbances could result in catastrophic failures such as "punching" failures of foundations supported above the liquefiable deposits.

Based on recent work by Youd and Garris⁴, the presence of a sufficiently thick (> 3 meters) layer of non-liquefiable soils over liquefiable sands will prevent ground disruptions. Across the majority of the site, non-liquefiable soils (including an assumed

³ Seed, H.B., Idriss, I.M., and Arango, I., "Evaluation of Liquefaction Potential Using Field Performance Data," *Journal of Geotechnical Engineering*, ASCE, Vol. 109, No. 3, Mar., 1983, pp. 458-462.

⁴ Youd, T.L., and Garris, C.T., "Liquefaction - Induced Ground Surface Disruption," *Journal of Geotechnical Engineering*, ASCE, Vol. 121, No. 11, November, 1995, pp. 805-809.

2-ft layer of new fill) which overlies the liquefiable sands appear to be sufficiently thick to prevent extensive ground surface disruption.

Because of the heavy structural loads of the garage, a deep foundation system will be required. Our subsequent recommendations for deep foundations take into account the presence of these liquefiable deposits. Therefore, the only structural elements at risk to liquefaction induced volumetric compression settlement are slabs-on-grade, retaining walls, planters, etc. Prediction of the magnitude of this settlement is very difficult. However, based upon currently available methods, we estimate that settlement due to liquefaction induced volumetric compression could be as much as 2 to 5 in.

4.2 FOUNDATION RECOMMENDATIONS


The thick deposits of weak, compressible soils will not be capable of supporting the required foundation loads on spread footings. Therefore a deep foundation system bearing in the Cooper Marl will be required. However, we have evaluated the possibility of "earth supporting" the relatively lightly loaded first floor slab near existing grade. Our evaluations and recommendations are summarized in the following sections.

4.2.1 Deep Foundations

We have limited our deep foundation evaluation to only driven piles (pre-stressed concrete and steel H-piles). We assume that auger cast piles and/or drilled caissons are prohibitively expensive due to economic issues related to the contaminants in the soil. The local cost of transporting and incinerating contaminated (but not hazardous) material is on the order of \$50 per ton.

Axial Capacity. Estimates of the ultimate compressive capacity of 12-in. and 14-in. square, prestressed concrete piles and steel H-piles bearing in the Cooper Marl are

AQUARIUM PARKING GARAGE Allowable Axial Pile Capacity Vs. Penetration Below Existing Grade (12-in. and 14-in. PSC/H-pile)



- Notes:
- 1) Minimum center to center pile spacing assumed to be five pile diameters
 - 2) An efficiency factor of 1.0 should be used for center to center pile spacings of 5 pile diameters or more and decrease linearly to 0.8 at 3 pile diameters. Pile spacing should not be less than 3 pile diameters
 - 3) Allowable tensile capacities for driven piles are 50% of the compressive capacity
 - 4) The structural capacity of the pile has not been considered in our analysis
 - 5) Analysis assumes the Copper Marine is located at a depth of 80 ft below existing grade

Job No.: 1131-97-290

Date: September 19, 1997

Not to Scale





Allowable Compressive
Capacity
Driven 12-in. and 14-in. Piles
Aquarium Parking Garage
Charleston, South Carolina

Figure No.

1

Lateral Foundation Analyses. The effects of lateral loading on the 12 and 14 in. PSC/H-piles were estimated using the finite difference computer program LPILE Plus. This program models soil behavior with the use of p-y curves to estimate pile deflection and bending moment based on various pile sizes, soil conditions and loads. Our analyses assumed all lateral loads are applied at ground surface, and that center-to-center pile spacings are at least 5d. Figures 2 and 3 graphically presents our estimates of lateral load versus deflection and internal bending moment for single piles with an 80 ton axial load. Fixity, defined as the first inflection point of the pile displacements, occurs about 20 ft below the pile head for all four pile types that were considered.



Notes

- 1) 10-in and 14-in PSC piles analyzed using a 50-ton axial compressive load
- 2) Analysis conducted on a single pile. Analysis does not account for group effects
- 3) Lateral load applied at ground surface
- 4) The structural capacity of the piles was not considered in this analysis

Job No. 10-07-001

Date September 19, 1997



North Side



Lateral Pile Analysis
Driven PSC Piles
Aquarium Parking Garage
Charleston, South Carolina

Figure No.

2



- Notes
- 1) 12-in and 14-in H-piles analyzed using a fiction axial compressive load.
 - 2) Analysis conducted on a single pile. analysis does not account for group effects.
 - 3) Lateral load applied at ground surface.
 - 4) The structural capacity of the piles was not considered in this analysis.

Pile Installation. Based on our experience with similar projects, drop air or diesel hammers having rated energies in the range of 30 to 60 ft-kips should be suitable for the pile installation. However, the dense sand layers above the marl could cause some driving difficulties. Ordinarily, such sands would be pre-augered as necessary. Since pre-augering should be avoided due to site contamination, a larger hammer may be required. For this reason, steel piles (which will penetrate the dense sands easier) may be a better alternative, although they are typically more expensive than concrete piles. Consequently, the selection of a suitable driving system may have to be made based on the results of the test pile program. If pre-augering is required, and appears economically feasible, it should be limited to a depth of 80-ft. The diameter of the auger should be equal to the least dimension of the pile (i.e., 12 in. or 14 in., respectively, for 12 in. and 14 in. piles).

A review of historical maps indicates that the site is located in an area of original Cooper River marshland. Based upon the results of our borings, it appears that the site has been filled in the past and consequently, significant obstructions to pile installation may be encountered within the upper 10 ft. Typically, this relatively common problem is overcome by pre-augering or pre-excavation with a track-hoe. If pre-augering or digging is too expensive, a steel spud may be required to displace debris and create pilot holes through the uncontrolled fill. Again, the feasibility of this method will be best evaluated during the pile test program. Also, such concerns may make steel piles a better alternative.

Pile Vibrations. It does not appear that there are any structures in the immediate vicinity to the parking garage which would sustain damage as the result of vibrations induced by pile driving. However, it may be prudent to perform a pre- and post-construction survey in order to monitor the affects of pile installation on the surrounding areas. This survey should include video and photographic documentation as well as the installation of crack monitors throughout the area. In addition, we recommend that vibration monitoring be performed during initial pile installation.

4.2.2 FIRST FLOOR SLAB

Fill Placement and Settlement. We understand that if possible, the first floor slab will be non-structural and constructed at or just above present grade. Based on our borings, we anticipate that such plans may require extensive undercutting. After removal of surficial organic material (topsoil), uncontrolled fill (bricks, wood, concrete, etc.) may be encountered. Much of this debris may have to be removed to provide a stable subgrade. Due to environmental concerns, we assume that such undercutting should be avoided. The undercutting could be avoided provided that the uncontrolled fill is covered by a minimum of 2 ft of compacted controlled fill (described in subsequent paragraphs) beneath pavements and slabs. However, this fill placement will cause settlement.

Like much of peninsular Charleston the site was filled in the past, probably as much as 100 years ago. The very soft marine clay which was encountered beneath this fill (between depths of approximately 8 and 40 ft) is highly compressible, and will consolidate with even small stress increases (such as the weight of the 1 to 2 ft of new fill). Clays consolidate (causing surface settlement) as water is expelled from the voids in the soil. This process is extremely slow, particularly in this case where the clay stratum is very thick, and consolidation can continue for many decades. Based on their high natural moisture contents (73% to 126%), the clays at this site may still be consolidating under the weight of the 6 to 10 ft of existing fill.

Structures (i.e., a non-structural parking slab) supported above these clays will settle as the clays consolidate. The prediction of the rate and magnitude of any remaining consolidation due to the existing fill loads is extremely difficult. However, it is possible that some additional long-term settlement (probably < 1 in.) may occur. It is important to note that this settlement will occur even if no additional load is added to the soil. Settlement will be much greater assuming 2-ft of fill will be required, as discussed previously.

The addition of 2 ft of fill under a non-structural parking slab will cause the soft clays to consolidate. Based on the consolidation test and moisture content test data, we estimate that the long-term consolidation settlements due only to fill placement will be on the order of 6 in. or more. This again is in addition to the settlement which is probably still occurring from the placement of the original fill.

If the loading is reduced, the settlement will be reduced. Obviously, one option is to construct the first floor parking deck as a structurally supported slab. Another option is to use lightweight or engineered fill, thereby reducing the load and resulting settlement. Several types of lightweight fill are available. These include pumice stone mined in Greece and marketed by Tarmac America, Inc. This material, slightly larger than pea gravel, is currently being used on a road construction project in North Charleston. Other examples include Solite (expanded shale) and Elastizell (all with unit weights of 30 to 55 pcf). These materials may be combined with earthen fill in order to reduce costs. Reduction of the average soil density to less than 40 pcf with the use of lightweight fill may reduce total settlements resulting from fill loads to less than 3½ in.

A third option is to preconsolidate the site by surcharging. A surcharge program consists of placing an additional quantity of temporary fill over the required permanent fill. The additional fill increases the stress on the compressible soil, thereby speeding consolidation. Once the compressible soils have consolidated to a point where further settlement due only to the weight of the permanent fill is within tolerable limits, the surcharge is removed. The greater the surcharge, the sooner the surcharge may be removed. However, drainage distance is another controlling factor with regard to consolidation time. Due to the relatively large thickness (40 ft) of the clay layer, measures to speed consolidation by reducing the drainage distance must be considered. Wick drains are typically the most cost-effective method of decreasing drainage distance and shortening the consolidation time. (Wick drain costs are typically about \$0.50 per lineal ft. installed).

Various combinations of surcharge height, surcharge time, and wick spacing are presented in Table 1. All scenarios assume a permanent fill height of 2-ft.

Table 1
SURCHARGING OPTIONS

Fill Height (permanent and surcharge)	Surcharge Time	Wick Spacing	Assumed Wick Cost*	Remaining Settlement Due to Fill
6 ft	180 days	7 ft	\$42,000	2½ in.
6 ft	180 days	5 ft	\$83,000	½ in.
6 ft	90 days	5 ft	\$83,000	2½ in.
8 ft	180 days	9 ft	\$26,000	2½ in.
8 ft	180 days	7 ft	\$42,000	1 in.

* Wick cost estimate based on 50 ft long wicks, spaced in a triangular pattern over a 190 ft by 375 ft area at \$0.50/ft. Does not include cost of mobilization.

To monitor the rate and magnitude of site settlement we recommend that settlement plates be installed at several locations within the garage footprint. A sketch of a typical settlement plate arrangement is shown in Figure A-3 of the Appendix. Protection (from any movement) of the settlement plates during construction is imperative. Fill soils should be methodically hand placed and compacted in areas above and immediately surrounding the settlement plates. Fill soils should not be dumped in the immediate areas of the settlement plates. Settlement plate locations should be barricaded after completion of filling to prevent the plates from being disturbed or destroyed. Upon completion of controlled fill placement, the site should be allowed to consolidate until settlement plate data, as interpreted by a geotechnical engineer, indicates post construction settlement due to the permanent fill will be within tolerable limits. Accurate surveying of the elevation of the plates should begin immediately after their installation and continue weekly for the first four weeks and then bi-weekly thereafter.

4.3 SITE PREPARATION

As mentioned previously, typical site preparation will likely be modified due to the contamination within the upper soils. Based on the results of the borings, we anticipate that extensive undercutting will be required. However, due to the contaminants in the soil, and the thickness of the uncontrolled fill (6 to 10 ft), we assume that undercutting will be prohibitively expensive. Foreign debris such as uncontrolled fill (bricks, wood, etc.) was encountered within all seven borings. Typically, any debris encountered must be completely removed to depths necessary to provide a minimum of 2 ft of compacted, controlled fill beneath pavements and slabs. After stripping, areas at grade to receive fill are generally proofrolled with a fully loaded tandem-axle dump truck or similar equipment to detect any unstable areas. Any areas which pump or rut excessively are scarified and densified in-place, or undercut and replaced with soil subsequently described as controlled fill. At this time, we recommend that only surficial organic material (topsoil) be removed and the exposed subgrade (which will typically contain uncontrolled fill) receive a minimum of 2 ft of controlled fill. Areas which receive controlled fill should be proofrolled with a to detect any unstable areas.

4.4 CONTROLLED FILL

Controlled fill material should be cohesionless soil containing no more than 10% fines (material passing the No. 200 sieve) by weight and having a maximum dry density (ASTM D-1557) of at least 100 pcf. The soil should be free of organics, deleterious matter and elongated or flat particles which may be susceptible to degradation. The fill should be placed in uniform lifts of 10 inches or less (loose measure), and compacted to at least 95% of the modified Proctor maximum dry density (ASTM D-1557).

4.5 CONSTRUCTION MONITORING AND TESTING

Random in-place density testing should be performed on all fill by an experienced engineering technician to determine whether the specified compaction has been achieved and if the fill material meets specified requirements. Fill subgrade evaluations and proofrolling and undercutting operations should be performed by a geotechnical engineer or their representative.

Test Pile Program. The environmental contamination and poor soil conditions of this site combine to make foundation construction complicated and potentially difficult. Pre-augering and shallow excavation should ideally be avoided due to environmental costs yet the dense, deep sands and near surface debris may interfere with pile driving. Additionally, the elevation of the bearing stratum (Cooper marl) varies by as much as 8-ft across the site and the thick compressible strata makes down drag a concern. Finally, the depth of the bearing stratum and the structural loads will result in relatively long piles. The uncertainties associated with these factors can substantially increase the cost of the foundation. An elimination or reduction of these uncertainties can result in significant savings. For example, the use of steel piles would alleviate many of the pile drivability concerns. However, due to the large difference in material costs, substantial savings will be realized if the prestressed concrete piles can be driven. Therefore, a thorough pile load test program is warranted. Furthermore, the saving will be maximized if the testing is performed prior to construction. The results of the testing will then be available for the final bid documents. This approach was used with great success during the design/construction of the Charleston County Health Complex Parking Garage.

Pile capacities should be verified at the start of construction through static pile testing and dynamic testing with a Pile Driving AnalyzerTM (PDA) in accordance with ASTM D-1143 and D-4945. We recommend that eight probe piles be driven at production pile locations across the site. Four of the probe piles should be prestressed concrete and

four should be steel. A steel pile should be driven at a location close to each of the four concrete piles such that drivability can be better evaluated. One of the pile pairs should be driven in the vicinity of GT-4 since the marl was deeper in this boring.

After installation, the piles should be dynamically monitored during restrikes. We recommend restrikes be performed 3 to 7 days after driving. At least one of the concrete piles should be statically loaded to failure, or to a minimum of three times the design load, using the "quick load test method" of ASTM D-1143 - Standard Method of Testing Piles Under Static Axial Compressive Load. The static test pile should be instrumented with electronic strain gauges to develop load transfer data for the overburden soils. The load transfer data will be used to evaluate negative skin friction potential. After an evaluation of the dynamic and static load test data, production pile lengths and capacities can be established. Additionally, the installation of all driven piles during production should be monitored by an engineering technician working under the direction of a geotechnical engineer.

A pre- and post-construction survey of the surrounding buildings should be performed in order to document any damage associated with the installation of driven piles. This survey should include video and photographic records and the installation of crack monitors throughout the area. We also recommend that vibration monitoring be performed during pile installation.

5.0 LIMITATIONS OF REPORT

This report has been prepared in accordance with generally accepted geotechnical engineering practice for specific application to this project. The conclusions and recommendations contained in this report are based upon applicable standards of our practice in this geographic area at the time this report was prepared. No other warranty, expressed or implied, is made.

APPENDIX

FIGURE A-1: BORING LOCATION PLAN

FIGURE A-2: SOIL PROFILES

BORING LOGS


FIELD TESTING PROCEDURES

SOIL DATA SUMMARY


CONSOLIDATION REPORT

LABORATORY TESTING PROCEDURE

FIGURE A-3: SETTLEMENT PLATE DETAIL



Boring locations are shown in general arrangement only. Do not use boring locations for determination of distances or quantities. This plan is adapted from site plan provided by Fluor Daniel GTI, Inc.



Job No : 1131-97-290

Date: September 17, 1997

Not to Scale



Boring Location Plan
Aquarium Parking Garage
Charleston, South Carolina

Figure No:


A-1

PROJECT: AQUARIUM PARKING GARAGE CHARLESTON, SOUTH CAROLINA 1131-97-290		BORING LOG GT-1				
DATE STARTED: 8/13/97		DATE FINISHED: 8/13/97				
DRILLING METHOD: MUD ROTARY		NOTES: GUS-PECH 1000, AUTOMATIC SAFETY HAMMER. 12" BIT FROM 0' TO 10'.				
CASING LENGTH:	DRILLER: RICHARD SIMMONS					
WATER LEVEL: WATER AT 4 FEET AT TIME OF DRILLING						
DEPTH (feet)	GRAPHIC LOG	MATERIAL DESCRIPTION	ELEVATION (ft-MSL)	SAMPLE NO./TYPE	STANDARD PENETRATION TEST DATA (blows/ft)	N VALUE
					0 10 20 30 60 80	
		FILL: SILTY SAND (SM) medium dense, dark brown, fine		S-1		13
5		--- wood fragments		S-2		17
		--- brick fragments, odor		S-3		17
		FILL: SANDY GRAVEL (SP/GP) medium dense, gray and reddish-brown, coarse; brick and wood content, odor		S-4		27
10		FILL: CLAY WITH WOOD (CH/OH) very stiff, dark gray		S-5		15
		BORING ABANDONED AT 12 FEET		S-6		22

1. BORING AND SAMPLING IS IN ACCORDANCE WITH ASTM D-1586.
2. PENETRATION (N-VALUE) IS THE NUMBER OF BLOWS OF 140 LB. HAMMER FALLING 30 IN. REQUIRED TO DRIVE 1.4 IN. I.D. SAMPLER 1 FT.









S & ME, INC.
840 LOW COUNTRY BOULEVARD
MT. PLEASANT, SOUTH CAROLINA



1. BORING AND SAMPLING IS IN ACCORDANCE WITH ASTM D-1586.
2. PENETRATION (N-VALUE) IS THE NUMBER OF BLOWS OF 140 LB. HAMMER
FALLING 30 IN. REQUIRED TO DRIVE 1.4 IN. I.D. SAMPLER 1 FT.



S & ME, INC.
840 LOW COUNTRY BOULEVARD
MT. PLEASANT, SOUTH CAROLINA

PROJECT: AQUARIUM PARKING GARAGE CHARLESTON, SOUTH CAROLINA 1131-97-290			<h2 style="margin: 0;">BORING LOG GT-1A</h2>		
DATE STARTED: 8/13/97		DATE FINISHED: 8/20/97		NOTES: GUS-PECH 1000, AUTOMATIC SAFETY HAMMER. 12" BIT FROM 0' TO 8', 4" BIT 8' TO 82'.	
DRILLING METHOD: MUD ROTARY					
CASING LENGTH: 8" & 4"/15' & 58'		DRILLER: RICHARD SIMMONS			
WATER LEVEL: WATER AT 4 FEET AT TIME OF DRILLING					
DEPTH (feet)	GRAPHIC LOG	MATERIAL DESCRIPTION	ELEVATION (ft-MSL)	SAMPLE NO./TYPE	STANDARD PENETRATION TEST DATA (blows/ft)
					0 10 20 30 60 80
60		firm, greenish-gray		S-14	5
65		--- (CH), soft; slight sand and shell content, PP = 1.5		S-15	3
70		--- no recovery <u>SILTY SAND (SM)</u> loose, dark bluish-gray, fine; trace shell hash		S-16	7
75				S-17	8
80		<u>COOPER GROUP: SANDY SILT (MH)</u> stiff, olive; calcareous, PP = 1.25		S-18	5
		<u>BORING TERMINATED AT 82 FEET</u>		S-19	9

1. BORING AND SAMPLING IS IN ACCORDANCE WITH ASTM D-1586.
2. PENETRATION (N-VALUE) IS THE NUMBER OF BLOWS OF 140 LB. HAMMER FALLING 30 IN. REQUIRED TO DRIVE 1.4 IN. I.D. SAMPLER 1 FT.



S & ME, INC.
 840 LOW COUNTRY BOULEVARD
 MT. PLEASANT, SOUTH CAROLINA


PROJECT: AQUARIUM PARKING GARAGE CHARLESTON, SOUTH CAROLINA 1131-97-290		BORING LOG GT-2	
DATE STARTED: 8/12/97		DATE FINISHED: 8/19/97	
DRILLING METHOD: MUD ROTARY			
CASING LENGTH: 8" & 4"/19' & 62'		DRILLER: RICHARD SIMMONS	
WATER LEVEL: WATER AT 2 FEET AT TIME OF DRILLING			
NOTES: GUS-PECH 1000, AUTOMATIC SAFETY HAMMER. 12" BIT FROM 0' TO 19', 4" BIT 19' TO 97'.			

DEPTH (feet)	GRAPHIC LOG	MATERIAL DESCRIPTION	ELEVATION (ft-MSL)	SAMPLE NO./TYPE	STANDARD PENETRATION TEST DATA (blows/ft)	N VALUE
		FILL: SILTY SAND (SM) medium dense, brown, fine; root and brick content				
5		--- very dense; slight brick content, wood in shoe		S-1		22
		--- (SP-SM), medium dense, coarse; brick content		S-2		10/6"
		--- (SM), loose, fine		S-3		11
10		CLAY (CH) very soft, dark gray; slight sand & organic content		S-4		3
		---		S-5		2/24"
		---		S-6		2/24"
		---		S-7		2/18"
		---		S-8		2/24"
		---		S-9		1/24"
20		--- some sand, trace shell hash		S-10		woh
		---		S-11		2
		--- slight sand and marsh grass content		S-12		2/24"
		--- no visible marsh grass		S-13		2/18"
		---		S-14		6
40		SANDY CLAY (CH) firm, dark gray; sand seams, H2S odor		S-15		3
		--- soft, gray and bluish-gray		S-16		12
50		SILTY SAND (SM) medium dense, dark gray, fine; w = 29%, fines = 18%				
		CLAY (CH)				

1. BORING AND SAMPLING IS IN ACCORDANCE WITH ASTM D-1586.
2. PENETRATION (N-VALUE) IS THE NUMBER OF BLOWS OF 140 LB. HAMMER FALLING 30 IN. REQUIRED TO DRIVE 1.4 IN. I.D. SAMPLER 1 FT.




S & ME, INC.
840 LOW COUNTRY BOULEVARD
MT. PLEASANT, SOUTH CAROLINA



1. BORING AND SAMPLING IS IN ACCORDANCE WITH ASTM D-1586.
2. PENETRATION (N-VALUE) IS THE NUMBER OF BLOWS OF 140 LB. HAMMER FALLING 30 IN. REQUIRED TO DRIVE 1.4 IN. I.D. SAMPLER 1 FT.



S & ME, INC.
840 LOW COUNTRY BOULEVARD
MT. PLEASANT, SOUTH CAROLINA



1. BORING AND SAMPLING IS IN ACCORDANCE WITH ASTM D-1586.
2. PENETRATION (N-VALUE) IS THE NUMBER OF BLOWS OF 140 LB. HAMMER FALLING 30 IN. REQUIRED TO DRIVE 1.4 IN. I.D. SAMPLER 1 FT.




S & ME, INC.
840 LOW COUNTRY BOULEVARD
MT. PLEASANT, SOUTH CAROLINA

PROJECT: AQUARIUM PARKING GARAGE CHARLESTON, SOUTH CAROLINA 1131-97-290			BORING LOG GT-3			
DATE STARTED: 8/13/97		DATE FINISHED: 8/20/97		NOTES: GUS-PECH 1000, AUTOMATIC SAFETY HAMMER. 12" BIT FROM 0' TO 8', 4" BIT FROM 8' TO 77'.		
DRILLING METHOD: MUD ROTARY						
CASING LENGTH: 8" & 4"/15' & 62'		DRILLER: RICHARD SEYMONS				
WATER LEVEL: WATER AT 4 FEET AT TIME OF DRILLING						
DEPTH (feet)	GRAPHIC LOG	MATERIAL DESCRIPTION	ELEVATION (ft-MSL)	SAMPLE NO./TYPE	STANDARD PENETRATION TEST DATA (blows/ft)	N VALUE
60		--- loose, fine to coarse; w = 30%	S-13		8	
65		<u>CLAY (CH/MH)</u> stiff, greenish-gray; slight sand content	S-14		9	
70		---	S-15		15	
75		--- soft; sandy, some shell content	S-16		4	
		--- no visible shell hash	S-17		6	
		<u>COOPER GROUP: SILTY SAND (SM)</u> loose, olive, fine; calcareous <u>BORING TERMINATED AT 77 FEET</u>				

1. BORING AND SAMPLING IS IN ACCORDANCE WITH ASTM D-1586.
2. PENETRATION (N-VALUE) IS THE NUMBER OF BLOWS OF 140 LB. HAMMER FALLING 30 IN. REQUIRED TO DRIVE 1.4 IN. I.D. SAMPLER 1 FT.



S & ME, INC.
840 LOW COUNTRY BOULEVARD
MT. PLEASANT, SOUTH CAROLINA



1. BORING AND SAMPLING IS IN ACCORDANCE WITH ASTM D-1586.
2. PENETRATION (N-VALUE) IS THE NUMBER OF BLOWS OF 140 LB. HAMMER FALLING 30 IN. REQUIRED TO DRIVE 1.4 IN. I.D. SAMPLER 1 FT.



S & ME, INC.
840 LOW COUNTRY BOULEVARD
MT. PLEASANT, SOUTH CAROLINA

PROJECT: AQUARIUM PARKING GARAGE CHARLESTON, SOUTH CAROLINA 1131-97-290		BORING LOG GT-4	
DATE STARTED: 8/14/97		DATE FINISHED: 8/21/97	
DRILLING METHOD: MUD ROTARY			
CASING LENGTH: 8" & 4"/15' & 62'		DRILLER: RICHARD SIMMONS	
WATER LEVEL: WATER AT 1.5 FEET AT TIME OF DRILLING			
DEPTH (feet)	GRAPHIC LOG	MATERIAL DESCRIPTION	STANDARD PENETRATION TEST DATA (blows/ft)
			0 10 20 30 60 80
60		medium dense, gray, medium to coarse; trace phosphate nodules	S-14
65		<u>CLAY (CH/MH)</u> firm, greenish-gray; some sand content, slight shell content	S-15
70		--- soft; some shell content, w = 53%	S-16
75		--- stiff; slight sand content, no visible shell content	S-17
80		--- firm	S-18
85		<u>SILTY SAND (SM)</u> loose, dark bluish-gray, fine; slight clay content	S-19
90		<u>COOPER GROUP: SANDY SILT (MH)</u> surf, olive; calcareous	S-20
95		--- hard; sand seams, PP = 3.0	S-21
		--- stiff; no sand seams <u>BORING TERMINATED AT 97 FEET</u>	S-22
			N VALUE
			16
			5
			4
			9
			6
			7
			10
			35
			10

1. BORING AND SAMPLING IS IN ACCORDANCE WITH ASTM D-1586.
2. PENETRATION (N-VALUE) IS THE NUMBER OF BLOWS OF 140 LB. HAMMER FALLING 30 IN. REQUIRED TO DRIVE 1.4 IN. I.D. SAMPLER 1 FT.



S & ME, INC.
 840 LOW COUNTRY BOULEVARD
 MT. PLEASANT, SOUTH CAROLINA

PROJECT: AQUARIUM PARKING GARAGE CHARLESTON, SOUTH CAROLINA 1131-97-290			BORING LOG GT-5			
DATE STARTED: 8/14/97		DATE FINISHED: 8/21/97		NOTES: GUS-PECH 1000, AUTOMATIC SAFETY HAMMER. 12" BIT FROM 0' TO 10', 4" BIT FROM 10' TO S2'.		
DRILLING METHOD: MUD ROTARY						
CASING LENGTH: 8" & 4"/15' & 63'		DRILLER: RICHARD SIMMONS				
WATER LEVEL: WATER AT 2 FEET AT TIME OF DRILLING						
DEPTH (feet)	GRAPHIC LOG	MATERIAL DESCRIPTION	ELEVATION (ft-MSL)	SAMPLE NO./TYPE	STANDARD PENETRATION TEST DATA (blows/ft)	N VALUE
				0	10 20 30 60 80	
		<u>FILL: SANDY CLAY (CH)</u> firm, yellowish-brown, gray and brown; slight root content		S-1		6
		<u>FILL: CLAYEY GRAVEL (GP)</u> loose, black, fine to medium; slight organic content, strong odor		S-2		7
5		<u>FILL: SANDY CLAY (CH)</u> firm, dark gray and gray; brick content		S-3		7
		<u>CLAY (CH)</u> firm, dark gray; slight sand, brick, shell and wood content --- very soft; slight sand and wood content		S-4		6
10				S-5		2/18"
		--- some sand and shell hash		S-6		woh
20		---		S-7		woh
		--- slight sand content, w = 96%		S-8		woh
25		---		S-9		woh
30		---		S-10		2/24"
		<u>VERY CLAYEY SAND (SC/CH)</u> very loose, dark bluish-gray, fine		S-11		3
45		--- loose		S-12		6
		<u>CLAY (CH)</u> firm, dark greenish-gray; slight fine sand content		S-13		7
50		<u>SAND (SP/SP-SM)</u>				

1. BORING AND SAMPLING IS IN ACCORDANCE WITH ASTM D-1586.
2. PENETRATION (N-VALUE) IS THE NUMBER OF BLOWS OF 140 LB. HAMMER FALLING 30 IN. REQUIRED TO DRIVE 1.4 IN. I.D. SAMPLER 1 FT.



S & ME, INC.
840 LOW COUNTRY BOULEVARD
MT. PLEASANT, SOUTH CAROLINA

PROJECT: AQUARIUM PARKING GARAGE CHARLESTON, SOUTH CAROLINA 1131-97-290			<h2 style="margin: 0;">BORING LOG GT-5</h2>			
DATE STARTED: 8/14/97		DATE FINISHED: 8/21/97		NOTES: GUS-PECH 1000, AUTOMATIC SAFETY HAMMER, 12" BIT FROM 0' TO 10', 4" BIT FROM 10' TO 82'.		
DRILLING METHOD: MUD ROTARY						
CASING LENGTH: 8" & 4"/15' & 63'		DRILLER: RICHARD SIMMONS				
WATER LEVEL: WATER AT 2 FEET AT TIME OF DRILLING						
DEPTH (feet)	GRAPHIC LOG	MATERIAL DESCRIPTION	ELEVATION (ft-MSL)	SAMPLE NO./TYPE	STANDARD PENETRATION TEST DATA (blows/ft)	N VALUE
		dense, gray, medium to coarse; trace phosphate nodules		S-14		45
60		<u>CLAY (CH/MH)</u> stiff, greenish-gray; slight sand and shell hash, w = 49%, LL = 86, PI = 37		S-15		9
65		--- (CH/SC), very sandy		S-16		9
70		---		S-17		9
75		--- firm		S-18		7
80		<u>COOPER GROUP: VERY SILTY SAND (MH/SM)</u> medium dense, olive, fine; calcareous		S-19		14
		<u>BORING TERMINATED AT 82 FEET</u>				

1. BORING AND SAMPLING IS IN ACCORDANCE WITH ASTM D-1586.
2. PENETRATION (N-VALUE) IS THE NUMBER OF BLOWS OF 140 LB. HAMMER FALLING 30 IN. REQUIRED TO DRIVE 1.4 IN. I.D. SAMPLER 1 FT.



S & ME, INC.
 840 LOW COUNTRY BOULEVARD
 MT. PLEASANT, SOUTH CAROLINA

PROJECT: AQUARIUM PARKING GARAGE CHARLESTON, SOUTH CAROLINA 1131-97-290		BORING LOG GT-6		
DATE STARTED: 8/13/97		DATE FINISHED: 8/20/97		
DRILLING METHOD: MUD ROTARY		NOTES: GUS-PECH 1000, AUTOMATIC SAFETY HAMMER. 12" BIT FROM 0' TO 12'. 4" BIT FROM 15' TO 92'.		
CASING LENGTH: 12" & 4"/15' & 57'	DRILLER: RICHARD SIMMONS			
WATER LEVEL: WATER AT 2 FEET AT TIME OF DRILLING				

DEPTH (feet)	GRAPHIC LOG	MATERIAL DESCRIPTION	ELEVATION (ft-MSL)	SAMPLE NO./TYPE	STANDARD PENETRATION TEST DATA (blows/ft)	N VALUE
					0 10 20 30 60 80	
		FILL: SILTY SAND (SM) loose, dark brown, fine; root content, odor --- medium dense		S-1	●	7
5		---		S-2	●	13
		---		S-3	●	21
10		--- loose; clay lenses, brick and gravel content, slight odor --- No Recovery		S-4	●	9
		CLAY (CH) very soft, dark gray; slight shell content		S-5	●	2/18"
15		---		S-6	●	2/24"
		--- slight sand and shell content		S-7	●	woh
20		3" x 30" Shelby Tube Pushed 18' to 20', 24" Recovery, w = 126%, fines = 94%, LL = 147, PI = 107		UD		
		--- slight sand and marsh grass content		S-8	●	woh
25		---		S-9	●	woh
30		---		S-10	●	woh
		--- w = 73%				
35		CLAY (CH) stiff, bluish-gray; slight sand content, PP = 1.5		S-11	●	12
40		SLIGHTLY SILTY SAND (SP-SM) medium dense, gray and bluish-gray, fine; clay lenses		S-12	●	27
45		SAND (SP) dense, gray, medium to coarse; trace phosphate nodules		S-13	●	43
50		VERY CLAYEY SAND (SC/CH) loose, greenish-gray, fine; trace shell content		S-14	●	6
		VERY SANDY CLAY (CH/SC)				

1. BORING AND SAMPLING IS IN ACCORDANCE WITH ASTM D-1586.
2. PENETRATION (N-VALUE) IS THE NUMBER OF BLOWS OF 140 LB. HAMMER FALLING 30 IN. REQUIRED TO DRIVE 1.4 IN. I.D. SAMPLER 1 FT.



S & ME, INC.
840 LOW COUNTRY BOULEVARD
MT. PLEASANT, SOUTH CAROLINA

PROJECT: AQUARIUM PARKING GARAGE CHARLESTON, SOUTH CAROLINA 1131-97-290			<h2 style="margin: 0;">BORING LOG GT-6</h2>			
DATE STARTED: 8/13/97		DATE FINISHED: 8/20/97		NOTES: GUS-PECH 1000, AUTOMATIC SAFETY HAMMER, 12" BIT FROM 0' TO 12', 4" BIT FROM 15' TO 92'.		
DRILLING METHOD: MUD ROTARY						
CASING LENGTH: 12" & 4"/15' & 57'		DRILLER: RICHARD SIMMONS				
WATER LEVEL: WATER AT 2 FEET AT TIME OF DRILLING						
DEPTH (feet)	GRAPHIC LOG	MATERIAL DESCRIPTION	ELEVATION (ft-MSL)	SAMPLE NO./TYPE	STANDARD PENETRATION TEST DATA (blows/ft)	N VALUE
					0 10 20 30 60 80	
	[diagonal lines]	firm, greenish-gray; slight shell content, PP = 1.5		S-15	•	6
60	[horizontal lines]	<u>VERY SILTY SAND (SM/MH)</u> loose, dark gray, fine; some clay content, slight shell hash		S-16	•	7
65	[diagonal lines]	<u>SANDY CLAY (CH/MH)</u> firm, dark bluish-gray; PP = 1.0		S-17	•	8
70	[cross-hatch]	<u>SILTY SAND (SM)</u> medium dense, dark bluish-gray, fine; slight clay content		S-18	•	17
75	[diagonal lines]	<u>CLAY (CH)</u> firm, dark bluish-gray; slight sand content, sand lenses, PP = 1.0		S-19	•	7
80	[cross-hatch]	<u>COOPER GROUP: SANDY SILT (MH)</u> soft, olive; calcareous, PP = 1.75		S-20	•	12
85	[cross-hatch]	--- firm; PP = 1.25		S-21	•	8
90	[cross-hatch]	--- stiff; PP = 1.25 <u>BORING TERMINATED AT 92 FEET</u>		S-22	•	10

1. BORING AND SAMPLING IS IN ACCORDANCE WITH ASTM D-1586.
2. PENETRATION (N-VALUE) IS THE NUMBER OF BLOWS OF 140 LB. HAMMER FALLING 30 IN. REQUIRED TO DRIVE 1.4 IN. I.D. SAMPLER 1 FT.



S & ME, INC.
 840 LOW COUNTRY BOULEVARD
 MT. PLEASANT, SOUTH CAROLINA

FIELD TESTING PROCEDURES

Soil Classifications

Soil classifications provide a general guide to the engineering properties of various soil types and enable the engineer to apply his past experience to current problems. In our exploration, samples obtained during drilling operations are examined and visually classified according to color, texture, and relative density or consistency (based on standard penetration resistance). The consistency and relative density designations are as follows:

SANDS		SILTS AND CLAYS	
N(SPT)	Relative Density	N(SPT)	Consistency
0 - 4	Very Loose	0 - 2	Very Soft
5 - 10	Loose	3 - 4	Soft
11 - 30	Medium Dense	5 - 8	Firm
		9 - 15	Stiff
31 - 50	Dense	16 - 30	Very Stiff
50+	Very Dense	31 - 50	Hard
		50+	Very Hard

Soil Test Borings

All boring and sampling operations were conducted in accordance with ASTM Designation D-1586. Initially, the borings were advanced by either mechanically augering or wash boring through the soils. Where necessary, a heavy drilling fluid is used below the water table to stabilize the side and bottom of the drill hole. At regular intervals soil samples were obtained with a standard 1.4-inch I.D., 2-inch O.D., split-barrel sampler. The sampler was first seated 6 inches to penetrate any loose cuttings and then driven an additional foot with blows of a 140 pound hammer falling 30 inches. The number of hammer blows required to drive the sampler the final foot is designated the "Standard Penetration Resistance". The penetration resistance, when properly evaluated, is an index to the soil strength.

Undisturbed Sampling

The split-barrel samples obtained during the penetration testing are available for visual examination and routine classification tests, but are not sufficiently intact for more quantitative laboratory testing. Consequently, undisturbed samples were obtained by forcing 30-inch long, 3-inch O.D. thin walled steel tube into the soil at the desired sampling level. This sampling procedure is described by ASTM Specification D-1587. After removing the sampler from the borehole, the ends are scraped to remove loose soils and sealed with microcrystalline wax. The undisturbed samples were then returned to the laboratory for testing.

September 15, 1997


SOIL DATA SUMMARY

Job No. 1131-97-290

Aquarium Parking Garage

[illegible]

CONSOLIDATION TEST REPORT



Coefficients of Consolidation and Secondary Consolidation

No.	Load (ksf)	C_v (ft.2/day)	C_α	No.	Load (ksf)	C_v (ft.2/day)	C_α	No.	Load (ksf)	C_v (ft.2/day)	C_α
1	0.10	0.01	0.002	11	0.10	0.00					
2	0.25	0.05	0.006								
3	0.50	0.02	0.011								
4	1.00	0.01	0.022								
5	2.00	0.01	0.029								
6	4.00	0.01	0.021								
7	8.00	0.01	0.020								
8	16.00	0.01	0.035								
9	4.00	0.06									
10	1.00	0.01									

Natural		Dry Dens. (pcf)	LL	Pl	Sp. Gr.	Overburden (ksf)	P_c (ksf)	C_c	C_r	Swell Press. (ksf)	Swell %	e_o
Sat.	Moist.											
149.3 %	125.9 %	51.3	147.1	106.5	2.68		0.66	1.08				2.261

MATERIAL DESCRIPTION

USCS

AASHTO

Project No. 1151-97-290 Client:

Project: Aquarium Parking Garage

Source: Boring GT-6

Sample No.: 1

Elev./Depth: 18 ft. to 20 f.

Remarks:

94.1% Passing #200 Sieve

CONSOLIDATION TEST REPORT

S & ME, Inc.

Figure 1

Dial Reading vs. Time





Project No.: 1131-97-290

Project: Aquarium Parking Garage

Source: Boring GT-6

Sample No.: 1

Elev./Depth: 18 ft. to 20 f.



Dial Reading vs. Time
S & ME, Inc.

Figure 2

Dial Reading vs. Time





Project No.: 1131-97-290

Project: Aquarium Parking Garage

Source: Boring GT-6

Sample No.: 1

Elev./Depth: 13 ft. to 20 f.



Dial Reading vs. Time
S & ME, Inc.

Figure 3

Dial Reading vs. Time




Project No.: 1131-97-290

Project: Aquarium Parking Garage

Source: Boring GT-6

Sample No.: 1

Elev./Depth: 18 ft. to 20 f.



Dial Reading vs. Time

S & ME, Inc.

Figure 4

CONSOLIDATION TEST DATA

Client:
Project: Aquarium Parking Garage
Project Number: 1131-97-290

Sample Data

Source: Boring GT-6
Sample No.: 1
Elev. or Depth: 13 ft. to 20 f. Sample Length (in./cm.): 1
Location:
Description:
Liquid Limit: 147.1 Plasticity Index: 106.5
USCS: AASHTO: Figure No.: 1
Testing Remarks: 94.1% Passing #200 Sieve

Test Specimen Data

TOTAL SAMPLE	BEFORE TEST	AFTER TEST
Wet w+t = 30.50 g.	Consolidometer # = 1	Wet w+t = 188.16 g.
Dry w+t = 13.50 g.		Dry w+t = 155.68 g.
Tare Wt. = .00 g.	Spec. Gravity = 2.66	Tare Wt. = 109.75 g.
Height = 1.00 in.	Height = 1.00 in.	
Diameter = 2.50 in.	Diameter = 2.50 in.	
Weight = 149.35 g.	Defl. Table = n/a	
Moisture = 125.9 %	Ht. Solids = 0.3066 in.	Moisture = 70.7 %
Wet Den. = 115.9 pcf	Dry Wt. = 66.11 g.*	Dry Wt. = 45.93 g.
Dry Den. = 51.3 pcf	Void Ratio = 2.261	Void Ratio = 0.973
	Saturation = 149.3 %	

* Initial dry weight used in calculations

End-of-Load Summary

Pressure (ksf)	Final Dial (in.)	Machine Defl. (in.)	C_v (ft. ² /day)	C_α	Void Ratio	% Compression /Swell
start	0.00000				2.261	
0.10	0.00650	0.00000	0.01	0.002	2.240	0.7 Compr.
0.25	0.02935	0.00000	0.05	0.006	2.165	2.9 Compr.
0.50	0.06760	0.00000	0.02	0.011	2.041	6.8 Compr.
1.00	0.14000	0.00000	0.01	0.022	1.805	14.0 Compr.
2.00	0.24410	0.00000	0.01	0.029	1.465	24.4 Compr.
4.00	0.34170	0.00000	0.01	0.021	1.147	34.2 Compr.
8.00	0.42730	0.00000	0.01	0.020	0.866	42.7 Compr.
16.00	0.48220	0.00000	0.01	0.035	0.689	48.2 Compr.
4.00	0.46720	0.00000	0.06		0.733	46.7 Compr.
1.00	0.44390	0.00000	0.01		0.797	44.9 Compr.
0.10	0.39490	0.00000	0.00		0.973	39.5 Compr.

$C_c = 1.08$ $P_c = 0.66$ ksf

LABORATORY TESTING PROCEDURES

Moisture-Density Relationship (Modified Proctor) (ASTM D-1557)

Bulk samples of near surface soils were tested to determine moisture-density characteristics by the "modified" method using a 10-lb. hammer and 18 inch drop. The tests determine maximum dry density and optimum moisture content. Test results are graphically presented in the form of dry density versus moisture content on the Compaction Test sheets included in the Appendix.

Laboratory California Bearing Ratio (CBR) Tests (ASTM D-1883)

The California Bearing Ratio, usually abbreviated as CBR, is a punching shear test. The CBR value is a semi-empirical index of the soil strength and deflection characteristics and has been correlated with pavement performance to establish design curves for pavement thickness. The test was performed on 6-inch diameter, 5-inch thick discs of compacted soil, confined in a steel cylinder. The specimens were then soaked for 72 hours prior to testing. A piston approximately 2-inches in diameter was then forced into the soils at a standard rate to determine the resistance to penetration. The CBR is the ratio, expressed as a percentage, of the actual load required to produce a 0.1 inch deflection to the load required for the same deflection in a standard crushed stone sample. The results of the CBR tests are given on the CBR Test sheets included in the Appendix.

Grain Size Tests (ASTM D-1140 and ASTM D-422)


Grain size tests were performed to determine the soil particle size distribution. The amount of material finer than the #200 sieve was determined by washing the sample over that particular size sieve. The grain size distribution of the soil retained on the #200 sieve was then determined by passing the retained portion through a standard set of nested sieves.

Atterberg Limits Test (ASTM D-4318)

Atterberg Limits tests were performed to determine the soil plasticity characteristics. The soil plasticity index (PI) is representative of this characteristic and is bracketed by the liquid limit (LL) and the plastic limit (PL). The liquid limit is the moisture content at which the soil will flow as a heavy viscous fluid. The plastic limit is the moisture content at which the soil begins to lose its plasticity. The difference between the liquid limit and plastic limit is the plasticity index.

Moisture Content Test (ASTM D-2216)

Moisture content tests were conducted to determine the ratio, expressed as a percentage, of the weight of water in a given amount of soil to the weight of the solid particles.



Job No : 1131-97-290

Date: 19 September 1997

Scale: N.T.S.



Settlement Plate Detail
 Aquarium Parking Garage
 Charleston, South Carolina

Figure No :

A-3